

Redacted

**Site Inspection Report
for
Nethery Landfill
Dallas, Dallas County, Texas**

Contract No.: 68-W6-0013
TDD No.: S06-99-03-0001
PAN: 080801SIXX

NOVEMBER 1999

Prepared for:

**UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
Region 6
1445 Ross Avenue
Dallas, Texas**



ecology and environment, inc.

International Specialists in the Environment

1999 Bryan Street, Dallas, Texas 75201

Tel: (214) 245-1000, Fax: (214) 245-1001

152313



Table of Contents

| <u>Section</u> | <u>Page</u> |
|---|-------------|
| 1 Introduction | 1-1 |
| 1.1 Site Inspection Objectives | 1-1 |
| 2 Site Background | 2-1 |
| 2.1 Site Location and Description | 2-1 |
| 2.2 Ownership and Operational History | 2-1 |
| 2.3 Regulatory Status/Activities | 2-2 |
| 2.4 Previous Investigations | 2-2 |
| 2.5 Source Waste Characterization | 2-2 |
| 3 Investigation Methodology | 3-1 |
| 3.1 Site-Specific Objectives | 3-1 |
| 3.2 Sample Methodology | 3-1 |
| 3.2.1 Source Samples | 3-2 |
| 3.2.2 Sediment Samples | 3-2 |
| 3.3 Non-Sampling Data Collection Methodology | 3-2 |
| 3.4 Emergency Response/Removal Sampling Actions | 3-3 |
| 4 Investigation Results | 4-1 |
| 4.1 Previous Analytical Results | 4-1 |
| 4.2 Site Inspection Analytical Data Results | 4-1 |
| 4.2.1 Source Samples | 4-2 |
| 4.2.2 Sediment Samples | 4-2 |
| 5 Pathway Assessment | 5-1 |
| 5.1 Ground water Pathway | 5-1 |
| 5.1.1 Ground water Characteristics | 5-1 |
| 5.1.2 Ground Water Receptors | 5-2 |

Table of Contents (Cont.)

CERCLIS #: TX0000605190

| <u>Section</u> | <u>Page</u> |
|---|-------------|
| 5.2 Surface Water Pathway | 5-2 |
| 5.2.1 Surface Water Characteristics | 5-2 |
| 5.2.2 Surface Water Receptors | 5-2 |
| 5.3 Ground Water to Surface Water Pathway | 5-3 |
| 5.4 Soil Exposure Pathway | 5-3 |
| 5.4.1 Resident Threat Receptors | 5-3 |
| 5.4.2 Nearby Threat Receptors | 5-4 |
| 5.5 Air Pathway | 5-4 |
| 5.5.1 Air Pathway Characteristics | 5-4 |
| 5.5.2 Air Receptors | 5-4 |
| 6 Project Management | 6-1 |
| 6.1 Key Personnel | 6-1 |
| 6.2 Community Relations | 6-1 |
| 7 Summary | 7-1 |
| 8 References | 8-1 |
| <u>Appendix</u> | |
| A Photodocumentation | A-1 |
| B Chain-of-Custody Documentation | B-1 |
| C TDD (Original and Amendments A and B) | C-1 |
| D Photo Negatives (in START file only) | D-1 |

List of Tables

| <u>Table</u> | <u>Page</u> |
|---|-------------|
| 3-1 Site Inspection Samples | 3-4 |
| 4-1 Source Soil Samples Metals Analysis | 4-3 |
| 4-2 Source Soil Samples Semivolatile Analysis | 4-4 |
| 4-3 Sediment Samples Metals Analysis | 4-5 |
| 4-4 Sediment Samples Semivolatile Analysis | 4-7 |
| 4-5 Sediment Samples Pesticide Analysis | 4-13 |

List of Illustrations

| <u>Figure</u> | | <u>Page</u> |
|---------------|---------------------------|-------------|
| 1 | Site Location Map | 2-4 |
| 2 | Site Sketch | 2-5 |
| 3 | Sample Location Map | 3-7 |

List of Acronyms

| | |
|---------|--|
| BNAs | Base Neutral Acids |
| CERCLIS | Comprehensive Environmental Response, Compensation, and Liability Information System |
| cfs | cubic feet per second |
| CID | Criminal Investigation Division |
| CLP | Contract Laboratory Program |
| COC | chain-of-custody |
| E & E | Ecology and Environment, Inc. |
| EPA | United States Environmental Protection Agency |
| ESI | Expanded Site Inspection |
| HRS | Hazard Ranking System |
| ISE | imminent and substantial endangerment |
| NFRAP | No Further Remedial Action Planned |
| NPDES | National Pollution Discharge Elimination System |
| NPL | National Priorities List |
| NWI | National Wetlands Inventory |
| PAH | polynuclear aromatic hydrocarbons |
| PCBs | polychlorinated biphenyls |
| ppb | parts per billion |
| PPE | Probable Point of Entry |
| SAM | Site Assessment Manager |
| SARA | Superfund Amendments and Reauthorization Act |
| SI | Site Inspection |
| SQL | sample quantitation limit |
| START | Superfund Technical Assessment and Response Team |
| TAL | Target Analyte List |
| TCL | Target Compound List |
| TDL | target distance limit |
| TNRCC | Texas Natural Resource Conservation Commission |
| TPH | total petroleum hydrocarbons |
| VOA | volatile organics analyses |
| VOC | volatile organic compounds |

1**Introduction**

Pursuant to Contract No. 68-W6-0013, Ecology and Environment, Inc. (E & E), the Region 6 Superfund Technical Assessment and Response Team (START) contractor, was tasked by the United States Environmental Protection Agency (EPA) to conduct a Site Inspection (SI) at the Nethery Landfill site (CERCLIS # TX0000605190), located in Dallas, Dallas County, Texas.

1.1 Site Inspection Objectives

An SI is the initial sampling stage associated with the EPA site assessment process. An SI is performed to characterize a site identified on Comprehensive Environmental Response, Compensation, and Liability Information System (CERCLIS) through the use of Hazard Ranking System (HRS) documentation and to evaluate the site for imminent and substantial endangerment (ISE) conditions and removal potential. An SI includes the collection and analysis of target data, environmental samples, and other data required for the completion of an HRS PREScore. Data obtained during the SI are used to determine whether a CERCLIS site warrants one of the following actions according to the Superfund Amendments and Reauthorization Act (SARA):

- An additional removal action;
- An Expanded Site Inspection (ESI);
- An HRS scoring package for proposal to the National Priorities List (NPL); or
- A No Further Remedial Action Planned (NFRAP) designation.

2**Site Background**

2.1 Site Location and Description

The Nethery Landfill is located at 500 Deepwood Street in Dallas, Dallas County, Texas (Ref. 11). The landfill occupies approximately 84 acres and is bordered by a residential neighborhood to the north, the Woodland Springs Park to the east, the Trinity River and McCommas Bluff Park to the south, and non-operational quarry land to the west. The nearest residents are located approximately 250 feet north of the landfill. An apartment complex is north of the intersection of Jim Miller Road and Gayglen Drive (Figures 1 and 2). The geographic coordinates of the site are 30°42' 29.66" north latitude and 96°42' 6.07" west longitude as measured from Etak, Inc. software (Ref. 14).

The inactive and abandoned landfill can be divided into three primary areas: the North Disposal Area, the South Side, and the West Side (Figure 2). The North Disposal Area contains the majority of the debris and comprises approximately 35 acres with waste reaching a depth of 20 to 30 feet. The waste has not been covered by soil or any other material. The South Side consists of low-lying areas not utilized in the day to day operations of the facility and comprises approximately 24 acres. The West Side, approximately 25 acres, consists of low-lying areas and had limited use as a disposal area (Ref. 5).

2.2 Ownership and Operational History

The site was an unlicensed and unpermitted landfill, owned by Mr. Herman Nethery and operated by Mr. Herman Gibbons (Ref. 18). Nethery Landfill received approximately two million cubic feet of primarily construction materials since August 1994, when it began operations (Ref. 18). In August 1996, the EPA issued a cease-and-desist order, which closed the landfill, because of the possible migration of surface water runoff from the landfill to the Trinity

River (Ref. 16). There are no manifests or records of wastes that the landfill received. There are documented episodes of illegal dumping of unknown materials at night (Ref. 16).

2.3 Regulatory Status/Activities

Specific "Industrial Activities" are required to have a National Pollution Discharge Elimination System (NPDES) Storm Water permit and a Storm Water Pollution Prevention Plan to ensure that storm water runoff will not impact water quality. Nethery Landfill did not have NPDES permit or any other permits authorizing landfill operations (Ref. 18).

2.4 Previous Investigations

The City of Dallas took civil action against Mr. Nethery, the site owner, in 1996. In June 1996, the Texas Natural Resource Conservation Commission (TNRCC) and the EPA-Criminal Investigation Division (CID) began to investigate the landfill operations for possible criminal intent. On September 13, 1996, TNRCC and EPA-CID conducted an inspection at the landfill. The inspectors observed a smoldering area within the landfill and the START contractor responded to the fire, conducted air monitoring, and documented site conditions. Air monitoring equipment was used to test for volatile organic compounds (VOCs), cyanide, hydrogen sulfide, phosgene, and radiation. Air monitoring results did not indicate the presence of these contaminants at concentrations greater than background levels (Ref. 17). The landfill burned for approximately seven months, from September 1996 through March 1997 (Ref. 17). Sampling was also conducted by TNRCC and City of Dallas. The analytical results are discussed in Section 4.1.


2.5 Source Waste Characterization

The North Disposal Area is the source of contamination. This area contains the portion of the landfill which occupies approximately 35 acres and has a waste thickness of 20 to 30 feet in some areas (Ref. 5).


Topographic maps show the landfill is located on land which was previously used as a gravel pit and was bordered by a levee on the south side (Ref. 19). There is no documentation or evidence that a liner, leachate collection system, run-off control system, or monitoring wells were installed at the source (Ref. 15). There is no containment of the waste or cover to the landfill (Appendix A). The majority of the property is fenced or contains barriers to access, but a

portion of the fencing on the north side of the North Disposal Area is missing. This section is adjacent to the nearest residences approximately 250 feet to the north, and allows for easy access by foot (Appendix A).

Hazardous substances associated with the landfill include copper and polynuclear aromatic hydrocarbons (PAHs). The analytical results of the samples characterizing the landfill are discussed in Section 4.2.1.



SCALE 1:24 000



CONTOUR INTERVAL 10 FEET



QUADRANGLE LOCATION


ecology and environment, inc.
 Superfund Technical Assessment
 & Response Team - Region 6

CERCLIS/CASE No. Tx000605190

TDD No. S06-99-03-0001

SOURCE: U.S.G.S. 7.5 MIN. TOPOGRAPHIC QUADRANGLES
 HUTCHINS, TEXAS - 1958

FIGURE 1
SITE LOCATION MAP
NETHERY LANDFILL
DALLAS, TEXAS



LEGEND

CATTAILS

TREES

OVERFLOW

ecology and environment, inc.
 Superfund Technical Assessment
 & Response Team - Region 6

FIGURE 2 SITE SKETCH
 NETHERY LANDFILL
 DALLAS, DALLAS COUNTY, TEXAS

TDD# 06-99-03-0001

Date: JULY 23, 1999

PAN 080801SIXX

P.M.: M. BROWN

3

Investigation Methodology

3.1 Site-Specific Objectives

The objectives of the SI performed at the Nethery Landfill site were to:

- Obtain sufficient HRS-quality analytical data to characterize the site;
- Determine whether surface water exposure target receptors have been adversely impacted by contaminants at the site;
- Obtain additional non-sampling data for source characterization and pathway evaluation; and
- Determine whether contamination is present at the site at concentrations that pose a health risk to residents or future occupants.

3.2 Sample Methodology

To meet the objectives of this investigation, START performed judgmental sampling to characterize potential contaminants associated with the site. From August 10 to 12, 1999, 19 samples were collected by START, including surface soil, sediment, and field duplicates. All surface and sediment samples were collected with cleaned stainless-steel trowels. All samples were sent to designated Contract Laboratory Program (CLP) laboratories and were analyzed for Target Compound List (TCL) volatiles, TCL semivolatiles, TCL pesticides, polychlorinated biphenyls (PCBs), and Target Analyte List (TAL) metals using CLP protocols (Ref. 21). All samples were cooled to 4°C with bagged ice placed in the shipping coolers and were shipped for overnight delivery to the designated CLP laboratory using Federal Express. Inorganic and

organic traffic reports and chain-of-custody (COC) forms are presented in Appendix B. All field activities were documented using sample tags/labels, daily logs, field notebooks, photographic documentation, and COC procedures (Appendix D). Figure 3 is a map of sample locations.

3.2.1 Source Samples

Four grab surface (0 to 6 inches) soil samples, including a duplicate and a background, were collected from the North Disposal Area landfill. One sample was collected from the north end of the landfill close to the east pond (SS-01) (Figure 3). Another sample and its duplicate were collected at the south end of the landfill west of the west trench and close to the southern overflow (SS-02 and 03). The background sample was taken across the street from the apartments located north of the site (SS-04). All of the samples were analyzed for TCL volatiles, TCL semivolatiles, TCL pesticides, PCBs, and TAL metals under EPA's CLP statement of work (Table 3-1) (Ref. 21).

3.2.2 Sediment Samples

Fifteen sediment samples, including a duplicate and background, were collected at the overflows and surface water pathways during the SI field activities. Three samples were collected from the pond east of the North Disposal Area (SD-01, 02, and 03). Two samples were collected from the overflow at the south end of the pond (SD-04 and 05). Three samples and a duplicate were collected from Elam Creek (SD-06, 07, 08, and 09). These samples were collected at approximately 200-foot intervals beginning at the first Probable Point of Entry (PPE 1). Five samples were collected from the overflow south of the North Disposal Area (SD-11, 12, 13, 14, and 15). These samples were collected at approximately 100-foot intervals beginning at the landfill and continuing to PPE 2. The background sample was taken from Elam Creek north of the site (SD-10). All of the samples were analyzed for TCL volatiles, TCL semivolatiles, TCL pesticides, PCBs, and TAL metals under EPA's CLP statement of work (Table 3-1) (Ref. 21).

3.3 Non-Sampling Data Collection Methodology

Non-sampling data collected during the course of the SI included source dimensions and containment structures; site terrain, soil and vegetation; population counts; surface water targets; and wetland frontage. This information will be discussed in the appropriate sections.

3.4 Emergency Response/Removal Sampling Actions

No actual or potential exposure to nearby humans, animals, or food chain from hazardous substances, pollutants, or contaminants was noted during the START SI field activities. No imminent and substantial endangerment (ISE) conditions such as potential to fire or explosion were observed. No additional sampling was conducted in support of removal actions or for removal considerations at the Nethery Landfill site.

Table 3-1
August 1999
Site Inspection Samples
Nethery Landfill
Dallas, Dallas County, Texas

| Station No. | CLP Sample No. | Matrix | Destination | Location/Rationale |
|-------------|-------------------|----------|---------------------------|---|
| SS-01 | FC-X38 MFJ-S80 | Soil | CLP designated laboratory | Source soil sample collected north of the east trench in the North Disposal Area. <u>Rationale:</u> This sample will serve to characterize the contents of the landfill. <u>Depth:</u> 0 to 6 inches |
| SS-02 | FC-X39 MFJ-S81 | Soil | CLP designated laboratory | Source soil sample collected southwest of the west trench in the North Disposal Area. <u>Rationale:</u> This sample will serve to characterize the contents of the landfill <u>Depth:</u> 0 to 6 inches |
| SS-03 | FC-X40 MFJ-S82 | Soil | CLP designated laboratory | Duplicate of SS-02. <u>Rationale:</u> To check field and laboratory procedures. <u>Depth:</u> 0 to 6 inches |
| SS-04 | FC-X56 MFJ-S98 | Soil | CLP designated laboratory | Background soil sample collected north of landfill. <u>Rationale:</u> To determine ambient concentrations of organic and inorganic compounds. <u>Depth:</u> 0 to 6 inches |
| SD-01 | FC-X41 MFJ-S83 | Sediment | CLP designated laboratory | Target sediment sample collected from the north end of the pond east of the North Disposal Area. <u>Rationale:</u> To determine if hazardous substances from the landfill have migrated into the pond. |
| SD-02 | FC-X42 MFJ-S84 | Sediment | CLP designated laboratory | Target sediment sample collected from the middle of the pond east of the North Disposal Area. <u>Rationale:</u> To determine if hazardous substances from the landfill have migrated into the pond. |
| SD-03 | FC-X43 MFJ-S85 | Sediment | CLP designated laboratory | Target sediment sample collected from the south end of the pond east of the North Disposal Area. <u>Rationale:</u> To determine if hazardous substances from the landfill have migrated into the pond. |

**Table 3-1
August 1999
Site Inspection Samples
Nethery Landfill
Dallas, Dallas County, Texas**

| Station No. | CLP Sample No. | Matrix | Destination | Location/Rationale |
|-------------|-------------------|----------|---------------------------|---|
| SD-04 | FC-X44 MFJ-S86 | Sediment | CLP designated laboratory | Target sediment sample collected from the overflow at the south end of the east pond. <u>Rationale:</u> To determine if hazardous substances from the pond have migrated to the overflow. |
| SD-05 | FC-X45 MFJ-S87 | Sediment | CLP designated laboratory | Target sediment sample collected near PPE 1 from the overflow into Elam Creek. <u>Rationale:</u> To determine if hazardous substances from the overflow have migrated to Elam Creek. |
| SD-06 | FC-X46 MFJ-S88 | Sediment | CLP designated laboratory | Target sediment sample collected from Elam Creek near PPE 1. <u>Rationale:</u> To determine if hazardous substances have entered an HRS criteria wetland. |
| SD-07 | FC-X47 MFJ-S89 | Sediment | CLP designated laboratory | Target sediment sample collected from Elam Creek downstream of PPE 1. <u>Rationale:</u> To determine if hazardous substances have entered an HRS criteria wetland. |
| SD-08 | FC-X48 MFJ-S90 | Sediment | CLP designated laboratory | Target sediment sample collected from Elam Creek approximately 1,000 feet down stream of PPE 1. <u>Rationale:</u> To determine if hazardous substances have entered an HRS criteria wetland. |
| SD-09 | FC-X49 MFJ-S91 | Sediment | CLP designated laboratory | Duplicate of sample SD-08. <u>Rationale:</u> To check field and laboratory procedures. |
| SD-10 | FC-X50 MFJ-S92 | Sediment | CLP designated laboratory | Background sediment sample collected upstream of the PPE in Elam Creek. <u>Rationale:</u> To determine ambient concentrations of organic compounds and inorganic analytes. |
| SD-11 | FC-X51 MFJ-S93 | Sediment | CLP designated laboratory | Target sediment sample collected from the overflow where the trenches meet south of the North Disposal Area. <u>Rationale:</u> To determine if hazardous substances from the landfill have migrated to the overflow. |

**Table 3-1
August 1999
Site Inspection Samples
Nethery Landfill
Dallas, Dallas County, Texas**

| Station No. | CLP Sample No. | Matrix | Destination | Location/Rationale |
|-------------|-------------------|--------|---------------------------|--|
| SD-12 | FC-X52 MFJ-S94 | Soil | CLP designated laboratory | Target sediment sample collected from the overflow south of the North Disposal Area. <u>Rationale:</u> To determine if hazardous substances have entered the drainage pathway to the Trinity River. |
| SD-13 | FC-X53 MFJ-S95 | Soil | CLP designated laboratory | Target sediment sample collected from the overflow south of the North Disposal Area. <u>Rationale:</u> To determine if hazardous substances have entered the drainage pathway to the Trinity River. |
| SD-14 | FC-X54 MFJ-S96 | Soil | CLP designated laboratory | Target sediment sample collected from the overflow south of the North Disposal Area and dirt road. <u>Rationale:</u> To determine if hazardous substances have entered the drainage pathway to the Trinity River. |
| SD-15 | FC-X55 MFJ-S97 | Soil | CLP designated laboratory | Target sediment sample collected in a dry pond near PPE 2 to the Trinity River from the overflow south of the North Disposal Area. <u>Rationale:</u> To determine if hazardous substances have entered the drainage pathway to the Trinity River. |



SINGLE-FAMILY
RESIDENTIAL
DEVELOPMENT

SINGLE-FAMILY
RESIDENTIAL
DEVELOPMENT

MULTI-FAMILY
RESIDENTIAL
DEVELOPMENT

DEEPWOOD STREET

WESTERN HILLS DRIVE

JIM MILLER ROAD

GAYLEN DRIVE

FACILITY GATE

NORTH DISPOSAL
AREA WASTE PILE

WEST TRENCH

EAST TRENCH

SS02/SS03

SS01

SD01

SD02

POND

SD03

SD04

OVERFLOW

SD05

PPE 1

ELAM CREEK

UNDEVELOPED/WOODLANDS

SD06

SD07

SD15

PPE 2

TRINITY RIVER

UNDEVELOPED/WOODLANDS

TRINITY RIVER

NOT TO SCALE

LEGEND



DRAINAGE DIRECTION

X PROBABLE POINT
OF ENTRY (PPE)



SD08 SEDIMENT
SAMPLE



SS03 SURFACE SOIL
SAMPLE



OVERFLOW



Ecology and environment, inc.
Superfund Technical Assessment
& Response Team - Region 6

FIGURE 3 SAMPLE LOCATION MAP
NETHERY LANDFILL
DALLAS, DALLAS COUNTY, TEXAS

TDD# 06-99-03-0001

Date: JULY 23, 1999

PAN 080801SIXX

P.M.: M. BROWN

4

Investigation Results

4.1 Previous Analytical Results

Areas of the site have been sampled by TNRCC, START, and the City of Dallas-Dallas Water Utilities.

Initial sampling at the landfill was conducted by the TNRCC in late August and early September of 1996. Water and soil samples, from unknown locations, were analyzed for metals, base neutral acids (BNAs), total petroleum hydrocarbons (TPH), total solids, and volatile organics analyses (VOA). Low levels of metals and VOAs were detected in the soil samples analyzed, and all of the samples contained petroleum hydrocarbons (Ref. 22). The BNA results were not available to START.

START performed air monitoring in March of 1997 during the fire at the site which had continued since September 1996. Results showed that all contaminant levels were near or below background levels (Ref. 17).

Also in March 1997, during the fire, the City of Dallas-Dallas Water Utilities analyzed three water samples. The samples were taken upstream of the discharge point from the landfill, at the discharge point from the landfill (effluent), and downstream of the discharge point from the landfill. The location of the discharge point is unknown. Results indicated only the effluent sample contained slightly elevated levels of benzene (7.1 parts per billion [ppb]). The detection limit for benzene is 5.0 ppb (Ref. 23). No other sampling has taken place since March of 1997.

4.2 Site Inspection Analytical Data Results

This section discusses the results of the sampling conducted during the SI. Source soil and sediment samples were collected and analyzed in accordance with methods described in Section 3.

The analyte or compound concentrations, if qualified, were corrected based on their bias (Ref. 24). They were then compared to results obtained from background and sample quantitation limits (SQLs) from each medium after the SQLs were adjusted to reflect any changes which took place in the laboratory's extraction or analytical techniques (Ref. 20, Ref. 25). This was done to determine whether observed contamination or an observed release could be documented. To meet observed release or observed contamination criteria, if the analyte or compound is detected in the background sample, the concentration in the sample must be greater than the SQL and at least three times greater than the concentration detected in the background sample (Ref. 3). If not detected in the background sample, observed release or observed contamination criteria are met if the sample concentration is greater than the sample and background SQLs (Ref. 3). Those analytes or compounds that meet the observed release or observed contamination criteria are highlighted in Tables 4-1 through 4-5.

4.2.1 Source Samples

Source samples were collected from areas close to the leachate or overflows. The results for TAL metals did not indicate the presence of any heavy metals. Copper was detected in one of the samples and its presence may be attributed to the construction debris. This analyte was also present in the background sample (Table 4-1).

The only organic compounds detected in the source samples were from the TCL semivolatiles analysis (Table 4-2). PAHs were detected above SQLs and background levels in two of the source samples. Phenanthrene, fluoranthene, pyrene, benzo(a)anthracene, chrysene, bis(2-Ethylhexyl)phthalate, benzo(k)fluoranthene, benzo(a)pyrene and indeno(1,2,3-cd)pyrene met observed contamination criteria. These compounds are characteristic of burned waste. The landfill burned for approximately seven months, from September 1996 through March 1997 (Ref. 17). The background sample (SS-04) was non-detect at the SQL or below SQL for all organic compounds (Table 4-2).

4.2.2 Sediment Samples

Sediment samples were collected from overflow segments to the surface water and from Elam Creek. The surface water pathway is surrounded by designated wetlands (Ref. 3, Ref. 9). Several of the samples contained low-level metals contamination that met observed release criteria (Table 4-3).

In the TCL semivolatiles analysis, PAHs (phenanthrene, anthracene, carbozole, fluoranthene, pyrene, benzo(a)anthracene, chrysene, benzo(b)fluoranthene, benzo(k)fluoranthene, benzo(a)pyrene, indeno(1,2,3-cd)pyrene, dibenzo(a,h)anthracene and benzo(g,h,i)perylene) met observed release criteria in four of the sediment samples (Table 4-4). As stated above, the presence of these compounds can be attributed to the fire. In the TCL pesticides analysis, one sediment sample contained Dieldrin at a concentration slightly greater than the SQL and three times above the background level (Table 4-5). This compound is not attributable to the source and was most likely a result of local pesticide application.

Table 4-2
Nethery Landfill
Source Soil Samples
Semivolatile Analysis
August 1999

| SAMPLE | SS-04 | | SS-01 | | SS-02 | | SS-03 | |
|----------------------------|-------------------|-----|---------|-----|---------------|-----|--------|-----|
| CLP NO. | FC-X56 | | FC-X38 | | FC-X39 | | FC-X40 | |
| | Background Sample | | | | | | | |
| | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL |
| Phenanthrene | 120 QJK | 302 | 270 QJK | 647 | 410 JK (41) | 312 | 480 | 302 |
| Fluoranthene | 280 QJK | 302 | 580 QJK | 647 | 1200 JK (120) | 312 | 1500 | 302 |
| Pyrene | 250 QJK | 302 | 380 QJK | 647 | 1200 JK (101) | 312 | 1100 | 302 |
| Benzo(a)anthracene | 160 QJK | 302 | 290 QJK | 647 | 640 JK (64) | 312 | 760 | 302 |
| Chrysene | 210 QJK | 302 | 330 QJK | 647 | 710 JK (71) | 312 | 840 | 302 |
| bis(2-Ethylhexyl)phthalate | 330 U | 302 | 800 | 647 | 330 U | 312 | 330 U | 302 |
| Benzo(k)fluoranthene | 140 QJK | 302 | 280 QJK | 647 | 670 JK (67) | 312 | 520 | 302 |
| Benzo(a)pyrene | 180 QJK | 302 | 280 QJK | 647 | 700 JK (70) | 312 | 860 | 302 |
| Indeno(1,2,3-cd)pyrene | 170 QJK | 302 | 230 QJK | 647 | 500 JK (50) | 312 | 580 | 302 |

Key:Conc. = Concentration (given in $\mu\text{g/kg}$)

K = unknown bias

U = analyzed for but not detected

SQL = Sample Quantitation Limit

J = Sample concentration is estimated

Q = Sample concentration is below the sample quantitation limit

() = Adjusted concentration for data utilizing *Using Qualified Data to Document an Observed Release and Observed Contamination* (Ref. 28)

* = Three times background concentration

■ = Concentration meets observed contamination criteria

**Table 4-3
Nethery Landfil
Sediment Samples
Metals Analysis
August 1999**

| SAMPLE | SD-10 | | SD-01 | | SD-02 | | SD-03 | | SD-04 | | SD-05 | | SD-06 | | SD-07 | |
|-----------|-------------------|------|---------|------|---------|------|-------------------|------|----------|------|---------|------|---------|------|-------------------|------|
| CLP NO. | MFJ-S92 | | MFJ-S83 | | MFJ-S84 | | MFJ-S85 | | MFJ-S86 | | MFJ-S87 | | MFJ-S88 | | MFJ-S89 | |
| | Background Sample | | | | | | | | | | | | | | | |
| | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL |
| Barium | 33.2 Q | 48 | 80.2 | 55 | 74.0 | 56.6 | 139 | 54.8 | 43.1 Q | 63.8 | 11.4 Q | 48 | 27.7 Q | 52.2 | 136 | 56.8 |
| Beryllium | 0.07 U | 1.2 | 0.08 U | 1.38 | 0.21Q | 1.42 | 0.08 U | 1.37 | 0.10 U | 1.60 | 0.07 U | 1.2 | 0.08 U | 1.3 | 1.5 | 1.42 |
| Copper | 3.3 UB | 6 | 9.9 | 6.88 | 10.5 | 7.08 | 15.4 | 6.85 | 7.4 QJK | 7.98 | 9.6 | 6 | 6.5 Q | 6.52 | 17.8 | 7.1 |
| Lead | 54.6 163.8* | 0.72 | 31.0 | 0.82 | 36.8 | 0.85 | 780 | 0.82 | 16.6 | 0.96 | 12.5 | 0.72 | 41.3 JK | 0.78 | 57.0 | 0.85 |
| Mercury | 0.06 U | 0.12 | 0.07 U | 0.14 | 0.07 U | 0.14 | 0.18 | 0.14 | 0.08 U | 0.16 | 0.06 U | 0.12 | 0.07 U | 0.13 | 0.07 U | 0.14 |
| Nickel | 8.3 QJK | 9.6 | 13.3 Q | 11 | 18.3 JK | 11.3 | 18.3 JK (14.2) | 1.10 | 12.5 QJK | 12.8 | 6.1 U | 9.6 | 8.0 Q | 10.4 | 25.0 JK (19.4) | 11.4 |
| Vanadium | 18.7 56.1* | 12 | 32.4 | 13.8 | 31.1 | 14.2 | 25.8 | 13.7 | 24.1 | 16 | 14.1 | 12 | 21.7 | 13 | 59.3 | 14.2 |

Key:

Conc. = Concentration (given in mg/kg)

K = unknown bias

U = analyzed for but not detected

SQL = Sample Quantitation Limit

J = Sample concentration is estimated

Q = Sample concentration is below the sample quantitation limit

B = Detection level raised due to blank contamination

() = Adjusted concentration for data utilizing *Using Qualified Data to Document an Observed Release and Observed Contamination* (Ref. 28)

* = Three times background concentration

■ = Concentration meets observed contamination criteria

Table 4-3 Continued
Nethery Landfill
Sediment Samples
Metals Analysis
August 1999

| SAMPLE | SD-10 | | SD-08 | | SD-09 | | SD-11 | | SD-12 | | SD-13 | | SD-14 | | SD-15 | |
|-----------|-------------------|------|---------|------|---------|------|---------|------|---------|------|------------------|------|---------|------|-------------------|------|
| CLP NO. | MFJ-S92 | | MFJ-S90 | | MFJ-S91 | | MFJ-S93 | | MFJ-S94 | | MFJ-S95 | | MFJ-S96 | | MFJ-S97 | |
| | Background Sample | | | | | | | | | | | | | | | |
| | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL |
| Barium | 33.2 Q | 48 | 71.8 | 55.2 | 70.8 | 51 | 54.4 | 51.2 | 42.0 Q | 56.2 | 34.4 Q | 48.8 | 47.8 | 44.6 | 61.9 | 44.2 |
| Beryllium | 0.07 U | 1.2 | 0.62 Q | 1.38 | 0.67 U | 1.28 | 0.11 Q | 1.28 | 0.13 Q | 1.4 | 0.09 Q | 1.22 | 0.28 Q | 1.12 | 0.69 Q | 1.10 |
| Copper | 3.3 UB | 6 | 9.9 | 6.9 | 12.1 | 6.38 | 4.5 UB | 6.4 | 4.6 UB | 7.0 | 5.8 UB | 6.1 | 9.7 | 5.58 | 14.8 | 5.52 |
| Lead | 54.6 163.8* | 0.72 | 18.5 | 0.83 | 42.0 | 0.76 | 3.9 | 0.77 | 10.7 | 0.84 | 8.1 | 0.73 | 55.0 | 0.67 | 18.6 | 0.66 |
| Mercury | 0.06 U | 0.12 | 0.07 U | 0.14 | 0.06 U | 0.13 | 0.06 U | 0.13 | 0.07 U | 0.14 | 0.06 U | 0.12 | 0.06 U | 0.11 | 0.06 U | 0.11 |
| Nickel | 8.3 QJK | 9.6 | 7.0 U | 11 | 19.1 | 10.2 | 6.5 UJK | 10.2 | 7.4 QJK | 11.2 | 10.8 JK (9.0) | 9.76 | 10.8 | 8.92 | 11.6 JK (8.99) | 8.84 |
| Vanadium | 18.7 56.1* | 12 | 23.1 | 13.8 | 29.8 | 12.8 | 4.5 UB | 12.8 | 12.0 Q | 14 | 15.5 | 12.2 | 17.1 | 11.2 | 32.4 | 11.0 |

Key:

Conc. = Concentration (given in mg/kg)

K = unknown bias

U = analyzed for but not detected

SQL = Sample Quantitation Limit

J = Sample concentration is estimated

Q = Sample concentration is below the sample quantitation limit

B = Detection level raised due to blank contamination

() = Adjusted concentration for data utilizing *Using Qualified Data to Document an Observed Release and Observed Contamination* (Ref. 28)

* = Three times background concentration

■ = Concentration meets observed contamination criteria

Table 4-4
Nethery Landfill
Sediment Samples
Semivolatile Analysis
August 1999

| SAMPLE | SD-10 | | SD-01 | | SD-02 | | SD-03 | | SD-04 | | SD-05 | | SD-06 | |
|--------------------|-----------------------|-----|--------|-----|---------|------|---------|-----|--------|-----|--------|-----|---------|-----|
| CLP NO. | FC-X50 | | FC-X41 | | FC-X42 | | FC-X43 | | FC-X44 | | FC-X45 | | FC-X46 | |
| | Background Sample | | | | | | | | | | | | | |
| | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL |
| Phenanthrene | 2200 JK (200) 660* | 373 | 3400 | 426 | 5400 | 802 | 870 | 475 | 490 U | 492 | 21 QJK | 356 | 59 QJK | 350 |
| Anthracene | 520 JK (52) 156* | 373 | 1000 | 426 | 1400 | 802 | 160 QJK | 475 | 490 U | 492 | 360 U | 356 | 350 U | 350 |
| Carbazole | 290 QJK | 373 | 520 | 426 | 820 | 802 | 130 QJK | 475 | 490 U | 492 | 360 U | 356 | 19 QJK | 350 |
| Fluoranthene | 3000 JK (300) 900* | 373 | 6200 D | 848 | 10000 D | 1600 | 2000 | 475 | 490 U | 492 | 27 QJK | 356 | 280 QJK | 350 |
| Pyrene | 3000 JK (253) 759* | 373 | 4100 D | 848 | 6400 D | 1600 | 1400 | 475 | 490 U | 492 | 360 U | 356 | 240 QJK | 350 |
| Benzo(a)anthracene | 1500 JK (150) 450* | 373 | 2800 | 426 | 4900 | 802 | 810 | 475 | 490 U | 492 | 22 QJK | 356 | 130 QJK | 350 |
| Chrysene | 1600 JK (160) 480* | 373 | 2800 | 426 | 5000 | 802 | 970 | 475 | 490 U | 492 | 21 QJK | 356 | 150 QJK | 350 |

Key:Conc. = Concentration (given in $\mu\text{g/kg}$)

K = unknown bias

U = analyzed for but not detected

SQL = Sample Quantitation Limit

J = Sample concentration is estimated

Q = Sample concentration is below the sample quantitation limit

D = Data obtained as a result of dilution

() = Adjusted concentration for data utilizing *Using Qualified Data to Document an Observed Release and Observed Contamination* (Ref. 28)

* = Three times background concentration

■ = Concentration meets observed contamination criteria

Table 4-4 Continued
Nethery Landfill
Sediment Samples
SemivolatILE Analysis
August 1999

| SAMPLE | SD-10 | | SD-01 | | SD-02 | | SD-03 | | SD-04 | | SD-05 | | SD-06 | |
|------------------------|-----------------------|-----|--------|-----|--------|-----|---------|-----|--------|-----|--------|-----|---------|-----|
| CLP NO. | FC-X50 | | FC-X41 | | FC-X42 | | FC-X43 | | FC-X44 | | FC-X45 | | FC-X46 | |
| | Background Sample | | | | | | | | | | | | | |
| | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL |
| Benzo(b)fluoranthene | 1400 JK (140) 420* | 373 | 2300 | 426 | 4800 | 802 | 920 | 475 | 490 U | 492 | 360 U | 356 | 130 QJK | 350 |
| Benzo(k)fluoranthene | 1000 JK (100) 300* | 373 | 2100 | 426 | 2700 | 802 | 620 | 475 | 490 U | 492 | 360 U | 356 | 180 QJK | 350 |
| Benzo(a)pyrene | 1300 JK (130) 309* | 373 | 2600 | 426 | 4400 | 802 | 850 | 475 | 490 U | 492 | 22 QJK | 356 | 130 QJK | 350 |
| Indeno(1,2,3-cd)pyrene | 820 JK (82) 246* | 373 | 1500 | 426 | 2600 | 802 | 530 | 475 | 490 U | 492 | 360 U | 356 | 86 QJK | 350 |
| Dibenzo(a,h)anthracene | 400 JK (40) 120* | 373 | 7890 | 426 | 1400 | 802 | 210 QJK | 475 | 490 U | 492 | 360 U | 356 | 46 QJK | 350 |
| Benzo(g,h,i)perylene | 820 JK (82) 246* | 373 | 1500 | 426 | 2600 | 802 | 580 | 475 | 490 U | 492 | 22 QJK | 356 | 97 QJK | 350 |

Key:

Conc. = Concentration (given in $\mu\text{g/kg}$)

K = unknown bias

U = analyzed for but not detected

SQL = Sample Quantitation Limit

J = Sample concentration is estimated

Q = Sample concentration is below the sample quantitation limit

() = Adjusted concentration for data utilizing *Using Qualified Data to Document an Observed Release and Observed Contamination* (Ref. 28)

* = Three times background concentration

■ = Concentration meets observed contamination criteria

Table 4-4 Continued
Nethery Landfill
Sediment Samples
Semivolatile Analysis
August 1999

| SAMPLE | SD-10 | | SD-07 | | SD-08 | | SD-09 | | SD-11 | | SD-12 | | SD-13 | |
|--------------------|--------------------------|-----|--------|-----|---------|-----|---------|-----|---------|------|--------|-----|--------|-----|
| CLP NO. | FC-X50 | | FC-X47 | | FC-X48 | | FC-X49 | | FC-X51 | | FC-X52 | | FC-X53 | |
| | Background Sample | | | | | | | | | | | | | |
| | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL |
| Phenanthrene | 2200 JK (220) 660* | 373 | 27 QJK | 455 | 150 QJK | 396 | 270 QJK | 380 | 440 QJK | 1086 | 390 U | 389 | 370 U | 373 |
| Anthracene | 520 JK (52) 156* | 373 | 450 U | 455 | 22 QJK | 396 | 62 QJK | 380 | 130 QJK | 1086 | 390 U | 389 | 370 U | 373 |
| Carbazole | 290 QJK | 373 | 450 U | 455 | 34 QJK | 396 | 57 QJK | 380 | 1100 U | 1086 | 390 U | 389 | 370 U | 373 |
| Fluoranthene | 3000 JK (300)900* | 373 | 66 QJK | 455 | 460 | 396 | 850 | 380 | 450 QJK | 1086 | 390 U | 389 | 370 U | 373 |
| Pyrene | 3000 JK (253) 759* | 373 | 54 QJK | 455 | 420 | 396 | 770 | 380 | 580 QJK | 1086 | 28 QJK | 389 | 370 U | 373 |
| Benzo(a)anthracene | 1500 JK (150) 450* | 373 | 33 QJK | 455 | 160 QJK | 396 | 390 | 380 | 260 QJK | 1086 | 390 U | 389 | 370 U | 373 |
| Chrysene | 1600 JK (160) 480* | 373 | 53 QJK | 455 | 230 QJK | 396 | 380 U | 380 | 250 QJK | 1086 | 390 U | 389 | 370 U | 373 |

Key:Conc. = Concentration (given in $\mu\text{g/kg}$)

K = unknown bias

U = analyzed for but not detected

SQL = Sample Quantitation Limit

J = Sample concentration is estimated

Q = Sample concentration is below the sample quantitation limit

() = Adjusted concentration for data utilizing *Using Qualified Data to Document an Observed Release and Observed Contamination* (Ref. 28)

* = Three times background concentration

■ = Concentration meets observed contamination criteria

Table 4-4 Continued
Nethery Landfill
Sediment Samples
Semivolatile Analysis
August 1999

| SAMPLE | SD-10 | | SD-07 | | SD-08 | | SD-09 | | SD-11 | | SD-12 | | SD-13 | |
|------------------------|-----------------------|-----|--------|-----|---------|-----|---------|-----|---------|------|--------|-----|--------|-----|
| CLP NO. | FC-X50 | | FC-X47 | | FC-X48 | | FC-X49 | | FC-X51 | | FC-X52 | | FC-X53 | |
| | Background Sample | | | | | | | | | | | | | |
| | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL |
| Benzo(b)fluoranthene | 1400 JK (140) 420* | 373 | 65 QJK | 455 | 240 QJK | 396 | 320 QJK | 380 | 180 QJK | 1086 | 390 U | 389 | 370 U | 373 |
| Benzo(k)fluoranthene | 1000 JK (100) 300* | 373 | 25 QJK | 455 | 240 QJK | 396 | 390 | 380 | 210 QJK | 1086 | 390 U | 389 | 370 U | 373 |
| Benzo(a)pyrene | 1300 JK (130) 309* | 373 | 42 QJK | 455 | 200 QJK | 396 | 320 QJK | 380 | 220 QJK | 1086 | 390 U | 389 | 370 U | 373 |
| Indeno(1,2,3-cd)pyrene | 820 JK (82) 246* | 373 | 47 QJK | 455 | 150 QJK | 396 | 240 QJK | 380 | 130 QJK | 1086 | 390 U | 389 | 370 U | 373 |
| Dibenzo(a,h)anthracene | 400 JK (40) 120* | 373 | 450 U | 455 | 63 QJK | 396 | 110 QJK | 380 | 73 QJK | 1086 | 390 U | 389 | 370 U | 373 |
| Benzo(g,h,i)perylene | 820 JK (82) 246* | 373 | 52 QJK | 455 | 170 QJK | 396 | 250 QJK | 380 | 150 QJK | 1086 | 390 U | 389 | 370 U | 373 |

Key:

Conc. = Concentration (given in µg/kg)

K = unknown bias

U = analyzed for but not detected

SQL = Sample Quantitation Limit

J = Sample concentration is estimated

Q = Sample concentration is below the sample quantitation limit

() = Adjusted concentration for data utilizing *Using Qualified Data to Document an Observed Release and Observed Contamination* (Ref. 28)

* = Three times background concentration

■ = Concentration meets observed contamination criteria

Table 4-4 Continued
Nethery Landfill
Sediment Samples
Semivolatile Analysis
August 1999

| SAMPLE | SD-10 | | SD-14 | | SD-15 | |
|--------------------|-----------------------|-----|---------|-----|--------|-----|
| CLP NO. | FC-X50 | | FC-X54 | | FC-X55 | |
| | Background Sample | | | | | |
| | Conc. | SQL | Conc. | SQL | Conc. | SQL |
| Phenanthrene | 2200 JK (220) 660* | 373 | 99 QJK | 325 | 42 QJK | 370 |
| Anthracene | 520 JK (52) 156* | 373 | 18 QJK | 325 | 370 U | 370 |
| Carbozole | 290 QJK | 373 | 330 U | 325 | 370 U | 370 |
| Fluoranthene | 3000 JK (300) 900* | 373 | 150 QJK | 325 | 65 QJK | 370 |
| Pyrene | 3000 JK (253) 759* | 373 | 230 QJK | 325 | 98 QJK | 370 |
| Benzo(a)anthracene | 1500 JK (150) 450* | 373 | 100 QJK | 325 | 48 QJK | 370 |
| Chrysene | 1600 JK (160) 480* | 373 | 120 QJK | 325 | 66 QJK | 370 |

Key:Conc. = Concentration (given in $\mu\text{g/kg}$)

K = unknown bias

U = analyzed for but not detected

SQL = Sample Quantitation Limit

J = Sample concentration is estimated

Q = Sample concentration is below the sample quantitation limit

() = Adjusted concentration for data utilizing *Using Qualified Data to Document an Observed Release and Observed Contamination* (Ref. 28)

* = Three times background concentration

■ = Concentration meets observed contamination criteria

Table 4-4 Continued
Nethery Landfill
Sediment Samples
Semivolatile Analysis
August 1999

| SAMPLE | SD-10 | | SD-14 | | SD-15 | |
|------------------------|-----------------------|-----|---------|-----|--------|-----|
| CLP NO. | FC-X50 | | FC-X54 | | FC-X55 | |
| | Background Sample | | | | | |
| | Conc. | SQL | Conc. | SQL | Conc. | SQL |
| Benzo(b)fluoranthene | 1400 JK (140) 420* | 373 | 120 QJK | 325 | 59 QJK | 370 |
| Benzo(k)fluoranthene | 1000 JK (100) 300* | 373 | 110 QJK | 325 | 73 QJK | 370 |
| Benzo(a)pyrene | 1300 JK (130) 309* | 373 | 110 QJK | 325 | 53 QJK | 370 |
| Indeno(1,2,3-cd)pyrene | 820 JK (82) 246* | 373 | 64 QJK | 325 | 43 QJK | 370 |
| Dibenzo(a,h)anthracene | 400 JK (40) 120* | 373 | 330 U | 325 | 19 QJK | 370 |
| Benzo(g,h,i)perylene | 820 JK (82) 246* | 373 | 72 QJK | 325 | 50 QJK | 370 |

Key:Conc. = Concentration (given in $\mu\text{g/kg}$)

K = unknown bias

U = analyzed for but not detected

SQL = Sample Quantitation Limit

J = Sample concentration is estimated

Q = Sample concentration is below the sample quantitation limit

() = Adjusted concentration for data utilizing *Using Qualified Data to Document an Observed Release and Observed Contamination* (Ref. 28)

* = Three times background concentration

■ = Concentration meets observed contamination criteria

Table 4-5
Nethery Landfill
Sediment Samples
Pesticide Analysis
August 1999

| SAMPLE | SD-10 | | SD-01 | | SD-02 | | SD-03 | | SD-04 | | SD-05 | | SD-06 | | SD-07 | |
|----------|-------------------|-----|---------|-----|--------|-----|---------|-----|--------|-----|--------|-----|--------|-----|--------|-----|
| CLP NO. | FC-X50 | | FC-X41 | | FC-X42 | | FC-X43 | | FC-X44 | | FC-X45 | | FC-X46 | | FC-X47 | |
| | Background Sample | | | | | | | | | | | | | | | |
| | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL |
| Dieldrin | 380 U | 376 | 150 QJK | 370 | 340 | 370 | 200 QJK | 460 | 510 U | 508 | 360 U | 364 | 350 U | 355 | 460 U | 456 |

Table 4-5 Continued
Nethery Landfill
Sediment Samples
Pesticide Analysis
August 1999

| SAMPLE | SD-10 | | SD-08 | | SD-09 | | SD-11 | | SD-12 | | SD-13 | | SD-14 | | SD-15 | |
|----------|-------------------|-----|--------|-----|--------|-----|--------|-----|--------|-----|--------|-----|--------|-----|--------|-----|
| CLP NO. | FC-X50 | | FC-X41 | | FC-X42 | | FC-X43 | | FC-X44 | | FC-X45 | | FC-X46 | | FC-X47 | |
| | Background Sample | | | | | | | | | | | | | | | |
| | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL | Conc. | SQL |
| Dieldrin | 380 U | 376 | 390 U | 394 | 380 U | 376 | 560 U | 565 | 400 U | 399 | 380 U | 380 | 340 U | 342 | 360 U | 361 |

Key:Conc. = Concentration (given in $\mu\text{g/kg}$)

K = unknown bias

U = analyzed for but not detected

SQL = Sample Quantitation Limit

J = Sample concentration is estimated

Q = Sample concentration is below the sample quantitation limit

() = Adjusted concentration for data utilizing *Using Qualified Data to Document an Observed Release and Observed Contamination* (Ref. 28)

* = Three times background concentration

■ = Concentration meets observed contamination criteria

5

Pathway Assessment

This section characterizes the environmental pathways and associated targets of potential contaminant migration from the site.

5.1 Ground Water Pathway

5.1.1 Ground Water Characteristics

The site is situated on an outcrop of alluvium which consists of sand, silt, clay, and gravel. The alluvium overlies the Austin Group, which consists of the following geological units: Gober Chalk, Brownstown Marl, Blossom Sand, and Bonham Formation. These units have an approximate maximum thickness of 700 feet and consist of chalk, limestone, and marl. The Austin Group yields small to moderate quantities of water to wells in parts of Texas north of the site with very limited use as an aquifer (Ref. 26, Ref. 30). Below the Austin Group is the Trinity Aquifer, the major aquifer in the area, which is located in the Antlers Formation (which is subdivided into the Paluxy Formation, Glen Rose Formation and Twin Mountains Formation). The Antlers Formation consists of rocks of Cretaceous age and consists of fine sand, sandy shale, and shale on top, limestone, marl, shale, and anhydrite in the middle, and fine to course sand, shale, clay, and basal gravel and conglomerate at the bottom. It has an approximate maximum thickness of 1,000 feet. The Trinity Aquifer yields small quantities of water in the areas surrounding the site. Underlying the Trinity Aquifer is a confining unit consisting of clay and shale (Ref. 26). There is no evidence of karst terrain. Annual net precipitation for the area is 37 inches (Ref. 4).

5.1.2 Ground Water Receptors

There is one inactive public supply water well located between 2 and 3 miles from the site and two wells located between 3 and 4 miles from the site. None of these wells are used for drinking or irrigation (Ref. 27). Currently, all potable water for the City of Dallas is supplied by surface water (Ref. 6). All other wells located within the target distance limit (TDL) are either unused or abandoned. No wellhead protection areas have been identified.

5.2 Surface Water Pathway

5.2.1 Surface Water Characteristics

The site is located on arents, loamy, hilly soil which consists of an overburden that has been left in mounds and ridges in the gravel pits. Permeability is moderate, run-off is rapid, and the hazard for erosion is severe (Ref. 8). Overland flow from the landfill flows in two directions (Ref. 15). Drainage from the east side of the landfill flows toward the east into the pond. The pond then flows overland approximately 1,000 feet to Elam Creek; this point is PPE 1 (Ref 3). Based on observations made during the SI field activities, Elam Creek has a flow rate of less than 10 cubic feet per second (cfs) (Ref. 1 ; Appendix A). Drainage from the south of the landfill flows south, overland approximately 500 feet to the Trinity River, PPE 2. The Trinity River has an average flow of 2,017 cfs (Ref. 28). The upgradient drainage is the area of the source, which is 35 acres. The landfill, although located within a pit, is situated several feet above the surface water which surrounds it (Appendix A).

The two-year, 24-hour rainfall is 4 inches (Ref. 7). The site is located between a 100-year and 500-year flood plain (Ref. 12). There is no flood containment on site.

5.2.2 Surface Water Receptors

There are no surface water intakes (drinking) located within the 15-mile TDL, as all public water supply is obtained from reservoirs located north of the site (Ref. 6).

Elam Creek has no documented surface water resource usage. No evidence of surface water use within the TDL has been documented from the Trinity River; however, evidence of fishing was observed (Appendix A). The annual poundage of aquatic human food chain organisms caught and consumed cannot be documented (Ref. 32). The varieties of fish caught from the Trinity River include bass, bluegill, carp, catfish, sunfish, crappie, drum, warmouth, and

gar (Ref. 29). It will be assumed that at least 1 pound of human food chain, aquatic organisms are caught and consumed annually from the Trinity River (Ref. 1, Ref. 3).

Several federal listed threatened and endangered species, including the Black-capped Vireo, the Interior Least Tern, the Migrant Loggerhead Shrike, and the Texas Garter Snake may inhabit areas along the 15-mile TDL; however, they have not been officially documented as being present (Ref. 13).

According to the National Wetlands Inventory (NWI) and 40 CFR 230.3, eligible wetlands border Elam Creek and parts of the Trinity River south of the landfill (Ref. 3, Ref. 9). Approximately 17 miles of designated wetland frontage exists along Elam Creek and the Trinity River within the 15-mile TDL (Ref. 9).

Sediment samples were taken along Elam Creek at least 0.1 mile down from PPE 1 to establish environmental threat (Ref. 31). The first 800 feet from PPE 1 contained no observed release of hazardous constituents (Ref. 3). The analytical data from the last 225 feet of sediment sampling met observed release criteria (Ref. 3)(Tables 4-3 through 4-5). This distance is less than the 528 feet or 0.10 mile required to establish environmental threat (Ref. 31).

5.3 Ground Water to Surface Water Pathway

The depth to ground water in the vicinity of the site is approximately 500 feet below ground surface (Ref. 30). The surface water elevation of Elam Creek and the Trinity River is unknown. Additional information would need to be obtained to determine if the criteria for the pathway have been met (Ref. 1).

5.4 Soil Exposure Pathway

5.4.1 Resident Threat Receptors

The site has been inactive since mid-1996. No workers are present at the site. During the SI field activities, START did not observe any schools or day care centers located on site or within 200 feet of the source (Ref. 15). The nearest resident is approximately 250 feet north of the site. Habitats for several federal listed threatened and endangered species, including the Black-capped Vireo, the Interior Least Tern, the Migrant Loggerhead Shrike, and the Texas Garter Snake exist within Dallas County; however, these species have not been officially documented as being present within the one mile TDL (Ref. 13). No commercial livestock production, grazing, silviculture, or agriculture occurs on the site (Ref. 15).

5.4.2 Nearby Threat Receptors

The entrance to the landfill is fenced and locked and dirt roads to the property are blocked (Ref. 15). A fence surrounds most of the northern perimeter, but is missing from a few locations just south of residences (Appendix A). During SI field activities, it was observed that hunting occurs on the facility property. Numerous shotgun shells were located to the south of the site and there is evidence that local residents may trespass on the property with egress from the southeast of the site (Ref. 15) (Appendix A). Attractiveness/accessibility will be evaluated as “moderately accessible with some public recreation use” (Ref. 3, Ref. 15).

The distance to the nearest individual is 100 feet. The nearby populations are as follows (Ref. 10):

| Distance Ring | Population Estimate |
|---------------|---------------------|
| 0 to ¼ mile | 270 |
| ¼ to ½ mile | 2,253 |
| ½ to 1 mile | 6,966 |
| Total | 9,489 |

Within the 1-mile radius, there are two elementary schools with a total enrollment of 1,217 students and a park (Ref. 19, Ref. 33) (Figure 1).

Based on the data obtained during the SI, the soil exposure pathway is not of concern (Tables 4-1 and 4-2).

5.5 Air Pathway

5.5.1 Air Pathway Characteristics

The landfill is moderately vegetated, which limits the potential for gaseous or particulate release to air. There were no odors detected during SI field activities, and previous air monitoring results did not indicate the presence of these contaminants at concentrations greater than background levels (Ref. 17).

5.5.2 Air Receptors

The nearest individual is located within 250 feet of the site (Ref. 15). In Dallas County, there are approximately 26 schools within a 4-mile TDL (Ref. 19). Many other schools in Dallas

County are within the 4-mile TDL but their enrollments were not included in the population estimates, since their total enrollments are not known.

| Distance Ring | Population Estimate |
|---------------|---------------------|
| 0 to ¼ mile | 270 |
| ¼ to ½ mile | 2,253 |
| ½ to 1 mile | 6,966 |
| 1 to 2 miles | 13,868 |
| 2-3 miles | 18,939 |
| 3 to 4 miles | 41,635 |
| Total | 83,931 |

Woodlands Springs Park, a designated recreation area, is located within ¼ to ½ mile of the site (Ref. 15). There is approximately 1,775 acres of HRS criteria wetlands within the 4-mile TDL (Ref. 3, Ref. 9).

6**Project Management**

Section 6 presents on-site E & E personnel associated with the SI and the community relations staff to be contacted for information pertaining to this site. Key personnel, level of effort, and community relations are addressed in this section.

6.1 Key Personnel

Michelle Brown of E & E was the project manger for completion of the SI. Her responsibilities included the implementation of the work plan and completion of the report. E & E field operations staff also included Mike Mitchell, Maggie Lin-Carson, and Jody Shires. Mitchell was responsible for implementing the Health and Safety Plan. Mitchell, Lin-Carson, and Shires were responsible for sampling. All team members assisted in the decontamination procedures and packaging of the samples. William Rhotenberry, EPA Site Assessment Manager (SAM), was on site during most of the SI field sampling activities.

6.2 Community Relations

Persons requesting site information are instructed to submit a Freedom of Information Act Request to:

Freedom of Information Office
EPA Region 6
1445 Ross Avenue
Dallas, Texas 75202-2737

7**Summary**

The Nethery Landfill is located at 500 Deepwood Drive in Dallas , Dallas County, Texas. The site is an inactive landfill which was illegally operated from mid-1994 until mid-1996. The site is surrounded by residential areas and is moderately accessible to the public. It is located 500 feet north of the Trinity River. People have been documented on the south side of the property. There are no buildings or equipment on site. The nearest school is within the ¼- to ½-mile target radius of the site.

The landfill was an unpermitted and unlicensed facility and its owner and operator underwent criminal investigations in 1996. The site contains mainly construction debris, which reaches a depth of 20 to 30 feet in some areas. The landfill utilized existing gravel pits and is uncovered and unlined.

SI field activities were conducted at the site during the week of August 9, 1999. During this time, the START contractor collected samples for chemical analysis and documented evidence of egress onto the site. Source soil samples and sediment samples from the overflows and surface water were collected and sent for TCL volatiles, TCL semivolatiles, TCL pesticides, PCBs, and TAL metals analyses.

Analysis of the samples collected indicate the presence of metals and PAHs characteristic of the waste and fire which occurred at the site from 1996 through 1997.

The pathway of concern for HRS evaluation is the Surface Water Migration Pathway. An area of observed release of Hazardous Substances were documented into the wetlands; however, the wetland frontage subject to contamination is less than 0.1 mile. Samples collected from the overflow to the Trinity River contained metal contamination at the beginning of the overflow and for the last two hundred feet before the PPE 2 to the Trinity River. The middle 300 feet of sampling contained no observed contamination. No other contaminants were found in the samples collected at this overflow.

CERCLIS #: TX0000605190

Based on the available data, the Nethery Landfill site is not an eligible candidate for placement onto the National Priorities List (NPL).

8

References

1. United States Environmental Protection Agency. Final Rule, Hazard Ranking System. FR51532-51667. December 14, 1990.
2. Superfund Chemical Data Matrix. June 1996.
3. United States Environmental Protection Agency. Office of Solid Waste and Emergency Response. Hazard Ranking System. Guidance Manual. Publication 9345.1-07, PB92-963377, EPA 540-R-92-026. November 1992.
4. Climate Diagnostics Center website, Annual Mean Rankings for Dallas Love Field, Texas, <http://www.cdc.noaa.gov/cgi-bin/rankall.calc.pl>, September 16, 1999.
5. National Pollutant Discharge Elimination System Stormwater Pollution Prevention Plan, from Environmental Materials, Inc. to EPA, dated November 22, 1996.
6. Your Drinking Water Quality, Publication No. 98/99-55, Published July 1999 by City of Dallas, Dallas Water Utilities.
7. U.S. Department of Commerce. Rainfall Frequency Atlas of the United States. Prepared by David M. Hershfield, Weather Bureau. Technical Paper No. 40. May 1961.
8. Soil Survey of Dallas County, Texas. United States Department of Agriculture. Soil Conservation Service in cooperation with Texas Agricultural Experiment Station, issued February, 1980.
9. National Wetlands Inventory, United States Department of the Interior, Fish and Wildlife Service. Map, White Rock Lake, Texas, 1989. Map, Hutchins, Texas, 1989. Map, Oak Cliff, Texas, 1989. Map, Ferris, Texas, 1989. Map, India, Texas, 1989.
10. United States Census Bureau, The Official Statistics, website. Mable/Geocorr V2.5 Geographic Correspondence Engine, <http://www.census.gov/plue/>, March 18, 1999.
11. U.S. EPA, NPDES Compliance Inspection Report, Keth A. Smith, EPA/6EN-AS, January 27, 1997.

12. Federal Emergency Management Agency. National Flood Insurance Program. Floodway, Flood Boundary and Floodway Map. City of Dallas, Texas. Dallas, Denton, Collin, Rockwell and Kaufman Counties. Panel 180 of 235. Revised July 2, 1991.
13. Fax from Texas Parks and Wildlife to Michelle Brown, E&E. Dated April 19, 1999. Annotated County Lists of Rare Species. Last Revision, August 13, 1998.
14. Etak, Inc. website, Eagle Results, <http://www.etak.com>, September 16, 1999.
15. Site Investigation Field Logbook. Nethery Landfill. Dallas, Dallas County, Texas. Ecology and Environment, Inc. July 1, 1999 to August 12, 1999.
16. U.S. EPA, Criminal Investigation Division. Report of Investigation. CID Form 009 (5/94). Case Number 0600-0238. August 30, 1996 to December 31, 1996.
17. Emergency Response Report. Jim Miller Landfill Fire. Prepared by E&E for EPA-Region 6. TDD number S06-97-02-016. June 30, 1997.
18. Memorandum. Nethery Recycling Cease and Desist Order. From Mr. Taylor Sharpe, Federal Enforcement Officer, U.S. EPA-Region 6. September 12, 1996.
19. U.S.G.S. 7.5-Minute Series Topographic Maps. Hutchins, Texas, Photorevised 1968 and 1973. Oak Cliff, Texas, Photorevised 1981. White Rock Lake, Texas, Photorevised 1968 and 1973.
20. CLP Case # 27273. Ecology and Environment, Inc., Data Quality Assurance Review, Nethery Landfill. Prepared by Michelle Brown. November 1, 1999. Contract Laboratory Program Data Review, Nethery Landfill. Prepared by Tom C. H. Chiang, ESAT Team Manager, Region 6. September 17 and 18, 1999.
21. Ecology and Environment, Inc. Site Inspection Work Plan for Nethery Landfill. July 19, 1999.
22. Data from Maxim Technologies, Inc. to Ernie Heyer, Texas Natural Resource Conservation Commission. Report Number D6-09-044. November 4, 1996.
23. Fax from Mike Rickman, Dallas Water Utilities to Gary Guerra, U.S. EPA-Region 6. Dated April 29, 1997. Sample data collected by EmTech Environmental Services on March 22, 1997.
24. Using Qualified Data to Document an Observed Release and Observed Contamination, EPA 540-F-94-028, November 1996.
25. Statement of Work For Sample Analysis (Organic and Inorganic). Prepared by Ecology and Environment, Inc. June 1995.
26. Occurrence, Availability, and Chemical Quality of Ground Water In The Cretaceous Aquifers Of North-Central Texas. Report 269, Volume 1. Texas Department of Water Resources. April 1982.

27. Occurrence, Availability, and Chemical Quality of Ground Water In The Cretaceous Aquifers Of North-Central Texas. Report 269, Volume 2. Texas Department of Water Resources. July 1982.
28. Water Resources Data. Texas. Water Year 1990, Volume 1. U.S. Geological Survey Water-Data Report TX-90-1.
29. Texas Parks and Wildlife Department, website. Fishing, <http://www.tpwd.state.tx.us/fish/infish/lakes/twbr.html.bak>, July 23, 1999.
30. Geologic Atlas of Texas, Dallas Sheet, Gayle Scott Memorial Edition. The University of Texas at Austin Bureau of Economic Geology. To accompany map - Dallas Sheet. 1972, Revised 1988.
31. United States Environmental Protection Agency. Office of Emergency and Remedial Response. Guidance for Performing Site Inspection under CERCLA, Interim Final. EPA/540-R-92-021, PB92-963375, September 1992.
32. Record of Communication. Fishing in the Trinity River. From: Michelle Brown To: Ken Kosalski, Texas Parks and Wildlife Department. August 3, 1999.
33. Dallas Public Schools, website. Frederick Douglass Elementary School, W.A. Blair Elementary, <http://www.dallas.isd.tenet.edu/schools/>, November 15, 1999.
34. United States Census Bureau, website. Estimates of Housing Units, Households, Households by Age of Householder, and Persons per Household, <http://www.census.gov/population/estimates/housing/prhuhht1.txt>, November 16, 1999.

A

Photodocumentation



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 101 PHOTOGRAPHER/WITNESS: LLYOD / BROWN
 DATE: 07/01/99 TIME: 0950 DIRECTION: WEST
 FRONT ENTRY SIGN



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 102 PHOTOGRAPHER/WITNESS: LLYOD / BROWN
 DATE: 07/01/99 TIME: 0955 DIRECTION: SOUTHWEST
 RANORAMIC VIEW OF LANDFILL



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 103 PHOTOGRAPHER/WITNESS: LLYOD / BROWN
 DATE: 07/01/99 TIME: 0955 DIRECTION: WEST
 PANORAMIC VIEW OF LANDFILL



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 104 PHOTOGRAPHER/WITNESS: LLYOD / BROWN
 DATE: 07/01/99 TIME: 0955 DIRECTION: WEST
 PANORAMIC VIEW OF LANDFILL



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 105 PHOTOGRAPHER/WITNESS: LLYOD / BROWN
 DATE: 07/01/99 TIME: 0955 DIRECTION: NORTHEAST
 PANORAMIC VIEW OF LANDFILL



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 106 PHOTOGRAPHER/WITNESS: LLYOD / BROWN
 DATE: 07/01/99 TIME: 1000 DIRECTION: SOUTHWEST
 GULLY AT PERIMETER OF LANDFILL



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 107 PHOTOGRAPHER/WITNESS: LLYOD / BROWN
 DATE: 07/01/99 TIME: 1002 DIRECTION: SOUTH
 SHOT OF LANDFILL FROM GULLY



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 108 PHOTOGRAPHER/WITNESS: LLYOD / BROWN
 DATE: 07/01/99 TIME: 1015 DIRECTION: SOUTH
 STAGNANT WATER IN GULLY SURROUNDING LANDFILL



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 109 PHOTOGRAPHER/WITNESS: LLYOD / BROWN
 DATE: 07/01/99 TIME: 1020 DIRECTION: SOUTH
 WATER WITH FLOATING DEBRIS



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 110 PHOTOGRAPHER/WITNESS: LLYOD / BROWN
 DATE: 07/01/99 TIME: 1030 DIRECTION: NORTHWEST
 VIEW OF FILL AND GULLY



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 111 PHOTOGRAPHER/WITNESS: LLYOD /BROWN
 DATE: 07/01/99 TIME: 1030 DIRECTION: NORTH
 VIEW OF FILL AND GULLY



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 112 PHOTOGRAPHER/WITNESS: LLYOD / BROWN
 DATE: 07/01/99 TIME: 1045 DIRECTION: SOUTH
 WETLANDS ON EAST SIDE OF LANDFILL



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 113 PHOTOGRAPHER/WITNESS: LLYOD / BROWN
 DATE: 07/01/99 TIME: 1100 DIRECTION: EAST
 BROKEN FENCE WITH OLD GRAVEL PIT IN BACKGROUND
 CONTAINING CONCRETE AND ROCKS



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 114 PHOTOGRAPHER/WITNESS: BROWN / LLYOD
 DATE: 07/08/99 TIME: 1040 DIRECTION: SOUTH
 SEWAGE VENT



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 115 PHOTOGRAPHER/WITNESS: BROWN / RHOTENBERRY
 DATE: 07/15/99 TIME: 1350 DIRECTION: NORTH
 FROM DIRT ROAD TOWARD FILL



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 116 PHOTOGRAPHER/WITNESS: BROWN / RHOTENBERRY
 DATE: 07/15/99 TIME: 1410 DIRECTION: SOUTH
 OVERFLOW FROM FILL TOWARD TRINITY



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 117 PHOTOGRAPHER/WITNESS: RHOTENBERRY / BROWN
 DATE: 07/15/99 TIME: 1412 DIRECTION: NORTH
 FROM HILL BY OVERFLOW TOWARD FILL



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 118 PHOTOGRAPHER/WITNESS: BROWN / RHOTENBERRY
 DATE: 07/15/99 TIME: 1450 DIRECTION: SOUTH
 WETLAND POND TO THE EAST OF FILL



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 119 PHOTOGRAPHER/WITNESS: BROWN / RHOTENBERRY
 DATE: 07/15/99 TIME: 1500 DIRECTION: SOUTHEAST
 FROM FILL TOWARDS POND



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 120 PHOTOGRAPHER/WITNESS: BROWN / RHOTENBERRY
 DATE: 07/15/99 TIME: 1505 DIRECTION: SOUTH
 TRENCH FOLLOWING FILL, GOES SOUTH TO OUTFALL



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 201 PHOTOGRAPHER/WITNESS: CAARSON / BROWN
 DATE: 08/10/99 TIME: 0830 DIRECTION: NORTH
 RESIDENCE WITH SWING NORTH OF FILL



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 202 PHOTOGRAPHER/WITNESS: CARSON / BROWN
 DATE: 08/10/99 TIME: 0832 DIRECTION: NORTHEAST
 RESIDENCE NORTH OF FILL



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 203 PHOTOGRAPHER/WITNESS: BROWN / MITCHELL
 DATE: 08/10/99 TIME: 1030 DIRECTION: NORTH
 SAMPLE SD12 LOCATION



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 204 PHOTOGRAPHER/WITNESS: BROWN / CARSON
 DATE: 08/10/99 TIME: 1035 DIRECTION: SOUTHWEST
 SAMPLE SD13 LOCATION



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 205 PHOTOGRAPHER/WITNESS: BROWN / CARSON
 DATE: 08/10/99 TIME: 1111 DIRECTION: NORTH
 SAMPLE SD15 LOCATION



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 206 PHOTOGRAPHER/WITNESS: BROWN / CARSON
 DATE: 08/10/99 TIME: 1115 DIRECTION: WEST
 SAMPLE SD11 LOCATION



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 207 PHOTOGRAPHER/WITNESS: BROWN / CARSON
 DATE: 08/10/99 TIME: 1120 DIRECTION: SOUTH
 SAMPLE SD14 LOCATION



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 208 PHOTOGRAPHER/WITNESS: BROWN / MITCHELL
 DATE: 08/10/99 TIME: 1125 DIRECTION: NORTHEAST
 SHOTGUNCASINGS AND FOOTPRINTS



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 209 PHOTOGRAPHER/WITNESS: BROWN / CARSON
 DATE: 08/11/99 TIME: 0845 DIRECTION: EAST
 SAMPLING LOCATION FOR SD05, PPE TO ELAM CREEK



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 210 PHOTOGRAPHER/WITNESS: BROWN / CARSON
 DATE: 08/11/99 TIME: 0846 DIRECTION: NORTHEAST
 JUST NORTH OF SD05



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 211 PHOTOGRAPHER/WITNESS: BROWN / CARSON
 DATE: 08/11/99 TIME: 0910 DIRECTION: NORTH
 SAMPLING LOCATION FOR SD04



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 212 PHOTOGRAPHER/WITNESS: BROWN / CARSON
 DATE: 08/11/99 TIME: 1005 DIRECTION: NORTH
 SAMPLING LOCATION FOR SD02 WITH DRUMS IN POND IN
 BACKGROUND



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 213 PHOTOGRAPHER/WITNESS: BROWN / MITCHELL
 DATE: 08/11/99 TIME: 1025 DIRECTION: NORTHEAST
 SAMPLING LOCATION FOR SD01 AT BEGINNING OF POND



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 214 PHOTOGRAPHER/WITNESS: BROWN / CARSON
 DATE: 08/11/99 TIME: 1045 DIRECTION: SOUTHEAST
 SAMPLING LOCATION FOR SS01



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 215 PHOTOGRAPHER/WITNESS: BROWN / CARSON
 DATE: 08/11/99 TIME: 1115 DIRECTION: EAST
 SAMPLING LOCATION FOR SS02 AND SS03



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 216 PHOTOGRAPHER/WITNESS: BROWN / MITCHELL
 DATE: 08/12/99 TIME: 0725 DIRECTION: SOUTHEAST
 FISHING BOUY OFF OF ELAM CREEK



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
PHOTO#: 217 PHOTOGRAPHER/WITNESS: BROWN / MITCHELL
DATE: 08/12/99 TIME: 0745 DIRECTION: SOUTHEAST
SAMPLING LOCATION FOR SD08 AND SD09



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
PHOTO#: 218 PHOTOGRAPHER/WITNESS: BROWN / MITCHELL
DATE: 08/12/99 TIME: 0805 DIRECTION: NORTH
SAMPLING LOCATION FOR SD07



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 219 PHOTOGRAPHER/WITNESS: BROWN / MITCHELL
 DATE: 08/12/99 TIME: 0815 DIRECTION: NORTH
 EVIDENCE OF BEAVERS



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 220 PHOTOGRAPHER/WITNESS: BROWN / MITCHELL
 DATE: 08/12/99 TIME: 0820 DIRECTION: NORTHEAST
 EVIDENCE OF BEAVERS



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 221 PHOTOGRAPHER/WITNESS: BROWN / CARSON
 DATE: 08/12/99 TIME: 0905 DIRECTION: SOUTH
 SAMPLING LOCATION FOR SD06



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 222 PHOTOGRAPHER/WITNESS: MITCHELL / SHIRES
 DATE: 08/11/99 TIME: 1005 DIRECTION: SOUTH
 SAMPLING LOCATION FOR SD10



SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 223 PHOTOGRAPHER/WITNESS: BROWN / CARSON
 DATE: 08/12/99 TIME: 1005 DIRECTION: SOUTH
 SAMPLING LOCATION FOR SS04

SITE NAME: NETHERY LANDFILL TDD#: S06-9903-001
 PHOTO#: 222 PHOTOGRAPHER/WITNESS: MITCHELL / SHIRES
 DATE: 08/11/99 TIME: 1005 DIRECTION: SOUTH
 SAMPLING LOCATION FOR SD10

B

Chain-of Custody Documentation



United States Environmental Protection Agency
Contract Laboratory Program

**Organic Traffic Report
& Chain of Custody Record**
(For Organic CLP Analysis)

SAS No.
(If applicable)

Case No.

27273

| | | | | | | | | | | | | | |
|---|-----------------------|-----------------------|---------------------------|---|----------------|---|-----------|---|-------------------------------|---|--|---|--|
| 1. Project Code | | Account Code | | 2. Region No. 06 Sampling Co. E4E/START | | 4. Date Shipped | | Carrier FED EX | | 6. Matrix (Enter in Column A) 1. Surface Water 2. Ground Water 3. Leachate 4. Field QC 5. Soil/Sediment 6. Oil (High only) 7. Waste (High only) 8. Other (Specify in Column A) | | 7. Preservative (Enter in Column D) 1. HCl 2. HNO3 3. NaHSO4 4. H2SO4 5. Ice only 6. Other (Specify in Column D) N. Not preserved | |
| Regional Information | | | | Sampler (Name) Michelle Brown | | Airbill Number 810801087070 | | | | | | | |
| Non-Superfund Program | | | | Sampler Signature <i>Michelle Brown</i> | | 5. Ship To SWOK 1700 WEST ALBANY, SUITE C BROKEN ARROW, OK 74012 ATTN: HARRY BORG | | | | | | | |
| Site Name NETHERY LF | | | | 3. Purpose* Lead: <input type="checkbox"/> SF <input type="checkbox"/> PRP <input type="checkbox"/> ST <input type="checkbox"/> FED Early Action: <input type="checkbox"/> CLEM <input type="checkbox"/> PA <input type="checkbox"/> REM <input type="checkbox"/> RI <input checked="" type="checkbox"/> SI <input type="checkbox"/> ESI Long-Term Action: <input type="checkbox"/> FS <input type="checkbox"/> RD <input type="checkbox"/> RA <input type="checkbox"/> O&M <input type="checkbox"/> INPLD | | | | | | | | | |
| City, State DALLAS, TX | | Site Spill ID | | | | | | | | | | | |
| CLP Sample Numbers (from labels) | A Matrix (from Box 6) | B Conc.: Low Med High | C Sample Type: Comp./Grab | D Preservative (from Box 7) | E RAS Analysis | | | F Regional Specific Tracking Number or Tag Numbers | G Station Location Identifier | H Mo/Day/Year/Time Sample Collection | I Corresponding CLP Inorganic Sample No. | J Sampler Initials | K Field QC Qualifier B = Blank S = Spike D = Duplicate R = Retest PE = Perform. Eval. - = Not a QC Sample |
| | Other: | | | Other: | VOA | BNA | High only | | | | | | |
| FCX38 | 5 | L | G | 5 | ✓ | ✓ | ✓ | 6-156859-156861 | SS-01 | 8-11-99/10:35 | MFJS80 | ML | - |
| FCX39 | 5 | L | G | 5 | ✓ | ✓ | ✓ | 6-156863-156865 | SS-02 | 8-11-99/11:10 | MFJS81 | ML | - |
| FCX40 | 5 | L | G | 5 | ✓ | ✓ | ✓ | 6-156867-156869 | SS-03 | 8-11-99/11:20 | MFJS82 | ML | D.F.SS02 |
| FCX41 | 5 | L | G | 5 | ✓ | ✓ | ✓ | 6-156871-156873 | SD-01 | 8-11-99/10:20 | MFJS83 | ML | - |
| FCX42 | 5 | L | G | 5 | ✓ | ✓ | ✓ | 6-156875-156877 | SD-02 | 8-11-99/10:00 | MFJS84 | ML | - |
| FCX43 | 5 | L | G | 5 | ✓ | ✓ | ✓ | 6-156879-156881 | SD-03 | 8-11-99/09:25 | MFJS85 | ML | - |
| FCX44 | 5 | L | G | 5 | ✓ | ✓ | ✓ | 6-156883-156885 | SD-04 | 8-11-99/08:50 | MFJS86 | ML | - |
| FCX45 | 5 | L | G | 5 | ✓ | ✓ | ✓ | 6-156887-156889 | SD-05 | 8-11-99/08:40 | MFJS87 | ML | - |
| FCX46 | 5 | L | G | 5 | ✓ | ✓ | ✓ | 6-156891-156893 | SD-06 | 8-12-99/09:05 | MFJS88 | ML | - |
| FCX47 | 5 | L | G | 5 | ✓ | ✓ | ✓ | 6-156895-156897 | SD-07 | 8-12-99/08:00 | MFJS89 | ML | - |
| Shipment for Case Complete? (Y/N) Y | | Page 1 of 2 | | Sample(s) to be Used for Laboratory QC FCX38, FCX46 | | | | Additional Sampler Signatures <i>[Signature]</i> | | | | Chain of Custody Seal Number(s) NA | |

CHAIN OF CUSTODY RECORD

| | | | | | |
|---|-------------------------------------|--|------------------------------|-------------|----------------------------------|
| Relinquished by: (Signature) <i>Michelle Brown</i> | Date / Time 8-12-99 14:00 | Received by: (Signature) FedEx | Relinquished by: (Signature) | Date / Time | Received by: (Signature) |
| Relinquished by: (Signature) | Date / Time | Received by: (Signature) | Relinquished by: (Signature) | Date / Time | Received by: (Signature) |
| Relinquished by: (Signature) | Date / Time | Received for Laboratory by: (Signature) | Date / Time | Remarks | Is custody seal intact? Y/N/none |

DISTRIBUTION: Blue - Region Copy
White - Lab Copy for Return to Region

Pink - SMO Copy
Yellow - Lab Copy for Return to SMO

EPA Form 9110-2

SEE REVERSE FOR ADDITIONAL STANDARD INSTRUCTIONS
*SEE REVERSE FOR PURPOSE CODE DEFINITIONS

361828



United States Environmental Protection Agency
Contract Laboratory Program

**Organic Traffic Report
& Chain of Custody Record**
(For Organic CLP Analysis)

SAS No.
(if applicable)

Case No.

27273

| | | | | | | | |
|-----------------------|--------------|-------------------|--------------|------------------|---------|---|---|
| 1. Project Code | Account Code | 2. Region No. | Sampling Co. | 4. Date Shipped | Carrier | 6. Matrix (Enter in Column A) 1. Surface Water 2. Ground Water 3. Leachate 4. Field QC 5. Soil/Sediment 6. Oil (High only) 7. Waste (High only) 8. Other (Specify in Column A) | 7. Preservative (Enter in Column D) 1. HCl 2. HNO3 3. NaHSO4 4. H2SO4 5. Ice only 6. Other (Specify in Column D) N. Not preserved |
| Regional Information | | Sampler (Name) | | Airbill Number | | | |
| Non-Superfund Program | | Sampler Signature | | 5. Ship To | | | |
| Site Name | | 3. Purpose* | | ATTN: HARRY BORG | | | |
| City, State | | Site Spill ID | | | | | |

Michelle Brown
Michelle Brown
NETHERY LF
DALLAS, TX
06
EVE/START
810801087070
SW OK
1700 WEST ALBANY, SUITE C
BROKEN ARROW, OK 74012

Lead
☐ SF
☐ PRP
☐ ST
☐ FED

Early Action
☐ CLEM
☐ PA
☐ REM
☐ RI
☒ SI
☐ ESI

Long-Term Action
☐ FS
☐ RD
☐ RA
☐ O&M
☐ INPLD

| CLP Sample Numbers (from labels) | A Matrix (from Box 6) Other: | B Conc.: Low Med High | C Sample Type: Comp./ Grab | D Preservative (from Box 7) Other: | E RAS Analysis | | | | F Regional Specific Tracking Number or Tag Numbers | G Station Location Identifier | H Mo/Day/ Year/Time Sample Collection | I Corresponding CLP Inorganic Sample No. | J Sampler Initials | K Field QC Qualifier B = Blank S = Spike D = Duplicate R = Pinpoint PE = Perform. Eval. -- = Not a QC Sample |
|----------------------------------|---------------------------------|-----------------------|----------------------------|---------------------------------------|----------------|-----|----------|-------------------|--|-------------------------------|---------------------------------------|--|--------------------|---|
| | | | | | VOA | BNA | Pest/PCB | High only ARO/TOX | | | | | | |
| FCX48 | 5 | L | G | 5 | ✓ | ✓ | ✓ | | 6-156899-156901 | SD-08 | 8-12-99/09:35 | MFJS 90 | MM | - |
| FCX49 | 5 | L | G | 5 | ✓ | ✓ | ✓ | | 6-156903-156905 | SD-09 | 8-12-99/07:40 | MFJS 91 | MM | D of SD 98 |
| FCX50 | 5 | L | G | 5 | ✓ | ✓ | ✓ | | 6-156907-156909 | SD-10 | 8-12-99/09:45 | MFJS 92 | MM | - |
| FCX51 | 5 | L | G | 5 | ✓ | ✓ | ✓ | | 6-156911-156913 | SD-11 | 8-10-99/11:10 | MFJS 93 | MM | - |
| FCX52 | 5 | L | G | 5 | ✓ | ✓ | ✓ | | 6-156915-156917 | SD-12 | 8-10-99/10:22 | MFJS 94 | MM | - |
| FCX53 | 5 | L | G | 5 | ✓ | ✓ | ✓ | | 6-156919-156921 | SD-13 | 8-10-99/10:30 | MFJS 95 | MM | - |
| FCX54 | 5 | L | G | 5 | ✓ | ✓ | ✓ | | 6-156923-156925 | SD-14 | 8-10-99/11:00 | MFJS 96 | MM | - |
| FCX55 | 5 | L | G | 5 | ✓ | ✓ | ✓ | | 6-156927-156929 | SD-15 | 8-10-99/11:10 | MFJS 97 | MM | - |
| FCX56 | 5 | L | G | 5 | ✓ | ✓ | ✓ | | 6-156931-156933 | SS-04 | 8-12-99/10:00 | MFJS 98 | MM | - |

| | | | | |
|-----------------------------------|--------|--|-------------------------------|---------------------------------|
| Shipment for Case Complete? (Y/N) | Page | Sample(s) to be Used for Laboratory QC | Additional Sampler Signatures | Chain of Custody Seal Number(s) |
| Y | 2 of 2 | FCX38, FCX46 | <i>Michelle Brown</i> | NA |

CHAIN OF CUSTODY RECORD

| | | | | | |
|------------------------------|---------------|---|------------------------------|--|--------------------------|
| Relinquished by: (Signature) | Date / Time | Received by: (Signature) | Relinquished by: (Signature) | Date / Time | Received by: (Signature) |
| <i>Michelle Brown</i> | 8-12-99 14:00 | <i>Fed Ex</i> | | | |
| Relinquished by: (Signature) | Date / Time | Received by: (Signature) | Relinquished by: (Signature) | Date / Time | Received by: (Signature) |
| | | | | | |
| Relinquished by: (Signature) | Date / Time | Received for Laboratory by: (Signature) | Date / Time | Remarks Is custody seal intact? Y/N/none | |
| | | | | | |

DISTRIBUTION: Blue - Region Copy
White - Lab Copy for Return to Region

Pink - SMO Copy
Yellow - Lab Copy for Return to SMO

EPA Form 9110-2

SEE REVERSE FOR ADDITIONAL STANDARD INSTRUCTIONS
*SEE REVERSE FOR PURPOSE CODE DEFINITIONS

361829



United States Environmental Protection Agency
Contract Laboratory Program

**Inorganic Traffic Report
& Chain of Custody Record**
(For Inorganic CLP Analysis)

SAS No.
(If applicable)

Case No.

27273

| | | | | | | | |
|-----------------------|--------------|-------------------|--------------|---|---------|---|---|
| 1. Project Code | Account Code | 2. Region No. | Sampling Co. | 4. Date Shipped | Carrier | 6. Matrix (Enter in Column A) 1. Surface Water 2. Ground Water 3. Leachate 4. Field QC 5. Soil/Sediment 6. Oil (High only) 7. Waste (High only) 8. Other (specify in Column A) | 7. Preservative (Enter in Column D) 1. HCl 2. HNO3 3. NaOH 4. H2SO4 5. K2CR2O7 6. Ice only 7. Other (specify in Column D) N. Not preserved |
| Regional Information | | Sampler (Name) | | Airbill Number | | | |
| Non-Superfund Program | | Sampler Signature | | 5. Ship To | | | |
| Site Name | | 3. Purpose | | DATA CHEM 950 WEST LEVOY DRIVE SALT LAKE CITY, UT 84123 ATTN: RICHARD WADE | | | |
| City, State | | Site Spill ID | | | | | |

| CLP Sample Numbers (from labels) | A Matrix (from Box 6) Other: | B Conc.: Low Med High | C Sample Type: Comp./Grab | D Preservative (from Box 7) Other: | E - RAS Analysis | | | | | | | | F Regional Specific Tracking Number or Tag Numbers | G Station Location Identifier | H Mo/Day/Year/Time Sample Collection | I Corresponding CLP Organic Sample No. | J Sampler Initials | K Field QC Qualifier B = Blank S = Spike D = Duplicate R = Rinsate PE = Perform. Eval. - = Not a QC Sample |
|----------------------------------|---------------------------------|-----------------------|---------------------------|---------------------------------------|------------------|--------------|---------|----------------------------------|----------|----|----------|----------|--|-------------------------------|--------------------------------------|--|--------------------|--|
| | | | | | Dis. Metals | Total Metals | Cyanide | NO ₂ /NO ₃ | Fluoride | Bt | Conduct. | | | | | | | |
| MFJS80 | 5 | L | G | 6 | ✓ | | | | | | | 6-156862 | SS01 | 8-11-99/10:35 | FCX38 | PK | - | |
| MFJS81 | 5 | L | G | 6 | ✓ | | | | | | | 6-156866 | SS02 | 8-11-99/11:10 | FCX39 | MO | - | |
| MFJS82 | 5 | L | G | 6 | ✓ | | | | | | | 6-156870 | SS03 | 8-11-99/11:20 | FCX40 | MO | DOF5502 | |
| MFJS83 | 5 | L | G | 6 | ✓ | | | | | | | 6-156874 | SD-01 | 8-11-99/10:20 | FCX41 | MM | - | |
| MFJS84 | 5 | L | G | 6 | ✓ | | | | | | | 6-156878 | SD-02 | 8-11-99/10:00 | FCX42 | PK | - | |
| MFJS85 | 5 | L | G | 6 | ✓ | | | | | | | 6-156882 | SD-03 | 8-11-99/9:25 | FCX43 | PK | - | |
| MFJS86 | 5 | L | G | 6 | ✓ | | | | | | | 6-156886 | SD-04 | 8-11-99/8:50 | FCX44 | PK | - | |
| MFJS87 | 5 | L | G | 6 | ✓ | | | | | | | 6-156890 | SD-05 | 8-11-99/8:40 | FCX45 | MM | - | |
| MFJS88 | 5 | L | G | 6 | ✓ | | | | | | | 6-156894 | SD-06 | 8-12-99/9:05 | FCX46 | MO | - | |
| MFJS89 | 5 | L | G | 6 | ✓ | | | | | | | 6-156898 | SD-07 | 8-12-99/8:00 | FCX47 | MO | - | |

| | | | | |
|-----------------------------------|-------------|--|-------------------------------|---------------------------------|
| Shipment for Case Complete? (Y/N) | Page 1 of 2 | Sample(s) to be Used for Laboratory QC | Additional Sampler Signatures | Chain of Custody Seal Number(s) |
| Y | | MFJS80, MFJS88 | [Signatures] | NA |

CHAIN OF CUSTODY RECORD

| | | | | | |
|------------------------------|---------------|---|------------------------------|-------------|----------------------------------|
| Relinquished by: (Signature) | Date / Time | Received by: (Signature) | Relinquished by: (Signature) | Date / Time | Received by: (Signature) |
| Michelle Brown | 8-12-99 14:00 | FedEx | | | |
| Relinquished by: (Signature) | Date / Time | Received by: (Signature) | Relinquished by: (Signature) | Date / Time | Received by: (Signature) |
| | | | | | |
| Relinquished by: (Signature) | Date / Time | Received for Laboratory by: (Signature) | Date / Time | Remarks | Is custody seal intact? Y/N/none |
| | | | | | |

DISTRIBUTION:

Green - Region Copy
White - Lab Copy for Return to Region

Pink - SMO Copy
Yellow - Lab Copy for Return to SMO

EPA Form 9110-1

SEE REVERSE FOR ADDITIONAL STANDARD INSTRUCTIONS
*SEE REVERSE FOR PURPOSE CODE DEFINITIONS

360000



United States Environmental Protection Agency
Contract Laboratory Program

**Inorganic Traffic Report
& Chain of Custody Record**
(For Inorganic CLP Analysis)

Case No.

27273

| | | | | | | | |
|----------------------------------|---------------|--|----------------------------------|--|--------------------------|---|--|
| 1. Project Code | Account Code | 2. Region No. <i>06</i> | Sampling Co. <i>E/E START</i> | 4. Date Shipped | Carrier <i>Fed Ex</i> | 6. Matrix (Enter in Column A) 1. Surface Water 2. Ground Water 3. Leachate 4. Field QC 5. Soil/Sediment 6. Oil (High only) 7. Waste (High only) 8. Other (specify in Column A) | 7. Preservative (Enter in Column D) 1. HCl 2. HNO ₃ 3. NaOH 4. H ₂ SO ₄ 5. K ₂ Cr ₂ O ₇ 6. Ice only 7. Other (specify in Column D) N. Not preserved |
| Regional Information | | Sampler (Name) <i>Michelle Brown</i> | | Airbill Number <i>810801087080</i> | | | |
| Non-Superfund Program | | Sampler Signature <i>Michelle Brown</i> | | 5. Ship To <i>DATA CHEM</i> <i>950 WEST LEVOY DRIVE</i> <i>SALT LAKE CITY, UT 84123</i> | | | |
| Site Name <i>NETHERY LF</i> | | 3. Purpose* Early Action <input type="checkbox"/> CLEM <input type="checkbox"/> PA <input type="checkbox"/> REM <input type="checkbox"/> RI <input checked="" type="checkbox"/> SI <input type="checkbox"/> ESI Long-Term Action <input type="checkbox"/> FS <input type="checkbox"/> RD <input type="checkbox"/> RA <input type="checkbox"/> O&M <input type="checkbox"/> NPLD | | ATTN: <i>RICHARD WADE</i> | | | |
| City, State <i>DALLAS, TX</i> | Site Spill ID | | | | | | |

| CLP Sample Numbers (from labels) | A Matrix (from Box 6) Other: | B Conc. Low Med High | C Sample Type: Comp./ Grab | D Preser- vative (from Box 7) Other: | E - RAS Analysis | | | | | | | | F Regional Specific Tracking Number or Tag Numbers | G Station Location Identifier | H Mo/Day/ Year/Time Sample Collection | I Corresponding CLP Organic Sample No. | J Sampler Initials | K Field QC Qualifier B = Blank S = Spike D = Duplicate R = Pinpoint PE = Perform. Eval. - = Not a QC Sample |
|--|--|----------------------------------|--|---|------------------|--------------|---------|----------------------------------|-------------------------|--------------|----------|----------|---|--|---|---|------------------------------|---|
| | | | | | Diss. Metals | Total Metals | Cyanide | NO ₂ /NO ₃ | Low only Fluoride | High only | | | | | | | | |
| | | | | | | | | | | pH | Conduct. | | | | | | | |
| MFJS90 | 5 | L | G | 6 | | ✓ | | | | | | 6-156902 | SD08 | 8-12-99/7:35 | FCX48 | MB | - | |
| MFJS91 | 5 | L | G | 6 | | ✓ | | | | | | 6-156906 | SD09 | 8-12-99/7:40 | FCX49 | MB | D-of 5048 | |
| MFJS92 | 5 | L | G | 6 | | ✓ | | | | | | 6-156910 | SD10 | 8-12-99/9:45 | FCX50 | MB | - | |
| MFJS93 | 5 | L | G | 6 | | ✓ | | | | | | 6-156914 | SD11 | 8-10-99/11:10 | FCX51 | MB | - | |
| MFJS94 | 5 | L | G | 6 | | ✓ | | | | | | 6-156918 | SD12 | 8-10-99/10:22 | FCX52 | MB | - | |
| MFJS95 | 5 | L | G | 6 | | ✓ | | | | | | 6-156922 | SD13 | 8-10-99/10:30 | FCX53 | MC | - | |
| MFJS96 | 5 | L | G | 6 | | ✓ | | | | | | 6-156926 | SD14 | 8-10-99/11:00 | FCX54 | MC | - | |
| MFJS97 | 5 | L | G | 6 | | ✓ | | | | | | 6-156930 | SD15 | 8-10-99/11:10 | FCX55 | MC | - | |
| MFJS98 | 5 | L | G | 6 | | ✓ | | | | | | 6-156934 | SS-04 | 8-12-99/10:00 | FCX56 | MB | - | |

| | | | | |
|---|-----------------------|---|---|--|
| Ship/prior for Case Complete? (Y/N) <i>Y</i> | Page <i>2 of 2</i> | Sample(s) to be Used for Laboratory QC <i>MFJS80, MFJS88</i> | Additional Sampler Signatures <i>Michelle Brown, R. Wade</i> | Chain of Custody Seal Number(s) <i>NA</i> |
|---|-----------------------|---|---|--|

CHAIN OF CUSTODY RECORD

| | | | | | |
|---|-------------------------------------|---|------------------------------|-------------|----------------------------------|
| Relinquished by: (Signature) <i>Michelle Brown</i> | Date / Time <i>8-12-99 14:00</i> | Received by: (Signature) <i>Fed Ex</i> | Relinquished by: (Signature) | Date / Time | Received by: (Signature) |
| Relinquished by: (Signature) | Date / Time | Received by: (Signature) | Relinquished by: (Signature) | Date / Time | Received by: (Signature) |
| Relinquished by: (Signature) | Date / Time | Received for Laboratory by: (Signature) | Date / Time | Remarks | Is custody seal intact? Y/N/none |

DISTRIBUTION:

Green - Region Copy
White - Lab Copy for Return to Region

Pink - CLASS Copy
Yellow - Lab Copy for Return to CLASS

EPA Form 9110-1

SEE REVERSE FOR ADDITIONAL STANDARD INSTRUCTIONS
*SEE REVERSE FOR PURPOSE CODE DEFINITIONS

368909

A21-012-13 REV

C

TDD (Original and Amendments)



Technical Direction Document
Amendment

06-99-03-0001-B

START CONTRACT #: 68-W6-0013

| | | |
|---|--|---|
| Activity Type: IV.A.2 Site Inspections Task: large General Task Description: Site Inspection at Nethery Landfill in Southeast Dallas Completion Date: 11/20/99 | | Created On: 10/29/99 DPO/PO: Henry Thompson Task Monitor: Rhotenberry W. (214/665-8372) Task Codes: SI; QB |
| Site/Project Name: Nethery Landfill Street Address: South end of Jim Miller Road County Name: Dallas City, State, Zip: Dallas, Tx | | Estimated Cost: \$0.00 Estimated Hrs: 0 Dedicated: 0 Non-Dedicated: 0 |
| Funds Source: CERCLA Site Assessment DCN #(s): SCR035 (AF2) CERCLA Site Assessment \$0.00 | | Deliverable: Formal Report Overtime: Not Applicable Reference: No |
| TDD Expenditure Limit: \$29,865.80 Hours: 590 Dedicated Hours: 590 Non-Dedicated Hours: 0 | | Staffing: Dedicated Staff Priority: Medium Start Date: 03/01/99 |

Specific Element(s): Refer to Statement of Work--08/02/94, IAW Y4 AWP (large)

Comments: This amendment (B) is to extend the completion date only. There was a delay in obtaining and validating the CLP data.

Conduct Site Inspection per SOW and EPA guidance EPA/540-R-92-021 "Guidance for Performing Site Inspections Under CERCLA", to document the presence of any hazardous substances at the site and evaluate all contaminant migration pathways. Although the site is filled primarily with construction materials, there have been documented episodes of illegal dumping at night of unknown materials. Coordinate with the TM for a scoping meeting on 3/4/99. Review existing EPA files prior to field work.

A. TDD Created By: - Signed by William Rhotenberry/R6/USEPA/US on 10/28/99 08:18:41 AM, according to 10/28/99

William Rhotenberry

Signed On:

B. Reviewed and Approved By: - Signed by Henry Thompson/R6/USEPA/US on 10/29/99 03:51:24 PM, according to 10/29/99

Project Officer:

Henry Thompson

10/29/99

Signed On:

M. Brown



Technical Direction Document
Amendment

06-99-03-0001-A

START CONTRACT #: 68-W6-0013

| | | |
|---|--|---|
| Activity Type: IV.A.2 Site Inspections Task: large General Task Description: Site Inspection at Nethery Landfill in Southeast Dallas Completion Date: 10/15/99 | | Created On: 09/01/99 DPO/PO: Henry Thompson Task Monitor: Rhotenberry W. (214/665-8372) Task Codes: SI; QB |
| Site/Project Name: Nethery Landfill Street Address: South end of Jim Miller Road County Name: Dallas City, State, Zip: Dallas, Tx | | Estimated Cost: \$0.00 Estimated Hrs: 0 Dedicated: 0 Non-Dedicated: 0 |
| Funds Source: CERCLA Site Assessment DCN #(s): SCR035 (AF2) CERCLA Site Assessment \$0.00 | | Deliverable: Formal Report Overtime: Not Applicable Reference: No |
| TDD Expenditure Limit: \$29,865.80 Hours: 590 Dedicated Hours: 590 Non-Dedicated Hours: 0 | | Staffing: Dedicated Staff Priority: Medium Start Date: 03/01/99 |

Specific Element(s): Refer to Statement of Work--08/02/94, IAW Y4 AWP (large)

Comments: This amendment (A) is to extend the completion date only. There was a delay in obtaining the CLP data.

Conduct Site Inspection per SOW and EPA guidance EPA/540-R-92-021 "Guidance for Performing Site Inspections Under CERCLA", to document the presence of any hazardous substances at the site and evaluate all contaminant migration pathways. Although the site is filled primarily with construction materials, there have been documented episodes of illegal dumping at night of unknown materials. Coordinate with the TM for a scoping meeting on 3/4/99. Review existing EPA files prior to field work.

A. TDD Created By: - Signed by William Rhotenberry/R6/USEPA/US on 09/01/99 08:57:30 AM, according

09/01/99

William Rhotenberry

Signed On:

B. Reviewed and Approved By: - Signed by Henry Thompson/R6/USEPA/US on 09/01/99 01:41:03 PM, according

Project Officer:

Henry Thompson

09/01/99

Signed On:

M. Brown

EPA**Technical Direction Document
(TDD)**

06-99-03-0001

START CONTRACT #: 68-W6-0013

| | | |
|--|--|--|
| Activity Type: IV.A.2 Site Inspections | | Created On: 03/02/99 |
| Task: large | | DPO/PO: Henry Thompson |
| General Task Description: Site Inspection at Nethery Landfill in Southeast Dallas | | Task Monitor: William Rhotenberry |
| Estimated Completion Date: 08/28/99 | | Task Codes: SI; QB |
| Site/Project Name: Nethery Landfill | | Estimated Cost: \$29,865.80 |
| Street Address: South end of Jim Miller Road | | Estimated Hrs: 590 |
| County Name: Dallas | | Dedicated: 590 |
| City, State, Zip: Dallas, Tx | | Non-Dedicated: 0 |
| Funds Source: CERCLA Site Assessment | | Deliverable: Formal Report |
| DCN #(s): | | Overtime: Not Applicable |
| SCRO35 (AF2) CERCLA Site Assessment \$29,865.80 | | Reference: No |
| TDD Expenditure Limit: \$29,865.80 | | Staffing: Dedicated Staff |
| Hours: 590 | | Priority: Medium |
| Dedicated Hours: 590 | | Start Date: 03/01/99 |
| Non-Dedicated Hours: 0 | | |

Specific Element(s): Refer to Statement of Work--08/02/94, IAW Y4 AWP (large)

Comments: Conduct Site Inspection per SOW and EPA guidance EPA/540-R-92-021 "Guidance for Performing Site Inspections Under CERCLA", to document the presence of any hazardous substances at the site and evaluate all contaminant migration pathways. Although the site is filled primarily with construction materials, there have been documented episodes of illegal dumping at night of unknown materials. Coordinate with the TM for a scoping meeting on 3/4/99. Review existing EPA files prior to field work.

Standard Language: Coordinate with Task Monitor**A. TDD Created By: - Signed by William Rhotenberry/R6/USEPA/US on 03/01/99 05:18:52 PM, according**

William Rhotenberry

03/01/99

Signed On:

B. Reviewed and Approved By: - Signed by Henry Thompson/R6/USEPA/US on 03/02/99 10:02:15 AM, acc**Project Officer:**

Henry Thompson

03/02/99

Signed On:

M. Brown
0808015IX X
80808

D

Photo Negatives (in START files only)

Nethery Landfill

S06-99-03-0001

Negatives

Reference 1

12-14-90

Vol. 55

No. 241

federal register

Friday
December 14, 1990

Book 2

United States
Government
Printing Office

SUPERINTENDENT
OF DOCUMENTS
Washington, DC 20402

OFFICIAL BUSINESS
Penalty for private use, \$300

SECOND CLASS NEWSPAPER

Postage and Fees Paid
U.S. Government Printing Office
(ISSN 0097-6326)

Reference 2

Superfund Chemical Data Matrix-Data Manager
Developed by the Office of Emergency and Remedial Response

United States Environmental Protection Agency

June 1996

SCDM Data Set

June 1996 Version


Reference 3

United States
Environmental Protection
Agency


Office of Solid Waste
and Emergency
Response

~~C. R. Riller~~
Riller 12/01/97
Publication 9345.1-07
PB92-963377
EPA 540-R-92-026
November 1992

Superfund



Hazard Ranking System Guidance Manual



Reference 4



Annual mean rankings for Dallas Love Fd TX

Variable: Annual precipitation (inches)

Time range: 1961-1996

Highest year: 55.31 1981
 Third quartile: 42.97
 Median: 37.47
 First quartile: 29.95
 Lowest year: 17.52 1963

Mean: 37.02

Ranked list with 35 years available

| Value | Year | Ranking |
|-------|------|---------|
| 55.31 | 1981 | 1 |
| 54.74 | 1962 | 2 |
| 51.69 | 1991 | 3 |
| 48.20 | 1994 | 4 |
| 47.96 | 1973 | 5 |
| 46.81 | 1990 | 6 |
| 46.06 | 1989 | 7 |
| 43.17 | 1992 | 8 |
| 42.97 | 1966 | 9 |
| 42.68 | 1974 | 10 |
| 41.68 | 1982 | 11 |
| 40.75 | 1971 | 12 |
| 39.99 | 1961 | 13 |
| 39.33 | 1984 | 14 |
| 38.55 | 1969 | 15 |
| 37.99 | 1979 | 16 |
| 37.80 | 1976 | 17 |
| 37.47 | 1964 | 18 |
| 36.19 | 1968 | 19 |
| 35.60 | 1995 | 20 |
| 35.50 | 1965 | 21 |
| 35.47 | 1993 | 22 |
| 34.34 | 1970 | 23 |
| 32.40 | 1986 | 24 |

| | | |
|-------|------|----|
| 30.76 | 1977 | 25 |
| 30.20 | 1983 | 26 |
| 29.95 | 1985 | 27 |
| 28.58 | 1987 | 28 |
| 28.07 | 1975 | 29 |
| 27.76 | 1967 | 30 |
| 27.64 | 1988 | 31 |
| 25.59 | 1978 | 32 |
| 24.36 | 1972 | 33 |
| 22.67 | 1980 | 34 |
| 17.52 | 1963 | 35 |

US Climate Pages***NOAA-CIRES Climate Diagnostics Center***

Document maintained by Cathy Smith (cas@cdc.noaa.gov)

Created Sep 16, 1999 18:46 GMT

<http://www.cdc.noaa.gov/cgi-bin/rankall.calc.pl>

Reference 5

ENVIRONMENTAL MATERIALS, INC.

**NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM
STORMWATER POLLUTION PREVENTION PLAN**

**NETHERY RECYCLING FACILITY
500 DEEPWOOD STREET
DALLAS, TEXAS 75217**

Submitted to:


**UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
REGION 6
1445 ROSS AVENUE
DALLAS, TEXAS 75202-2733**

Prepared by:

**Environmental Materials, Inc.
9900 North Central Expressway, Suite 301
Dallas, Texas 75231
(214) 361-8185**

**November 22, 1996
Project #9611850**

Written by:


**Collin D. Flatt
V.P., Operations**

Reviewed by:


**H. Edward Zinsmeyer
Environmental Scientist**

ENVIRONMENTAL MATERIALS, INC.

TABLE OF CONTENTS **Stormwater Pollution Prevention Plan** **Nethery Recycling Facility** **Dallas, Texas 75217**

| | | |
|-----|---|----|
| 1.0 | Introduction | 1 |
| 1.1 | General Facility Information | 1 |
| 2.0 | Pollution Prevention Team | 2 |
| 3.0 | Description of Potential Pollutant Sources | 3 |
| 3.1 | Site Map | 3 |
| 3.2 | Description of Outfall and Drainage Patterns | 3 |
| 3.3 | Inventory of Exposed Material | 5 |
| 3.4 | Significant Spills or Leaks | 8 |
| 3.5 | Existing Stormwater Sampling Data | 8 |
| 3.6 | Summary of Potential Pollutant Sources | 8 |
| 4.0 | Best Management Practices | 8 |
| 4.1 | Operational Controls | 9 |
| 4.2 | Good Housekeeping Practices | 9 |
| 4.3 | Preventive Maintenance Measures | 9 |
| 4.4 | Soil Prevention and Response Procedures | 10 |
| 4.5 | Facility Inspections | 11 |
| 4.6 | Employee Training | 12 |
| 4.7 | Sediment and Erosion Controls | 14 |
| 4.8 | Runoff Management Controls | 14 |
| 5.0 | Non-Stormwater Discharges | 15 |
| 5.1 | Authorized Non-Stormwater Discharges | 15 |
| 5.2 | Certification of Evaluation of Non-Stormwater Discharge | 15 |
| 6.0 | Comprehensive Site Compliance Evaluation | 18 |
| 7.0 | Required Signature | 19 |

List of Figures

Figure 1 - Site Map

List of Tables

| | |
|---|----|
| Table 1 - Inventory of Exposed Materials | 7 |
| Table 2 - Non-Stormwater Discharge Evaluation and Certification | 16 |

ENVIRONMENTAL MATERIALS, INC.

Nethery Recycling Facility
EMI Project #9611850

Stormwater Pollution Prevention Plan
November 22, 1996

1.0 INTRODUCTION

The Environmental Protection Agency (EPA) published regulations in November 1990 to control stormwater discharges under the National Pollutant Discharge Elimination System (NPDES) permit program. In September of 1992 the EPA published a final NPDES general permit for stormwater discharges associated with industrial activity. Stormwater dischargers associated with industrial activity seeking coverage under the general permit are required to develop and implement stormwater pollution prevention plans. The objectives of these plans are:

- to identify potential sources of pollution which may affect the quality of stormwater discharges; and
- to describe and ensure implementation of best management practices to minimize and control pollutants in stormwater discharge associated with facility activities.

This storm water pollution prevention plan addresses the operations of the Nethery Recycling Facility (Nethery) located at 500 Deepwood Street, Dallas, Texas. This facility receives recyclable materials in the form of construction debris (SIC Code 5093).

1.1 General Facility Information

Name of Facility: Nethery Recycling Facility

Facility Address: 500 Deepwood Street

Mailing Address: 915 Oak Park Drive
Dallas, Texas 75232-1235

Facility Contact: Herman L. Gibbons
Herman Nethery

Standard Industrial Classification Code: 5093

NPDES Stormwater Discharge Permit: Applied for but not yet received

Permitting Agency: Environmental Protection Agency, Region VI
Permit No.: _____

Effective Dates: 1996 through 2001

ENVIRONMENTAL MATERIALS, INC.

Nethery Recycling Facility
EMI Project #9611850

Stormwater Pollution Prevention Plan
November 22, 1996

2.0 POLLUTION PREVENTION TEAM

The Stormwater Pollution Prevention Team is responsible for developing, implementing, maintaining and revising this plan. The members of the team are familiar with different aspects of the management and operations of the facility. The members of the team are:

Herman Nethery

Herman Gibbons

Clyde Walker

Efphraim Garcia

Collin D. Flatt

Team Member Responsibilities:

Herman Nethery: Signatory authority, responsible for overall coordination of plan implementation.

Herman Gibbons, Facility Manager: Responsible for coordinating inspections, noting and reporting any plan changes, maintaining all inspection records and other documents.

Clyde Walker, Facility Supervisor: Responsible for coordinating the employee training program and for overseeing good housekeeping and material handling practices. Generally responsible for plan implementation.

Efphraim Garcia: Responsible for inspecting and approving all wastes received by the facility.

Collin D. Flatt, Environmental Consultant: Responsible for developing plan elements, evaluation and revision of plan when necessary, coordinating the annual Comprehensive Compliance Evaluation.

ENVIRONMENTAL MATERIALS, INC.

Nethery Recycling Facility
EMI Project #9611850

Stormwater Pollution Prevention Plan
November 22, 1996

3.0 DESCRIPTION OF POTENTIAL POLLUTANT SOURCES

3.1 Site Map

Figure 1, Site Map, illustrates the features of the site, as required by the Permit:

- Locations of outfall where stormwater is discharged from the property
- Arrows showing drainage patterns
- Locations where significant construction debris is exposed to stormwater
- Locations where processing equipment is exposed to stormwater
- Location of material loading/unloading areas
- Location of vehicle maintenance and cleaning areas
- Waste storage or disposal areas
- Location of liquid, fuel or chemical storage tanks
- Types of pollutants likely to be present in discharges

3.2 Description of Outfall and Drainage Patterns

The Nethery facility can be described as three primary areas. The three areas will be referenced as the North Side Disposal Area, the South Side and the West Side.

The North Side Disposal Area consists of:

- East Pond
- East office building and receiving.
- Landfill cells

The North Side Disposal Area comprises approximately 35 acres.

ENVIRONMENTAL MATERIALS, INC.

Nethery Recycling Facility
EMI Project #9611850

Stormwater Pollution Prevention Plan
November 22, 1996

The South Side consists of:

- Low-lying areas not utilized in the day to day operations of the facility.

The South Side comprises approximately 24 acres.

The West Side consists of:

- Low lying areas of the facility, limited use as current disposal area. Planned disposal cell development in the future.

The West Side comprises approximately 25 acres.

Total area of the Nethery facility is approximately 84 acres.

Three stormwater discharge points have been identified and are labeled as Outfall 1 through Outfall 3 on the site map.

- Outfall #1 is located near the northeast corner of the property. This outfall collects discharges from the northeast side of the North Side Disposal Area. The discharge from this outfall initiates in the East Pond and discharges during rainfall events at the south end of the pond via a concrete culvert. Flow from this outfall enters Elam Creek approximately 0.25 mile southeast of the property and ultimately enters the Trinity River.
- Outfall #2 is located near the south central portion of the South Side and drains the central portion of the Disposal Area as well as the low-lying areas of the South Side. Discharges only occur during significant rainfall events and is characterized as sheet flow discharge. The discharge area is primarily covered in native grasses and scrub vegetation. This drainage exits the property and enters the Trinity River approximately 200 feet south of the property boundary.
- Outfall #3 is located near the southwestern corner of the property and consists primarily of native grasses. This discharge area drains the West Side and run-off initiating from the western edge of the North Side Disposal Area. The drainage from this outfall exits the property as sheet wash discharge along the southwest side of the property and enters the Trinity River approximately 750 feet south of the property.

No other documented outfall was identified during routine inspections. None of the outfall identified on the property flows with potential for significant erosion.

ENVIRONMENTAL MATERIALS, INC.

Nethery Recycling Facility
EMI Project #9611850

Stormwater Pollution Prevention Plan
November 22, 1996

The types of pollutants which are potentially present in stormwater discharges associated with the activity at this facility are detailed in Section 3.6.

3.3 Inventory of Exposed Material

The NPDES general permit requires an inventory and narrative description of significant materials that have been handled, treated, stored or disposed of in a manner to allow exposure to stormwater between the date of this permit and three years prior. This description is to include the method and location of material storage, practices employed to minimize contact with stormwater runoff, and a description of any treatment the stormwater receives.

Nethery Recycling Facility receives unwanted debris generated from construction/demolition projects performed by Nethery and other local contractors. Facility operations consist of the disposal and subsequent processing of various debris, including wood, asphalt roofing shingles, soil and rock, concrete, brick and sheet metal. These materials are land filled in the North Side Disposal Area. Disposal activities include the placement and compaction of materials, which are periodically covered with soil. Fill materials are normally covered with soil on a daily basis. The area of the landfill is shaped to discourage drainage from the landfill area. The majority of stormwater which comes in contact with the construction debris is therefore contained within the area of the landfill, and percolates through the alternating layers of soil and debris.

The debris accepted by Nethery is recycled after a burial period of approximately five to seven years. The recycling process consists of the grinding and segregation of the land filled materials. The segregated materials are sold as various types of mulch and fill.

Nethery Recycling Facility receives an average of 100 tons of material per day. The facility is operated six days a week, with the exception of Christmas Day and New Year's Day. This rate of accepted waste volume equates to approximately 31,000 total tons per year.

The facility has been in operation since March of 1994. During the three prior years (actually 29 months of operation), Nethery estimates that the average fill rate of the facility was 100 tons per day; therefore, the total volume of debris exposed to stormwater run-off during the past three years is approximately 75,000 tons.

The garbage generated by the facility is collected in a truck which is parked on the north side of the landfill area. The garbage collected at the facility consists of municipal waste that is sometimes included in the loads of construction debris transported to Nethery. This garbage is separated from the construction debris by the facility load inspector and placed in the truck. The garbage collected in this truck is periodically hauled to the City of Dallas McCommas landfill.

The East Office Building is the only improvement to the property. This area is used for receiving/inspection

ENVIRONMENTAL MATERIALS, INC.

Nethery Recycling Facility
EMI Project #9611850

Stormwater Pollution Prevention Plan
November 22, 1996

of all materials. Routine maintenance performed on vehicles and equipment stationed at the landfill is completed by landfill personnel who have been instructed to properly containerize all fluids generated by the maintenance, including used oil, fuel and anti-freeze.

The fluids generated from maintenance activities are segregated and placed in closed top 55-gallon drums. The drums are stored in an area south of the east office building until they can be properly disposed or recycled. All fluids removed from the facility are properly manifested and copies of the manifests are retained in the East Office Building. Empty petroleum containers are also stored in an area located immediately south of the East Office Building. Used oil and other fluids collected by the facility are periodically picked up by a recycling company.

Table 1 lists all significant materials and potential pollutant sources that might be exposed to stormwater at this facility. Where appropriate, existing management practices utilized to reduce exposure of these materials to stormwater are listed in Table 1, Inventory of Exposed Materials.

**TABLE 1
 INVENTORY OF EXPOSED MATERIALS**

| Location | Material | Storage Method | Stormwater Management Practices, Structural/ Non-Structural Control |
|--------------------------|------------------------------------|--|---|
| North Side Landfill Area | construction debris | outside, normally covered with soil on a daily basis | landfill area shaped to discourage stormwater run-off and encourage rainwater to percolate through land filled materials |
| North Side Landfill Area | used oil and other waste fluids | outside, immediately south of the East Office Building, in sealed containers | Periodically collected by waste oil recycling company |

Note: "significant materials" as defined in 40 CFR 122.26(b)(12), are substances related to industrial activities such as process chemicals, raw materials, fuels, pesticides, and fertilizers (exposed to rain)

ENVIRONMENTAL MATERIALS, INC.

Nethery Recycling Facility
EMI Project # 9611850

Stormwater Pollution Prevention Plan
November 22, 1996

3.4 Significant Spills or Leaks

Significant spills or leaks include, but are not limited to, releases of oil, motor fuels, or hazardous substances in excess of reportable quantities. No evidence of spills or leaks was observed during inspection of the property. On site management reported that the facility has not experienced any spills or leaks over the past three years (29 months) of operation.

3.5 Existing Stormwater Sampling Data

As of the date this plan was prepared, the stormwater discharge from this facility has not been sampled during a rainfall event.

3.6 Summary of Potential Pollutant Sources

Based on the inventory of exposed significant materials, potential sources of pollutants have been identified. These sources are listed below, followed by potential pollutants of concern.

- Construction debris: No suspected potential pollutants.
- Waste grinder/crusher: Benzene, toluene, ethyl benzene and xylene (BTEX), oil and grease, metals, total suspended solids (TSS).
- Mobile handling equipment, such as bulldozers and loaders: BTEX, oil and grease, metals, TSS.
- Truck and vehicle parking: oil & grease, BTEX, metals, TSS.
- Garbage Collection Area: oil & grease, metals, phenols, TSS.

4.0 BEST MANAGEMENT PRACTICES

Stormwater management controls, or best management practices (BMPs), will be implemented to reduce the amount of pollutants in stormwater discharged from the Nethery facility. The following categories of BMPs will be implemented at this facility:

- Operational Controls
- Good Housekeeping Practices
- Preventive Maintenance Measures
- Spill Prevention and Response Procedures
- Facility Inspections

ENVIRONMENTAL MATERIALS, INC.

Nethery Recycling Facility
EMI Project # 9611850

Stormwater Pollution Prevention Plan
November 22, 1996

- Employee Training
- Sediment and Erosion Controls
- Runoff Management Controls

4.1 Operational Controls

- 1) Containment systems such as a concrete pad with berms shall be provided, where practicable, under the hydraulic systems of stationary processing equipment. Runoff from such bermed areas will be discharged into a sump, oil/water separator, sanitary sewer, or other appropriate drainage systems as applicable.
- 2) Maintain dry, clean working surfaces by using brooms, shovels, vacuum cleaners or cleaning machines.
- 3) Liquid wastes, including used oil, shall be stored in labeled non-leaking containers and hauled off-site for proper disposal or recycling in accordance with all requirements under the Resource Conservation and Recovery Act (RCRA) and applicable state and local laws.

4.2 Good Housekeeping Practices

Good housekeeping practices are intended to maintain a clean and orderly facility, thus limiting the exposure of potential pollutant sources to stormwater. The following specific good housekeeping BMPs will be implemented at this facility:

- 1) All accessible parts of the yard will be kept free of garbage and waste material.
- 2) Fuel oil will not be applied for dust control.
- 3) All drums/containers used to store chemicals or hazardous materials will be properly labeled.
- 4) Well organized work areas will be maintained throughout the facility.

4.3 Preventive Maintenance Measures

- 1) A Preventive Maintenance program for equipment and vehicles is currently implemented at this facility. The stormwater preventive maintenance program will expand upon the existing program, incorporating stormwater considerations and maintenance of stormwater management devices. The Pollution Prevention Team will be responsible for implementing necessary changes to the existing program, including training employees responsible for preventive maintenance to recognize stormwater considerations.

- 2) The preventive maintenance program includes:
 - The regular inspection and cleaning of equipment;
 - Lubricating, testing, and replacing worn or broken parts;
 - Knowledge of applicable MSDS information

Employees responsible for inspection and maintenance of equipment and vehicles will be made aware of relevant aspects of this Stormwater Pollution Prevention Plan. They will conduct regular inspection and maintenance of all equipment and vehicles used or stored outdoors, and inspection of all stormwater management devices.

- 3) Processing equipment and vehicles used or stored outside shall be kept clean by frequently removing accumulated oil and grease that may be exposed to stormwater (except where needed for proper operation of the equipment) or that may hide equipment trouble spots. Appropriate maintenance of such equipment will be performed on a regular basis.

4.4 Spill Prevention and Response Procedures

- 1) Contain and repair all significant leaks and spills as soon as practicable and, if applicable, install leak detection devices.
- 2) Use dry cleanup methods, where appropriate, on all leaks and spills. An adequate supply of absorbent material (such as "Oil Dry") will be maintained on-site. Used absorbent material will be swept up and properly disposed of as soon as possible. The source of the leak will be investigated and repaired as soon as practicable. If spills occur on soil the impacted soil will be removed with a shovel or other appropriate tools or machinery and stored in 55-gallon drums, pending characterization and disposal.
- 3) Drums containing liquids, such as petroleum products and lubricating oil, will be stored indoors. A shelter will be constructed south of the East Office Building to provide a covered storage area for petroleum products.
- 4) Drip pans or similar containers will be used to capture any petroleum or chemical leaks from stationary equipment until the leak is repaired. The drip pans must be inspected for leaks and checked for potential overflow and they will be emptied and cleaned regularly.
- 6) Recycle, reuse and reduce process materials to minimize waste generated onsite.

4.5 Facility Inspections

- 1) Regular inspections will be conducted by the designated member(s) of the Stormwater Pollution Prevention Team. These inspections will be conducted at least quarterly, and one can be done in conjunction with the Comprehensive Site Compliance Evaluation (Section 6.0). Inspections of the facility should also be conducted following all rainfall events in excess of 0.5 inches. Written documentation of these inspections is required, and should be attached to this plan. The Facility Manager will ensure that appropriate actions are taken in response to the inspections. Based on the observations and evaluations made during the inspection, this plan will be revised as necessary by the designated Pollution Prevention Team member.
- 2) All areas of the facility that could potentially introduce pollutants into stormwater will be inspected and their condition documented. At a minimum, the following areas will be inspected:
 - Materials unloading and loading areas which are exposed to stormwater;
 - Equipment and vehicle maintenance areas;
 - Any stormwater controls implemented at the facility;
 - Areas where waste is generated, stored, or exposed to stormwater; and
 - Each outfall area will be inspected for signs of erosion and condition of discharge, if any.
- 3) Any spills or leaks identified during the visual inspection will be immediately addressed according to Spill Prevention and Response BMPs. Any deterioration or damage to stormwater controls (concrete pads, berms, sumps) will be repaired as soon as possible.
- 4) Preventive maintenance inspections can be conducted as a part of the regular visual inspection. All inspections will be documented. Inspection records must show: when the inspection occurred, who conducted the inspection, what areas were inspected, what problems were found, steps taken to correct any problems, and who was notified.

The Facility Manager or Pollution Prevention Team member responsible for inspections will make certain that a timely inspection was conducted and the appropriate documentation exists. Record keeping will include, at a minimum, the following items.

- Record and document all spills
- Monitoring and maintenance activities
- Timely reporting of stormwater management related information to appropriate facility personnel.

The following inspection form has been generated to simplify the inspection process. This form may be altered as changing facility conditions dictate.

ENVIRONMENTAL MATERIALS, INC.

Nethery Recycling Facility
EMI Project # 9611850

Stormwater Pollution Prevention Plan
November 22, 1996

STORMWATER POLLUTION PREVENTION PLAN INSPECTION

Nethery Recycling Facility
500 Deepwood Street
Dallas, Texas 75217

Inspection conducted by: _____

Date: _____

EQUIPMENT

Visually inspect all storage and processing areas exposed to stormwater for spills, hydraulic oil leaks, or any conditions that could contaminate stormwater runoff. Check the integrity of any stormwater controls (concrete pads, curbs, sumps, oil/water separators).

Initials: _____ Comments: _____

Person Notified: _____

Results, Actions Taken: _____

STORAGE AREAS

Visually inspect outdoor ferrous and non ferrous storage areas for conditions that could contaminate stormwater runoff from these areas. Note any accumulations of oily raw material, unidentified liquids or residues, suspicious items, and undesirable items (batteries, capacitors, hazardous materials, etc.).

Initials: _____ Comments: _____

Person Notified: _____

Results, Actions Taken: _____

FUELING STATIONS, VEHICLE MAINTENANCE AREA

Inspect all AST areas that are potentially exposed to stormwater (fuel trucks). Inspect all areas where vehicle and equipment maintenance is conducted outside, if any. Note any leaks, spills, open containers of oil, or other conditions that could contaminate runoff. Inspect all containment structures.

Initials: _____ Comments: _____

Person Notified: _____

Results, Actions Taken: _____

ENVIRONMENTAL MATERIALS, INC.

Nethery Recycling Facility
EMI Project # 9611850

Stormwater Pollution Prevention Plan
November 22, 1996

STORMWATER POLLUTION PREVENTION INSPECTION (CONTINUED)

OUTFALL #1

Visually inspect the concrete conduit spillway of the East Pond. Note any accumulations of oily sheen behind the spillway or in the discharge area. Inspect the pond for unidentified liquids or residues or suspicious items.

Initials: _____ Comments: _____

Person Notified: _____

Results, Actions Taken: _____

OUTFALL #2

Visually inspect the outfall area for any sheen or unidentified liquids or suspicious items. Check the general area where water discharges from the facility for erosion or potential future erosion.

Initials: _____ Comments: _____

Person Notified: _____

Results, Actions Taken: _____

OUTFALL #3

Visually inspect the outfall area for any sheen or unidentified liquids or suspicious items. Check the general area where water discharges from the facility for erosion or potential future erosion.

Initials: _____ Comments: _____

Person Notified: _____

Results, Actions Taken: _____

For problems noted above, describe who was notified and steps taken to remedy the problems:

ENVIRONMENTAL MATERIALS, INC.

Nethery Recycling Facility
EMI Project # 9611850

Stormwater Pollution Prevention Plan
November 22, 1996

4.6 Employee Training

- 1) A training and education program will be implemented for employees of the facility that addresses conditions that cause pollution, use of the BMPs presented in this plan, and proper scrap inspection handling and storage procedures.
- 2) Employee Training appropriate to their job function will be provided for: truck drivers, supervisors and operating personnel. Training will take place in several stages: prior to job assignment, during initial operation of the plan, and ongoing. Ongoing training will take place in conjunction with regularly scheduled safety meetings.

The training program will address, at a minimum, the following items:

- Best Management Practices to be implemented at the facility;
 - How to identify potential problem areas;
 - Proper handling and storage procedures;
 - Procedures to follow in the event of a spill or leak;
 - Review of preventive maintenance requirements;
 - Review of the Stormwater Pollution Prevention Plan and its requirements.
- 3) A roster of employees attending the initial training will be attached to this plan. Documentation of all subsequent training will also be included in this plan or will be readily available for inspection. If additional training is conducted in conjunction with regularly scheduled safety meetings, the safety meeting roster will suffice for documentation.

4.7 Sediment and Erosion Control

One area of moderate erosion was noted on the south side of the landfill road near the eastern boundary of the fill area. EMI recommends controlling this small area of erosion by grading and covering this area of drainage with gravel. If, at a later date, any other areas with a high potential for soil erosion are identified, appropriate measures will be selected to limit the erosion. Measures considered may include, but are not limited to: paving or use of gravel to minimize soil exposure, diversions of water flow, vegetative practices, seeding, mulching, buffer zones and straw bale barriers.

4.8 Runoff Management Controls

It is anticipated that the above listed operational controls, good housekeeping practices, preventive maintenance measures and spill prevention and response procedures will achieve a sufficient level of pollution control. If, at a later date, it is determined that existing BMPs may not be sufficient to minimize pollutant loadings in stormwater, then additional stormwater management practices may be

ENVIRONMENTAL MATERIALS, INC.

Nethery Recycling Facility
EMI Project # 9611850

Stormwater Pollution Prevention Plan
November 22, 1996

implemented. An indication that such measures should be considered include: sediment deposition, oil sheens, or obvious sources of pollution. Additional measures could include, but are not limited to: berms, sediment filter boom, grassed buffer strips or swales, and oil/water separators.

5.0 NON STORMWATER DISCHARGES

5.1 Authorized Non-Stormwater Discharges

1) The following non-stormwater discharges are authorized by the General Permit:

- Discharges from fire fighting activities
- Fire hydrant flushes
- Potable water sources including waterline flushes
- Irrigation drainage
- Lawn or vegetation watering
- Uncontaminated groundwater
- Foundation or footing drains where flows are not contaminated with process water
- Discharges from springs
- Routing exterior building wash down which does not use detergents
- Pavement wash waters where spills or leaks of toxic or hazardous materials have not occurred and where detergents are not used
- Air conditioning condensate

5.2 Certification of Evaluation of Non-Stormwater Discharge

This plan includes a certification that the stormwater discharge has been evaluated for the presence of non-stormwater discharges other than those specified above. The certification is based on visual inspection of all discharge points on numerous occasions during dry weather.

The attached **Evaluation of Non-Stormwater Discharges** includes a description of the method used to evaluate the discharge, the date of evaluation, and the person conducting the test. Discharge points at this facility are labeled on the site map as Outfall #1, #2 and #3. The perimeter of the landfill area was also inspected for non-stormwater discharges.

**TABLE 2
NON-STORMWATER DISCHARGE
EVALUATION AND CERTIFICATION**

| Date of Test | Outfall Tested | Method Used to Evaluate Non-Stormwater Discharge | Describe Results of Test | Potential Sources of Discharge | Name of Tester |
|---------------------|----------------------------|---|---------------------------------|---------------------------------------|-----------------------|
| 10/14/96 | Outfall #1 | Visual inspection | No discharge | Rainfall | Collin Flatt |
| 10/14/96 | Outfall #2 | Visual inspection | No discharge | Rainfall | Collin Flatt |
| 10/14/96 | Outfall #3 | Visual inspection | No discharge | Rainfall | Collin Flatt |
| 10/14/96 | Perimeter of landfill area | Visual inspection | No discharge | Rainfall | Collin Flatt |

ENVIRONMENTAL MATERIALS, INC.

Nethery Recycling Facility
EMI Project #9611850

Stormwater Pollution Prevention Plan
November 22, 1996

CERTIFICATION OF EVALUATION OF NON-STORMWATER DISCHARGES


I certify under penalty of law that the stormwater drainage system described in this Stormwater Pollution Prevention Plan has been tested or evaluated for the presence of non-stormwater discharge under my direction or supervision in accordance with a program designed to ensure that qualified personnel properly gather and evaluate the information presented above. Based upon my inquiry of the person or persons directly responsible for gathering information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for knowing violations.


Herman Nethery

Herman Gibbons

Signatory Authority

Facility Manager


Signature


Signature

11/26/96
Date

11/26/96
Date

ENVIRONMENTAL MATERIALS, INC.

Nethery Recycling Facility
EMI Project #9611850

Stormwater Pollution Prevention Plan
November 22, 1996

6.0 COMPREHENSIVE SITE COMPLIANCE EVALUATION

A member of the Stormwater Pollution Prevention Team shall conduct a comprehensive site compliance evaluation at least once a year. This evaluation will consist of:

- 1) A visual inspection of stormwater drainage areas for evidence of pollutants entering the drainage system.
- 2) An evaluation of the effectiveness of measures to reduce pollutants, to determine if additional measures are needed.
- 3) An observation of structural measures and other stormwater controls to ensure they are operating properly.
- 4) An inspection of all equipment needed to implement the plan, such as spill response equipment.

Based on the evaluation of pollutant sources and pollution prevention controls, this plan will be revised if necessary within two weeks of the inspection. Any changes necessary will be implemented within 12 weeks of the inspection.

A report summarizing the inspection results, follow up actions taken and the date and personnel who conducted the inspection will be prepared. This report will also document all incidents of noncompliance, or a certification that the facility is in compliance with the plan. The report must be signed by a company officer or someone with designated signatory authority, according to the certification described in section 7.0.

ENVIRONMENTAL MATERIALS, INC.

Nethery Recycling Facility
EMI Project #9611850

Stormwater Pollution Prevention Plan
November 22, 1996

7.0 REQUIRED SIGNATURE

Any person signing documents under the NPDES General Permit for Stormwater Discharge Associated With Industrial Activity, including this Stormwater Pollution Prevention Plan for Nethery Recycling Facility, 500 Deep Wood Street, Dallas, Texas, shall make the following certification:

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."


Herman Nethery

Herman Gibbons

Signatory Authority

Facility Manager



Signature


Signature

11, 21, 96
Date

11/26/96
Date

Reference 6



Drinking Water Quality

1998 Report



dallas water utilities
city of dallas

Customer Service 214/651-1441
Water Quality Information 214/670-0900

En Español

Este documento contiene información importante sobre su agua potable.
Para obtener una copia de esta información en Español,
por favor llame al número 214/651-1441.

Published July 1999

Table of Contents

| | |
|---|----|
| Dallas water quality remained high in 1998 | 3 |
| Dallas continues to improve water quality | 4 |
| Your water sources | 5 |
| How your drinking water is treated | 6 |
| Questions and answers | 8 |
| Water quality monitoring results | 10 |
| All drinking water may contain contaminants | 12 |
| How to protect your water quality | 13 |
| Make every drop count | 15 |

Your participation is welcome

Dallas Water Utilities (DWU) is a not-for-profit department of the City of Dallas and is governed by the Dallas City Council. The City Council meets weekly on Wednesdays. For information about meetings and how to register as a speaker, contact the City Secretary's office at 214/670-3738.

Following are other helpful telephone numbers:

- Questions or concerns about water quality - 214/670-0900;
- To request a speaker for your group - 214/670-4022;
- Questions about your bill - 214/651-1441;
- For inquiries about public participation in DWU projects - 214/670-4297;
- For brochures on water conservation or pollution prevention - 214/670-3155.

Free water treatment plant tours are available for groups on weekdays during the daytime. Tours are restricted as to size, age and number of participants. Please call in advance to schedule (214/670-0900).

*This report was mailed to all Dallas Water Utilities customers.
The report is available in Dallas public libraries and recreation centers
and is on the City of Dallas website www.ci.dallas.tx.us*

If you know someone who did not receive a copy, we'll be happy to send one.

For additional copies or to comment on this report,
call 214/670-3155 or contact:
DWU Community Relations,
City Hall, 1500 Marilla, 5AS
Dallas, TX 75201

Printed on recycled paper




City of Dallas

Publication No. 98/99-55

Your water sources

Dallas uses surface water from six sources: the Elm Fork of the Trinity River and Lakes Ray Roberts, Lewisville, Grapevine, Ray Hubbard and Tawakoni. In addition, Dallas has water rights in Lakes Fork and Palestine to meet future needs. Pipelines will need to be constructed to connect these two lakes to the Dallas system. The City of Dallas regularly reviews its Long Range Water Supply Plan to address issues such as future sources of water. This planning, along with wise water use, will ensure an adequate supply of water for future needs.

DWU has an active Watershed Management Program that performed more than 8,000 tests on the water quality in the rivers, streams and reservoirs in 1998. In addition, the City of Dallas' storm water quality and industrial pretreatment programs help prevent pollution. As water travels over the surface of the land, it dissolves naturally occurring minerals and can be polluted by animals or human activity. The presence of any of these pollutants in the untreated water does not necessarily pose a health risk in your drinking water. The Texas Natural Resource Conservation Commission will be reviewing all of Texas' drinking water sources. This source water assessment process will be completed in three years. Dallas' current treatment techniques have proven effective in removing these pollutants. The City of Dallas will continue to commit the resources needed to ensure proper treatment and delivery of high quality water to its customers.



Reference 7

TECHNICAL PAPER NO. 40

RAINFALL FREQUENCY ATLAS OF THE UNITED STATES

for Durations from 30 Minutes to 24 Hours and
Return Periods from 1 to 100 Years

Prepared by
DAVID M. HERSHFIELD
Cooperative Studies Section, Hydrologic Services Division
for
Engineering Division, Soil Conservation Service
U.S. Department of Agriculture




WASHINGTON, D.C.

May 1961

Repaginated and Reprinted January 1963


2-YEAR 24-HOUR RAINFALL (INCHES)



Reference 8

United States Department of Agriculture
Soil Conservation Service
in cooperation with
Texas Agricultural Experiment Station

SOIL CONSERVATION SERVICE
1132A North Dallas Ave.
Lancaster, Texas 75146-1620



soil survey of

**Dallas County,
Texas**

cultivated farm crops has been used for urban development. The rest of the good cropland is also in danger of being converted to residential developments because it is nearly level to gently sloping and has few limitations to this development.

In recent years, less cropland has been used for row crops and more has been converted to grazing land. In the soil survey of 1924 (4), about 90 percent of the county was cultivated. Today, only about 25 percent is used for crops. Near the housing developments, many acres that were once cultivated are now idle and awaiting development. Most of this land has high or medium potential for use as cropland.

The one map unit in Dallas County that has very low potential for urban uses is the Trinity-Frio map unit. Because of the hazard of flooding, urban development on this land would be expensive. The soils in the Houston Black-Heiden, Eddy-Stephen-Austin, Austin-Houston Black, Wilson-Rader-Axtell, and Ferris-Heiden map units can be developed for urban use at a lower cost than can those in the Trinity-Frio map unit. The main limitations of these soils to urban uses are the high or very high shrink-swell potential, low soil strength, and high corrosivity to uncoated steel.

In addition to these limitations, the Eddy, Austin, and Stephen soils are limited by shallowness to bedrock. These soils have limestone bedrock at a depth of 5 to 40 inches; however, the rock is rippable and makes a good foundation for most structures. Except for the Eddy soils, all of these soils have high or medium potential for use as cropland or pasture.

The soils in the Silawa-Silstid-Bastsil map unit are well suited to urban uses. Some areas of this unit and of the Wilson-Rader-Axtell unit are wooded and are highly valued for residential development. Most areas of the Eddy-Stephen-Austin map unit are covered with trees and shrubs; in some areas of this unit, the land is steep and broken, providing striking scenery. The soils in the Eddy-Stephen-Austin map unit also are highly valued for residential development; however, because they are shallow and have unstable slopes, these soils have only medium potential for this use.

Most of the soils in Dallas County have low potential for recreation uses. The only soils that have high potential for recreation uses are those in the Silawa-Silstid-Bastsil map unit. The other soils in the county are too clayey, have slow permeability, are subject to flooding, or are shallow to bedrock.

Most of the soils in the county have low potential for sanitary facilities. The main limitations, especially to septic tank absorption fields, are the slow absorption of effluent and the shallowness of the soils to bedrock.

Soil maps for detailed planning

The map units on the detailed soil maps at the back of this survey represent the soils in the survey area. The

map unit descriptions in this section, along with the soil maps, can be used to determine the suitability and potential of a soil for specific uses. They also can be used to plan the management needed for those uses. More information on each map unit, or soil, is given under "Use and management of the soils."

Each map unit on the detailed soil maps represents an area on the landscape and consists of one or more soils for which the unit is named.

A symbol identifying the soil precedes the map unit name in the soil descriptions. Each description includes general facts about the soil, a brief description of the soil profile, and a listing of the principal hazards and limitations to be considered in planning management.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer or of the underlying material, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer or of the underlying material. They also can differ in slope, stoniness, salinity, wetness, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Austin silty clay, 1 to 3 percent slopes, is one of several phases in the Austin series.

Some map units are made up of two or more major soils. These map units are called soil complexes.

A *soil complex* consists of two or more soils in such an intricate pattern or in such small areas that they cannot be shown separately on the soil maps. The pattern and proportion of the soils are somewhat similar in all areas. Eddy-Brackett complex, 8 to 20 percent slopes, is an example.

Most map units include small scattered areas of soils other than those for which the map unit is named. Some of these included soils have properties that differ substantially from those of the major soil or soils. Such differences could significantly affect use and management of the soils in the map unit. The included soils are identified in each map unit description. Some small areas of strongly contrasting soils are identified by a special symbol on the soil maps.

Table 5 gives the acreage and proportionate extent of each map unit. Other tables (see "Summary of tables") give properties of the soils and the limitations, capabilities, and potentials for many uses. The Glossary defines many of the terms used in describing the soils.

Soil descriptions

1—Altoga silty clay, 5 to 12 percent slopes, eroded. This is a deep, well drained, sloping to strongly

sloping soil on escarpments of stream terraces. The areas are long and narrow to oval and range from 10 to more than 100 acres. In most areas, the original surface layer has been removed by sheet erosion. Rills and small gullies are common.

Typically, the surface layer is moderately alkaline, light yellowish brown silty clay about 4 inches thick. It is underlain, to a depth of 25 inches, by moderately alkaline, very pale brown silty clay that has fine yellowish brown mottles. To a depth of 65 inches, the soil is moderately alkaline silty clay that is mottled yellowish brown in the upper part and light brownish gray in the lower part. To a depth of 80 inches, it is moderately alkaline, brownish yellow silty clay loam.

Permeability is moderate, and the available water capacity is high. Runoff is medium. The hazard of erosion is severe.

Included in mapping are small areas of Ferris, Heiden, Silsby, and Sunev soils. The included soils make up less than 15 percent of the mapped areas.

This soil is used as pasture and for urban development. Because of the erosion hazard it is not suitable for cultivation.

This soil has medium potential for use as pasture. Runoff, erosion, and the high content of calcium carbonate are the main limitations.

This soil has low potential for urban development. The high shrink-swell potential, low soil strength, corrosivity, and the hazard of erosion are limitations to urban use.

This soil is in capability subclass VIe and in the Clay Loam range site.

2—Arents, loamy, gently undulating. This map unit is made up of areas that have been mined for gravel and sand. Piles of discarded overburden and remaining soil material have been smoothed, and most pits have been filled with soil material. The areas are lower than the surrounding landscape. Slopes range from 1 to 5 percent. The areas are rectangular and range from 20 to several hundred acres.

Because of mixing during mining operations, these soils do not have uniform layers. In places, there are fragments of soil layers. These soils are mainly sandy clay loam, clay loam, loam, or fine sandy loam in the upper 80 inches. Quartz pebbles are few to common throughout.

The organic matter content is low. Permeability is moderate. The water table is at a depth of 10 to 25 feet. Most areas are subject to flooding unless protected by levees.

Included in mapping are small areas of Bastisil, Dutek, Silawa, Silstid, and Trinity soils. Also included are areas of water in the deeper pits and areas where the surface is covered with thin layers of gravel or sand.

The soils in this map unit are used as pasture and for urban uses, including light industry, race tracks, golf driving ranges, sanitary landfills, and residential areas.

These soils have medium potential for use as pasture. Because of the low organic matter content, fertilizer is needed for good forage production.

These soils have low potential for urban development. The hazard of flooding in most areas is a limitation, but flooding can be controlled by levees or other flood-control structures. Corrosivity to uncoated steel also is a limitation.

This map unit was not assigned to a capability subclass or a range site.

3—Arents, loamy, hilly. This map unit consists of the discarded overburden of mining operations. The overburden has been left in mounds and ridges in the gravel pits. The areas are rectangular and range from 15 to several hundred acres. Slopes range from 10 to 30 percent. The pits contain areas of water that make up 5 to 25 percent of most mapped areas.

Typically, the soil material, to a depth of 80 inches, is moderately alkaline, light yellowish brown gravelly sandy clay loam. There are fragments of soil layers throughout.

Included in mapping are small areas of Bastisil, Dutek, Frio, Silstid, and Trinity soils. Also included are areas where thin layers of gravel or sand are on the surface. The included soils make up less than 15 percent of the mapped areas.

Permeability is moderate, and the available water capacity is medium. Runoff is rapid. The hazard of erosion is severe.

Most areas of this map unit are idle. A few areas are grazed. These soils have medium potential for use as pasture. The hilly slopes and the inaccessibility of the areas to livestock are limitations to use as pasture.

These soils have very low potential for urban development. The hazard of flooding in most areas is a major limitation, but flooding can be controlled by levees or other flood-control structures. The slopes of the ridges and mounds are a limitation; this limitation can be overcome by land leveling and smoothing. The corrosivity to uncoated steel also is a limitation.

This map unit was not assigned to a capability subclass or a range site.

4—Arents, clayey, gently undulating. This map unit consists of clayey soil material removed from nearby road cuts, borrow pits, or drainage ditches. This material has been piled into mounds several feet high. The areas are rectangular and range from 15 to 75 acres.



Typically, the soil material is dark brown, calcareous clay. It has many clods and bodies consisting of very dark brown and very dark grayish brown fragments of surface soil. In a few places, pebbles and broken concrete make up as much as 25 percent of the soil material.

Most areas of this map unit are idle and are covered with thick stands of johnsongrass. A few areas are used as building sites.

Permeability is slow to very slow, and the available water capacity is high. Runoff is medium.


Reference 9

NATIONAL WETLANDS INVENTORY
UNITED STATES DEPARTMENT OF THE INTERIOR



SPECIAL NOTE
This document was prepared primarily by stereoscopic analysis of high altitude aerial photographs. Wetlands were identified on the photographs based on vegetation, visible hydrology, and geography in accordance with the Classification of Wetlands and Deepwater Habitats of the United States (FWS/OBS-79/31 December 1979). The aerial photographs typically reflect conditions existing during the year and season when they were taken. In addition, there is a margin of error inherent in the use of the aerial photographs. Thus, a detailed on the ground and historical analysis of a single site may result in a revision of the wetland boundaries established through photographic interpretation. In addition, some small wetlands and those obscured by dense forest cover may not be included on this document.

Federal, State and local regulatory agencies with jurisdiction over wetlands may define and describe wetlands in a different manner than that used in this inventory. There is no attempt, in either the design or products of this inventory, to define the limits of proprietary jurisdiction of any Federal, State or local government or to establish the geographical scope of the regulatory programs of government agencies. Persons intending to engage in activities involving modifications within or adjacent to wetland areas should seek the advice of appropriate Federal, State or local agencies concerning specified agency regulatory programs and proprietary jurisdictions that may affect such activities.



NOTES TO THE USER
• Wetlands which have been field examined are indicated on the map by an asterisk (*).
• Additions or corrections to the wetlands information displayed on this map are solicited. Please forward such information to the address indicated.
• Subsystems, Classes, Subclasses, and Water Regimes in this map were developed specifically for NATIONAL WETLANDS INVENTORY mapping.
• Some areas designated as R45B, R45BW, or R45BJ (INTERMITTENT STREAMS) may not meet the definition of wetland.
• This map uses the class Unconsolidated Shore (US). On earlier NWS maps that class was designated Beach/Bar (B) or Flat (F). Subclasses remain the same in both versions.

U.S. DEPARTMENT OF THE INTERIOR
FISH AND WILDLIFE SERVICE
Prepared by National Wetlands Inventory

AERIAL PHOTOGRAPHY
DATE 11/82 DATE 1989
SCALE 1:65,000 SCALE
TYPE CIR TYPE

SYSTEM

SUBSYSTEM

CLASS

Subclass

M - MARINE

1 - SUBTIDAL

2 - INTERTIDAL

1 - SUBTIDAL

2 - INTERTIDAL

1 - SUBTIDAL

2 - INTERTIDAL

1 - SUBTIDAL

2 - INTERTIDAL

1 - SUBTIDAL

2 - INTERTIDAL

1 - SUBTIDAL

2 - INTERTIDAL

SYSTEM

SUBSYSTEM

CLASS

Subclass

R - RIVERINE

1 - TIDAL

2 - LOWER PERENNIAL

3 - UPPER PERENNIAL

4 - INTERMITTENT

5 - UNKNOWN PERENNIAL

1 - TIDAL

2 - LOWER PERENNIAL

3 - UPPER PERENNIAL

4 - INTERMITTENT

5 - UNKNOWN PERENNIAL

1 - TIDAL

2 - LOWER PERENNIAL

3 - UPPER PERENNIAL

4 - INTERMITTENT

5 - UNKNOWN PERENNIAL

1 - TIDAL

2 - LOWER PERENNIAL

3 - UPPER PERENNIAL

4 - INTERMITTENT

5 - UNKNOWN PERENNIAL

SYSTEM

SUBSYSTEM

CLASS

Subclass

L - LACUSTRINE

1 - LIMNETIC

2 - LITTORAL

1 - LIMNETIC

2 - LITTORAL

1 - LIMNETIC

2 - LITTORAL

1 - LIMNETIC

2 - LITTORAL

SYSTEM

SUBSYSTEM

CLASS

Subclass

P - PALUSTRINE

1 - TIDAL

2 - LOWER PERENNIAL

3 - UPPER PERENNIAL

4 - INTERMITTENT

5 - UNKNOWN PERENNIAL

1 - TIDAL

2 - LOWER PERENNIAL

3 - UPPER PERENNIAL

4 - INTERMITTENT

5 - UNKNOWN PERENNIAL

1 - TIDAL

2 - LOWER PERENNIAL

3 - UPPER PERENNIAL

4 - INTERMITTENT

5 - UNKNOWN PERENNIAL

1 - TIDAL

2 - LOWER PERENNIAL

3 - UPPER PERENNIAL

4 - INTERMITTENT

5 - UNKNOWN PERENNIAL

SYSTEM

SUBSYSTEM

CLASS

Subclass

MODIFIERS

WATER REGIME

WATER CHEMISTRY

SOIL

SPECIAL MODIFIERS

Non-Tidal

Tidal

Coastal Halinity

Inland Salinity

pH Modifiers for all Fresh Water

A. Temporarily Flooded

B. Seasonally Flooded

C. Seasonally Flooded with Dry Period

D. Seasonally Flooded with Dry Period

E. Seasonally Flooded with Dry Period

F. Seasonally Flooded with Dry Period

G. Seasonally Flooded with Dry Period

H. Seasonally Flooded with Dry Period

I. Seasonally Flooded with Dry Period

K. Artificially Flooded

L. Substrate

M. Artificially Flooded

N. Artificially Flooded

O. Artificially Flooded

P. Artificially Flooded

Q. Artificially Flooded

R. Artificially Flooded

S. Artificially Flooded

T. Temporarily Flooded

U. Seasonally Flooded

V. Seasonally Flooded

W. Seasonally Flooded

X. Seasonally Flooded

Y. Seasonally Flooded

Z. Seasonally Flooded

AA. Seasonally Flooded

AB. Seasonally Flooded

AC. Seasonally Flooded

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic

7. Eutrophic

8. Eutrophic

9. Eutrophic

1. Hyaline

2. Eutrophic

3. Eutrophic

4. Eutrophic

5. Eutrophic

6. Eutrophic


7. Eutrophic

8. Eutrophic

9. Eutrophic

NATIONAL WETLANDS INVENTORY
UNITED STATES DEPARTMENT OF THE INTERIOR

WHITE ROCK LAKE, TEX.



WHITE ROCK LAKE, TEX.



U.S. DEPARTMENT OF THE INTERIOR
FISH AND WILDLIFE SERVICE

Prepared by National Wetlands Inventory


1989

SPECIAL NOTE

This document was prepared primarily by stereoscopic analysis of high altitude aerial photographs. Wetlands were identified on the photographs based on vegetation, visible hydrology, and geography in accordance with Classification of Wetlands and Deepwater Habitats of the United States (FWS/OBS - 79/31 December 1979). The aerial photographs typically reflect conditions during the specific year and season when they were taken. In addition, there is a significant error inherent in the use of the aerial photographs. Thus, a detailed on the ground and historical analysis of a single site may result in a revision of the wetland boundaries established through photographic interpretation. In addition, some small wetlands and those obscured by dense forest cover may not be included on this document.

For Federal, State and local regulatory agencies with jurisdiction over wetlands may define and designate wetlands in a different manner than that used in this inventory. Therefore, an attempt, in either the design or products of this inventory, to define the limits of proprietary jurisdiction of any Federal, State or local government or to establish the geographical scope of the regulatory programs of government agencies. Persons intended to engage in activities involving developments within or adjacent to wetland areas should seek the advice of appropriate Federal, State or local agencies concerning the agency regulatory programs and proprietary jurisdictions that may affect such activities.

SYMBOLGY EXAMPLE



NOTES TO THE USER:

- Wetlands which have been field examined are indicated on the map by an asterisk (*).
- Additions or corrections to the wetlands information displayed on this map are solicited. Please forward such information to the address indicated.
- Subsystems, Classes, Subclasses, and Water Regimes in *italics* were developed specifically for NATIONAL WETLANDS INVENTORY mapping.
- Some areas designated as R4SB, R4SNW, OR R4SEU (INTERMITTENT STRAMS) may not meet the definition of a Strand.
- This map uses the class Unconsolidated Shore (US). On earlier NWI maps, that class was designated Beach/Bar (BB), or Flat (FL). Subclasses remain the same in both versions.

AERIAL PHOTOGRAPHY

DATE: 11 / / 82 DATE: / /
SCALE: 1:65000 SCALE:
TYPE: CIR TYPE:

SYSTEM

SUBSYSTEM

CLASS

SUBCLASS

1 - SUBTIDAL

2 - INTERTIDAL

RS - ROCK BOTTOM

US - UNCONSOLIDATED BOTTOM

AB - AQUATIC BED

RF - REEF

OW - OPEN WATER/Unknown Bottom

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Vascular

3 Worm

4 Submerged

1 Coral

2 Rubic

3 Mud

4 Organic

1 Benthic

2 Rubic

3 Mud

4 Organic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Vascular

3 Worm

4 Submerged

1 Coral

2 Rubic

3 Mud

4 Organic

SYSTEM

SUBSYSTEM

CLASS

SUBCLASS

1 - TIDAL

2 - LOWER PERENNIAL

3 - UPPER PERENNIAL

4 - INTERMITTENT

5 - UNKNOWN PERENNIAL

RS - ROCK BOTTOM

US - UNCONSOLIDATED BOTTOM

SS - STREAMED

AB - AQUATIC BED

RS - ROCKY SHORE

US - UNCONSOLIDATED SHORE

FM - EMERGENT

OW - OPEN WATER/Unknown Bottom

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

SYSTEM

SUBSYSTEM

CLASS

SUBCLASS

1 - LIMNETIC

2 - LITTORAL

RS - ROCK BOTTOM

US - UNCONSOLIDATED BOTTOM

AB - AQUATIC BED

OW - OPEN WATER/Unknown Bottom

RS - ROCK BOTTOM

US - UNCONSOLIDATED BOTTOM

AB - AQUATIC BED

RF - REEF

RS - ROCKY SHORE

US - UNCONSOLIDATED SHORE

FM - EMERGENT

OW - OPEN WATER/Unknown Bottom

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

6 Unknown Surface

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

6 Unknown Surface

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

6 Unknown Surface

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

6 Unknown Surface

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

6 Unknown Surface

SYSTEM

SUBSYSTEM

CLASS

SUBCLASS

1 - TIDAL

2 - LOWER PERENNIAL

3 - UPPER PERENNIAL

4 - INTERMITTENT

5 - UNKNOWN PERENNIAL

RS - ROCK BOTTOM

US - UNCONSOLIDATED BOTTOM

SS - STREAMED

AB - AQUATIC BED

RS - ROCKY SHORE

US - UNCONSOLIDATED SHORE

FM - EMERGENT

OW - OPEN WATER/Unknown Bottom

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

SYSTEM

SUBSYSTEM

CLASS

SUBCLASS

1 - TIDAL

2 - LOWER PERENNIAL

3 - UPPER PERENNIAL

4 - INTERMITTENT

5 - UNKNOWN PERENNIAL

RS - ROCK BOTTOM

US - UNCONSOLIDATED BOTTOM

SS - STREAMED

AB - AQUATIC BED

RS - ROCKY SHORE

US - UNCONSOLIDATED SHORE

FM - EMERGENT

OW - OPEN WATER/Unknown Bottom

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

SYSTEM

SUBSYSTEM

CLASS

SUBCLASS

1 - TIDAL

2 - LOWER PERENNIAL

3 - UPPER PERENNIAL

4 - INTERMITTENT

5 - UNKNOWN PERENNIAL

RS - ROCK BOTTOM

US - UNCONSOLIDATED BOTTOM

SS - STREAMED

AB - AQUATIC BED

RS - ROCKY SHORE

US - UNCONSOLIDATED SHORE

FM - EMERGENT

OW - OPEN WATER/Unknown Bottom

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

SYSTEM

SUBSYSTEM

CLASS

SUBCLASS

1 - TIDAL

2 - LOWER PERENNIAL

3 - UPPER PERENNIAL

4 - INTERMITTENT

5 - UNKNOWN PERENNIAL

RS - ROCK BOTTOM

US - UNCONSOLIDATED BOTTOM

SS - STREAMED

AB - AQUATIC BED

RS - ROCKY SHORE

US - UNCONSOLIDATED SHORE

FM - EMERGENT

OW - OPEN WATER/Unknown Bottom

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

SYSTEM

SUBSYSTEM

CLASS

SUBCLASS

1 - TIDAL

2 - LOWER PERENNIAL

3 - UPPER PERENNIAL

4 - INTERMITTENT

5 - UNKNOWN PERENNIAL

RS - ROCK BOTTOM

US - UNCONSOLIDATED BOTTOM

SS - STREAMED

AB - AQUATIC BED

RS - ROCKY SHORE

US - UNCONSOLIDATED SHORE

FM - EMERGENT

OW - OPEN WATER/Unknown Bottom

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

SYSTEM

SUBSYSTEM

CLASS

SUBCLASS

1 - TIDAL

2 - LOWER PERENNIAL

3 - UPPER PERENNIAL

4 - INTERMITTENT

5 - UNKNOWN PERENNIAL

RS - ROCK BOTTOM

US - UNCONSOLIDATED BOTTOM

SS - STREAMED

AB - AQUATIC BED

RS - ROCKY SHORE

US - UNCONSOLIDATED SHORE

FM - EMERGENT

OW - OPEN WATER/Unknown Bottom

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

SYSTEM

SUBSYSTEM

CLASS

SUBCLASS

1 - TIDAL

2 - LOWER PERENNIAL

3 - UPPER PERENNIAL

4 - INTERMITTENT

5 - UNKNOWN PERENNIAL

RS - ROCK BOTTOM

US - UNCONSOLIDATED BOTTOM

SS - STREAMED

AB - AQUATIC BED

RS - ROCKY SHORE

US - UNCONSOLIDATED SHORE

FM - EMERGENT

OW - OPEN WATER/Unknown Bottom

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

SYSTEM

SUBSYSTEM

CLASS

SUBCLASS

1 - TIDAL

2 - LOWER PERENNIAL

3 - UPPER PERENNIAL

4 - INTERMITTENT

5 - UNKNOWN PERENNIAL

RS - ROCK BOTTOM

US - UNCONSOLIDATED BOTTOM

SS - STREAMED

AB - AQUATIC BED

RS - ROCKY SHORE

US - UNCONSOLIDATED SHORE

FM - EMERGENT

OW - OPEN WATER/Unknown Bottom

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

SYSTEM

SUBSYSTEM

CLASS

SUBCLASS

1 - TIDAL

2 - LOWER PERENNIAL

3 - UPPER PERENNIAL

4 - INTERMITTENT

5 - UNKNOWN PERENNIAL

RS - ROCK BOTTOM

US - UNCONSOLIDATED BOTTOM

SS - STREAMED

AB - AQUATIC BED

RS - ROCKY SHORE

US - UNCONSOLIDATED SHORE

FM - EMERGENT

OW - OPEN WATER/Unknown Bottom

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

SYSTEM

SUBSYSTEM

CLASS

SUBCLASS

1 - TIDAL

2 - LOWER PERENNIAL

3 - UPPER PERENNIAL

4 - INTERMITTENT

5 - UNKNOWN PERENNIAL

RS - ROCK BOTTOM

US - UNCONSOLIDATED BOTTOM

SS - STREAMED

AB - AQUATIC BED

RS - ROCKY SHORE

US - UNCONSOLIDATED SHORE

FM - EMERGENT

OW - OPEN WATER/Unknown Bottom

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

SYSTEM

SUBSYSTEM

CLASS

SUBCLASS

1 - TIDAL

2 - LOWER PERENNIAL

3 - UPPER PERENNIAL

4 - INTERMITTENT

5 - UNKNOWN PERENNIAL

RS - ROCK BOTTOM

US - UNCONSOLIDATED BOTTOM

SS - STREAMED

AB - AQUATIC BED

RS - ROCKY SHORE

US - UNCONSOLIDATED SHORE

FM - EMERGENT

OW - OPEN WATER/Unknown Bottom

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

SYSTEM

SUBSYSTEM

CLASS

SUBCLASS

1 - TIDAL

2 - LOWER PERENNIAL

3 - UPPER PERENNIAL

4 - INTERMITTENT

5 - UNKNOWN PERENNIAL

RS - ROCK BOTTOM

US - UNCONSOLIDATED BOTTOM

SS - STREAMED

AB - AQUATIC BED

RS - ROCKY SHORE

US - UNCONSOLIDATED SHORE

FM - EMERGENT

OW - OPEN WATER/Unknown Bottom

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

SYSTEM

SUBSYSTEM

CLASS

SUBCLASS

1 - TIDAL

2 - LOWER PERENNIAL

3 - UPPER PERENNIAL

4 - INTERMITTENT

5 - UNKNOWN PERENNIAL

RS - ROCK BOTTOM

US - UNCONSOLIDATED BOTTOM

SS - STREAMED

AB - AQUATIC BED

RS - ROCKY SHORE

US - UNCONSOLIDATED SHORE

FM - EMERGENT

OW - OPEN WATER/Unknown Bottom

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

SYSTEM

SUBSYSTEM

CLASS

SUBCLASS

1 - TIDAL

2 - LOWER PERENNIAL

3 - UPPER PERENNIAL

4 - INTERMITTENT

5 - UNKNOWN PERENNIAL

RS - ROCK BOTTOM

US - UNCONSOLIDATED BOTTOM

SS - STREAMED

AB - AQUATIC BED

RS - ROCKY SHORE

US - UNCONSOLIDATED SHORE

FM - EMERGENT

OW - OPEN WATER/Unknown Bottom

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

3 Mud

4 Organic

1 Algal

2 Rhizoid Moss

3 Rhizoid Vascular

4 Floating Vascular

5 Mud

6 Organic

7 Vegetated

1 Benthic

2 Rubic

1 Cobble Gravel

2 Sand

Reference 10

U.S. Census Bureau *the Official Statistics™*



WELCOME!
MABLE/Geocorr V2.5
Geographic Correspondence Engine

[\[OSED Mirror\]](#) | [\[SEDAC Mirror\]](#) | [\[CENSUS Mirror\]](#)

This application allows you to access the MABLE geographic data base and to generate custom "correlation lists" as reports and/or files.

[Help](#) | [Examples](#) | [Usage Notes](#)
[Output Samples](#) | [New in V2](#) | [Articles](#) | [Future](#)

This form has 5 main sections. Only the first 2 are required.

[Input](#) | [Output](#) | [Point & Distance](#) | [Bounding Box](#) | [Geographic Filter](#)

Note: In most of the select-list boxes below you can make multiple selections. Some browsers require that you hold down the ctrl key while clicking before it will recognize multiple selections.

● **Input Options**

Select state(s) to process. (Limit of 5 states on weekdays, 7 AM - 6 PM)
 (Required Option)

| |
|-------------|
| ALABAMA |
| ALASKA |
| ARIZONA |
| ARKANSAS |
| CALIFORNIA |
| COLORADO |
| CONNECTICUT |
| DELAWARE |

For background information and help with any of the geographic codes used in the MABLE database (source/target geocodes) consult the file:

● **MAGGOT** ●

(Master Area Geographic Glossary Of Terms)

Select "SOURCE" Geocode(s)

Select "TARGET" Geocode(s)

Geocorr Population Ring Totals

Latitude 32.708239

Longitude 96.70169

| COUNTY | TRACT | BG | RING | POP | AFACT |
|--------|--------|----|------------|-------|-------|
| 48113 | 116.01 | 3 | 0.25 | 270 | 0.229 |
| | | | Ring Total | 270 | |
| 48113 | 93.04 | 3 | 0.5 | 205 | 0.272 |
| 48113 | 93.04 | 4 | 0.5 | 160 | 0.106 |
| 48113 | 116.01 | 2 | 0.5 | 259 | 0.268 |
| 48113 | 116.01 | 3 | 0.5 | 911 | 0.771 |
| | | | Ring Total | 1535 | |
| 48113 | 93.03 | 1 | 1 | 265 | 0.17 |
| 48113 | 93.03 | 3 | 1 | 338 | 0.236 |
| 48113 | 93.04 | 1 | 1 | 827 | 0.826 |
| 48113 | 93.04 | 2 | 1 | 1844 | 1 |
| 48113 | 93.04 | 3 | 1 | 548 | 0.728 |
| 48113 | 93.04 | 4 | 1 | 1104 | 0.73 |
| 48113 | 116.01 | 1 | 1 | 717 | 0.642 |
| 48113 | 116.01 | 2 | 1 | 707 | 0.732 |
| 48113 | 116.01 | 4 | 1 | 117 | 0.112 |
| | | | Ring Total | 6467 | |
| 48113 | 91.02 | 3 | 2 | 65 | 0.072 |
| 48113 | 91.02 | 4 | 2 | 1296 | 0.849 |
| 48113 | 91.02 | 5 | 2 | 408 | 0.408 |
| 48113 | 91.02 | 6 | 2 | 272 | 0.336 |
| 48113 | 92.02 | 2 | 2 | 425 | 0.388 |
| 48113 | 92.02 | 3 | 2 | 581 | 1 |
| 48113 | 92.02 | 4 | 2 | 213 | 0.203 |
| 48113 | 93.01 | 1 | 2 | 517 | 1 |
| 48113 | 93.01 | 2 | 2 | 1028 | 1 |
| 48113 | 93.01 | 3 | 2 | 1114 | 1 |
| 48113 | 93.01 | 4 | 2 | 535 | 1 |
| 48113 | 93.03 | 1 | 2 | 1295 | 0.83 |
| 48113 | 93.03 | 2 | 2 | 1327 | 1 |
| 48113 | 93.03 | 3 | 2 | 1092 | 0.764 |
| 48113 | 93.04 | 1 | 2 | 174 | 0.174 |
| 48113 | 93.04 | 4 | 2 | 248 | 0.164 |
| 48113 | 114.02 | 1 | 2 | 14 | 0.015 |
| 48113 | 116.01 | 1 | 2 | 400 | 0.358 |
| 48113 | 116.01 | 4 | 2 | 929 | 0.888 |
| 48113 | 116.02 | 1 | 2 | 735 | 1 |
| 48113 | 116.02 | 2 | 2 | 344 | 1 |
| 48113 | 116.02 | 3 | 2 | 235 | 0.232 |
| 48113 | 117 | 5 | 2 | 621 | 0.994 |
| | | | Ring Total | 13868 | |

| COUNTY | TRACT | BG | RING | POP | AFACT |
|--------|--------|----|------------|-------|-------|
| 48113 | 91.01 | 2 | 3 | 138 | 0.202 |
| 48113 | 91.01 | 4 | 3 | 111 | 0.082 |
| 48113 | 91.02 | 1 | 3 | 1096 | 1 |
| 48113 | 91.02 | 2 | 3 | 1515 | 1 |
| 48113 | 91.02 | 3 | 3 | 835 | 0.928 |
| 48113 | 91.02 | 4 | 3 | 230 | 0.151 |
| 48113 | 91.02 | 5 | 3 | 591 | 0.592 |
| 48113 | 91.02 | 6 | 3 | 537 | 0.664 |
| 48113 | 91.02 | 7 | 3 | 987 | 1 |
| 48113 | 92.01 | 1 | 3 | 70 | 0.06 |
| 48113 | 92.01 | 2 | 3 | 565 | 0.86 |
| 48113 | 92.01 | 3 | 3 | 859 | 1 |
| 48113 | 92.01 | 4 | 3 | 704 | 0.506 |
| 48113 | 92.01 | 5 | 3 | 763 | 1 |
| 48113 | 92.02 | 1 | 3 | 1672 | 1 |
| 48113 | 92.02 | 2 | 3 | 670 | 0.612 |
| 48113 | 92.02 | 4 | 3 | 836 | 0.797 |
| 48113 | 114.02 | 1 | 3 | 900 | 0.981 |
| 48113 | 115 | 1 | 3 | 74 | 0.063 |
| 48113 | 116.02 | 3 | 3 | 779 | 0.768 |
| 48113 | 116.02 | 4 | 3 | 70 | 0.107 |
| 48113 | 117 | 3 | 3 | 574 | 0.488 |
| 48113 | 117 | 4 | 3 | 1631 | 1 |
| 48113 | 117 | 5 | 3 | 4 | 0.006 |
| 48113 | 117 | 6 | 3 | 1330 | 0.92 |
| 48113 | 117 | 8 | 3 | 170 | 0.425 |
| 48113 | 118 | 3 | 3 | 40 | 0.021 |
| 48113 | 118 | 4 | 3 | 1002 | 0.951 |
| 48113 | 119 | 3 | 3 | 102 | 0.068 |
| 48113 | 169.02 | 1 | 3 | 76 | 0.157 |
| 48113 | 171 | 3 | 3 | 8 | 0.016 |
| | | | Ring Total | 18939 | |

| | | | | | |
|-------|-------|---|---|------|---|
| 48113 | 39.02 | 2 | 4 | 184 | 1 |
| 48113 | 39.02 | 3 | 4 | 475 | 1 |
| 48113 | 84 | 5 | 4 | 313 | 1 |
| 48113 | 84 | 6 | 4 | 438 | 1 |
| 48113 | 85 | 3 | 4 | 250 | 1 |
| 48113 | 85 | 4 | 4 | 2 | 1 |
| 48113 | 86.02 | 1 | 4 | 189 | 1 |
| 48113 | 86.02 | 2 | 4 | 1989 | 1 |
| 48113 | 87.01 | 1 | 4 | 569 | 1 |
| 48113 | 87.01 | 2 | 4 | 1200 | 1 |
| 48113 | 87.01 | 3 | 4 | 789 | 1 |
| 48113 | 87.01 | 4 | 4 | 1068 | 1 |
| 48113 | 87.01 | 5 | 4 | 1487 | 1 |
| 48113 | 90.02 | 1 | 4 | 794 | 1 |
| 48113 | 90.02 | 2 | 4 | 1041 | 1 |

| COUNTY | TRACT | BG | RING | POP | AFACT | |
|-----------------|--------|----|------|-------|-------|-------|
| 48113 | 90.02 | | 3 | 4 | 1353 | 1 |
| 48113 | 90.02 | | 4 | 4 | 953 | 1 |
| 48113 | 91.01 | | 1 | 4 | 918 | 1 |
| 48113 | 91.01 | | 2 | 4 | 546 | 0.798 |
| 48113 | 91.01 | | 3 | 4 | 1031 | 1 |
| 48113 | 91.01 | | 4 | 4 | 1242 | 0.918 |
| 48113 | 91.01 | | 5 | 4 | 1072 | 1 |
| 48113 | 92.01 | | 1 | 4 | 1090 | 0.94 |
| 48113 | 92.01 | | 2 | 4 | 92 | 0.14 |
| 48113 | 92.01 | | 4 | 4 | 687 | 0.494 |
| 48113 | 114.01 | | 1 | 4 | 679 | 1 |
| 48113 | 114.02 | | 1 | 4 | 3 | 0.003 |
| 48113 | 115 | | 1 | 4 | 1102 | 0.937 |
| 48113 | 115 | | 4 | 4 | 1755 | 1 |
| 48113 | 116.02 | | 4 | 4 | 585 | 0.893 |
| 48113 | 116.02 | | 5 | 4 | 692 | 1 |
| 48113 | 117 | | 1 | 4 | 1049 | 1 |
| 48113 | 117 | | 2 | 4 | 1516 | 1 |
| 48113 | 117 | | 3 | 4 | 603 | 0.512 |
| 48113 | 117 | | 6 | 4 | 115 | 0.08 |
| 48113 | 117 | | 7 | 4 | 457 | 1 |
| 48113 | 117 | | 8 | 4 | 230 | 0.575 |
| 48113 | 118 | | 1 | 4 | 70 | 1 |
| 48113 | 118 | | 2 | 4 | 2634 | 1 |
| 48113 | 118 | | 3 | 4 | 1884 | 0.979 |
| 48113 | 118 | | 4 | 4 | 52 | 0.049 |
| 48113 | 119 | | 1 | 4 | 1035 | 1 |
| 48113 | 119 | | 2 | 4 | 1445 | 1 |
| 48113 | 119 | | 3 | 4 | 1394 | 0.932 |
| 48113 | 119 | | 4 | 4 | 664 | 1 |
| 48113 | 120 | | 1 | 4 | 209 | 1 |
| 48113 | 120 | | 2 | 4 | 420 | 1 |
| 48113 | 169.01 | | 1 | 4 | 1088 | 1 |
| 48113 | 169.01 | | 2 | 4 | 1289 | 1 |
| 48113 | 169.02 | | 1 | 4 | 408 | 0.843 |
| 48113 | 171 | | 3 | 4 | 485 | 0.984 |
| Ring Total | | | | 41635 | | |
| Four-Mile Total | | | | 82714 | | |

Reference 11

EPA

NPDES Compliance Inspection Report

Section A: National Data System Coding

| | | | | |
|--|--------------------|--------------------------------|--------------------------|-------------------------|
| Transaction Code 1 N 2 5 3 N O P E R M I T 11 12 9 6 1 2 1 2 17 | NPDES yr/mo/day | Inspection Type 18 W | Inspector 19 R | Fac Type 20 2 |
| 21 M u l t i - s e c t o r S i t o r m W a t e r 66 | | | | |
| Facility Evaluation Rating 57 69 70 1 71 72 73 74 75 80 | | | | |

Section B: Facility Data

| | | | |
|---|--|--|------------------------------------|
| Name and Location of Facility Inspected Nethery Recycling Facility 500 Deepwood Street Dallas, TX 75217 | | Entry Time 2:15 pm | Permit Effective Date |
| Name(s) of On-Site Representative(s) Herman Gibbons Harlee Jimerson | | Exit Time/Date 4:00 pm, 12/12/96 | Permit Expiration Date |
| Title(s) Owner/Facility Manager Part-time Mechanic | | Phone No(s) (214) 371-0863 | |
| Name, Address of Responsible Official Herman Gibbons or Herman Nethery 915 Oak Park Drive Dallas, Texas 75232 | | Title Owners | Phone No. (214) 222-2350 |
| | | Contacted <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | |

Section C: Areas Evaluated During Inspection

(S = Satisfactory, M = Marginal, U = Unsatisfactory, N = Not Evaluated)

| | | | |
|--|--|---|---|
| <input type="checkbox"/> Permit | <input type="checkbox"/> Flow Measurement | <input type="checkbox"/> Stormwater | <input type="checkbox"/> CSO/SSO (Sewer Overflow) |
| <input type="checkbox"/> Records/Reports | <input type="checkbox"/> Self-Monitoring Program | <input type="checkbox"/> Sludge Handling/Disposal | <input type="checkbox"/> Pollution Prevention |
| <input type="checkbox"/> Facility Site Review | <input type="checkbox"/> Compliance Schedules | <input type="checkbox"/> Pretreatment | <input type="checkbox"/> Multimedia |
| <input type="checkbox"/> Effluent/Receiving Waters | <input type="checkbox"/> Laboratory | <input type="checkbox"/> Operations & Maintenance | <input type="checkbox"/> Other: |

Section D: Summary of Findings/Comments (Attach additional sheets if necessary)

See attached report and Photolog.

| | | |
|---|---|------------------------|
| Names(s) and Signature(s) of Inspector(s) Kenn A. Smith | Agency/Office/Telephone EPA/6EN-AS/(214) 665-8047 | Date 1/27/97 |
| Robert H. Reeves, P.E. | EPA/6EN-AS/(214) 665-8364 | |
| Nelson F. Smith, P.E. | EPA/6EN-WT/(214) 665-6466 | |
| Signature of Reviewer [Signature] | Agency/Office EPA/6EN-AS/214-665-8376 | Date 1/28/97 |

Reference 12

NATIONAL FLOOD INSURANCE PROGRAM

FLOODWAY
FLOOD BOUNDARY AND
FLOODWAY MAP

CITY OF
DALLAS, TEXAS
DALLAS, DENTON, COLLIN,
ROCKWALL AND KAUFMAN
COUNTIES

PANEL 180 OF 235

(SEE MAP INDEX FOR PANELS NOT PRINTED)

COMMUNITY-PANEL NUMBER

480171 0180

MAP REVISED:

JULY 2, 1991



Federal Emergency Management Agency

Reference 13

Texas Parks & Wildlife
Annotated County Lists of Rare Species

Last Revision: 8/13/98
Page 1 of 2

DALLAS COUNTY

Michelle Brown
295

| Federal Status | State Status |
|----------------|--------------|
|----------------|--------------|

*** BIRDS ***

Arctic Peregrine Falcon (*Falco peregrinus tundrius*) - due to similar field characteristics, treat all Peregrine Falcons as federal listed Endangered; potential migrant

| | |
|------|---|
| E/SA | T |
|------|---|

Bald Eagle (*Haliaeetus leucocephalus*) - found primarily near seacoasts, rivers, and large lakes; nests in tall trees or on cliffs near water; communally roosts, especially in winter; hunts live prey, scavenges, and pirates food from other birds

| | |
|----|---|
| LT | T |
|----|---|

Black-capped Vireo (*Vireo atricapillus*) - oak-juniper woodlands with distinctive patchy, two-layered aspect; shrub and tree layer with open, grassy spaces; requires foliage reaching to ground level for nesting cover; return to same territory, or one nearby, year after year; deciduous and broad-leaved shrubs and trees provide insects for feeding; species composition less important than presence of adequate broad-leaved shrubs, foliage to ground level, and required structure; nesting season March-late summer

| | |
|----|---|
| LE | E |
|----|---|

Henslow's Sparrow (*Ammodramus henslowii*) - wintering individuals (not flocks) found in weedy fields or cut-over areas where lots of bunch grasses occur along with vines and brambles; a key component is bare ground for running/walking; likely to occur, but few records within this county

Interior Least Tern (*Sterna antillarum athalassos*) - nests along sand and gravel bars within braided streams and rivers; also known to nest on man-made structures

| | |
|----|---|
| LE | E |
|----|---|

Migrant Loggerhead Shrike (*Lanius ludovicianus migrans*) - open and semi-open grassy areas with scattered trees and brush; breeding March-late August

Western Burrowing Owl (*Athene cunicularia hypugaea*) - open grasslands, especially prairie, plains, and savanna, sometimes in open areas such as vacant lots near human habitation or airports; nests and roosts in abandoned burrows

Whooping Crane (*Grus americana*) - potential migrant

| | |
|----|---|
| LE | E |
|----|---|

Wood Stork (*Mycteria americana*) - forages in prairie ponds, flooded pastures or fields, ditches, and other shallow standing water, including salt-water; usually roosts communally in tall snags, sometimes in association with other wading birds (i.e. active heronries); breeds in Mexico and birds move into Gulf States in search of mud flats and other wetlands, even those associated with forested areas; formerly nested in Texas, but no breeding records since 1960

| | |
|--|---|
| | T |
|--|---|

*** INSECTS ***

Black Lordithon Rove Beetle (*Lordithon niger*) - historically known from Texas

*** MAMMALS ***

Plains Spotted Skunk (*Spilogale putorius interrupta*) - catholic; open fields, prairies, croplands, fence rows, farmyards, forest edges, and woodlands; prefers wooded, brushy areas and tallgrass prairie

*** REPTILES ***

Texas Garter Snake (*Thamnophis sirtalis annectens*) - wet or moist microhabitats are conducive to the species occurrence, but is not necessarily restricted to them; hibernates underground or in or under surface cover; breeds March-August

Texas Parks & Wildlife
Annotated County Lists of Rare Species
DALLAS COUNTY, cont'd

Last Revision: 8/13/98
Page 2 of 2

| | Federal Status | State Status |
|---|-------------------|-----------------|
| Texas Horned Lizard (<i>Phrynosoma cornutum</i>) - open, arid and semi-arid regions with sparse vegetation, including grass, cactus, scattered brush or scrubby trees; soil may vary in texture from sandy to rocky; burrows into soil, enters rodent burrows, or hides under rock when inactive; breeds March-September | | T |
| Timber/Canebrake Rattlesnake (<i>Crotalus horridus</i>) - swamps, floodplains, upland pine and deciduous woodlands, riparian zones, abandoned farmland, limestone bluffs; sandy soil or black clay; prefers dense ground cover, i.e. grapevines or palmetto | | T |

*** VASCULAR PLANTS ***

Warnock's coral root (*Hexalectris warnockii*) - leaf litter and humus in oak-juniper woodlands in mountain canyons in the Trans Pecos but at lower elevations to the east, often on narrow terraces along creekbeds

LE, LT - Federally Listed Endangered/Threatened
PE, PT - Federally Proposed Endangered/Threatened
E/SA, T/SA - Federally Endangered/Threatened by Similarity of Appearance
C1 - Federal Candidate, Category 1; information supports proposing to list as endangered/threatened
DL, PDL - Federally Delisted/Proposed Delisted
E, T - State Endangered/Threatened
"blank" - Rare, but with no regulatory listing status

Species appearing on these lists do not share the same probability of occurrence. Some species are migrants or wintering residents only, or may be historic or considered extirpated.

Reference 14



Eagle Results

Use of these geocoding results is subject to RESTRICTIONS

| Original Address | Standard Address | Matched Address |
|---|--|-------------------------------------|
| 500 Deepwood Street Dallas, TX 75217 | 500 DEEPWOOD ST DALLAS, TX 75217-5941 | 500 DEEPWOOD ST DALLAS, TX 75217 |

EZLocate returned a Block Face Match from the Etak Map Premium database.

| Location (NAD-27) | Postal | Census |
|--|-----------------------------|---|
| <i>Decimal Degrees Deg:Min:Sec</i> Lat: 32.70823932:42:29.660N Lon: -096.701686 96:42:6.070W | Carrier:C055 DPBC...: 00 | FIPS County...: TX113 UAC.....: 1922 Pop. Density.: U MCD.....: Place.....: TX1085 Tract.....: TX113011601 BlockGroup...:TX1130116013 |

[home/](#) [demo/](#) [comments/](#) [more info/](#) [Etak](#)

Etak, Inc.

A Unit of the Sony Group

1605 Adams Drive

Menlo Park, CA 94025

Tel: 650.328.3825

©Copyright 1998 Etak, Inc.

Reference 15



**ecology and
environment, inc.**

International Specialists in the Environment

Job Number 506-99-03-0001

Nethery Landfill
Dallas, Dallas County, Tx.

080801SIXX

E & E Job Number KJ6104Telephone Code Number 80808Site Name Nethery LandfillCity/State Dallas, TXTDD 506-99-03-0001PAN 080801SIXX

SSID _____

Start/Finish Date 7/1/99, 8/12/99Book 01 of 01

E & E Emergency Response Center: (716) 684-8940

E & E Corporate Center: (716) 684-8060

MEDTOX Hotline: (501) 370-8263

E & E Safety Director (Home): (716) 655-1260

7/1/99

06-99-03-0001

0700 START Michelle Brown
picks-up Blazer at E+E
Warehouse

0800^{MB} START members

M. Brown and Kris Lloyd
have safety meeting
Weather sunny, high
in upper 90s °F.
level D PPE

Meeting conducted at
E+E Office

0915 M. Brown & K. Lloyd
pick-up, SAM Bill Rhotenberry
and intern Latricia
Fitzgerald at EPA bldg.

0945 M. Brown, K. Lloyd,
Rhotenberry & Fitzgerald
Arrive at site

1000 Walking perimeter
of landfill, approx.
20 ft high, primarily
construction materials
Stagnant water in
low-lying areas of
fill. Possible sediment

all the more so known

7/1/99

06-99-03-0001

SXS. From these areas
to the ^{MB} West of fill.
- fenced on the north
side closest to the
residences

11:00 drive to other entrance
off Loop 12, walk
down road, see what
we think is the
Trinity River

11:30 Return to
vehicle, try to drive
to another entrance
to gain access to
site

11:50 Find another
road, entryway, on
SE of site. Roadway
blocked w/ concrete

12:00 Break for lunch

13:00 Decide that
we will go back
to site next week.
Bill will call City of
Dallas and get Keys

- 7/1/99 Michelle Brown

7/1/99

06-99-03-0001

to gates so we will not have to walk on landfill area - too dangerous -

Need to find drainage pathways and PPE to Trinity on next trip.

13:30 Drop off B. Rhotenberry and L. Fitzgerald at

EPA and STARTS
M. Brown + K. Lloyd
return to office.

7/8/99

06-99-03-00

09:15

0930 START members

^{M.B.} Michelle Brown + Kris Lloyd
conduct site safety
meeting. Trip, slip, fall,
biological, flora hazards.

Weather - sunny, high 2
98°F. Meetings ^{M.B.}

conducted in vehicle at
the end of Deepwood St.

0940 M. Brown + K. Lloyd meet

SAM Bill Rhotenberry,
intern Latricia Fitzgerald.
EPA members Jon Kinchen
+ Jana Enders.

at Loop 12 entrance.


Begin to hike dirt
road surrounding fill.

Discovered several vents
to the south of field.

Could hear venting
occurring + smell

sulfur. Having trouble
finding drainage pathways
following what we think

- 7/8/99 Michelle Brown



7/8/99 06-99-03-0001

is a creek to the south of Fill and vents.

Need ariel photographs possibly a boat to better locate Trinity.

12:00 Break for lunch

13:00 START members

M. Brown + K. Lloyd

return to office.

will order ariel photos + meet w/ Bill to plan next step.

7/8/99

Michelle Brown

7/15/99

06-99-03-0001

0855 STARTS Michelle Brown + Kris Lloyd conduct safety meeting at E+E office.

weather pt. cloudy, high 95°F discussed hazards - slip,

trip, fall, bugs, poisoning

0930 Meet SAM, Bill

Rhotenberry at Longview/Riverwood entrance

0945 Attempt to get

Blazer over dirt pile to drive it down

road parallel to Trinity - get stuck

1000 Call warehouse -

talk to START Brian

Mason about helping

us get the Blazer out

1015 START M. Brown +

JAM B. Rhotenberry

walk dirt road to

Elam creek. Discuss

sampling along creek,

at pond of Jim Miller

- 7/15/99 Michelle Brown

7/15/99

CU-99-03-0001

and the outfall from
the pond to the creek
& from creek into

Trinity

1100 STARTS Brian Mason
+ Jay Donahoe get
Blazer.

1115 back at vehicles,
discuss sampling
strategy. 3 samples

at entry wetland,
1 at entry to Elam,
2-3 off Elam, one
soil on edge of fill,
one background

background for Elam,
background for Trinity
(poss. one for wetland)

- all sediment -

1-3 at outfall to west
of Elam

- water samples?

Will walk to other
outfall this afternoon

1200 Break for lunch

- 7/15/99 Michelle Brown

7/15/99

CU-99-03-0001

1315 START M. Brown + SAM
B. Rhotenberry return to
site at Longacre entrance
off Loop 12. START
K. Lloyd returned to
office

1400 Found horseshoe

section of Trinity,
stagnant water,

slow flow, cannot
find PPE into Trinity
but found pathway

to it. Sample at
swamp area to south
of fill + along
pathway to Trinity
(right after fork in
dirt road heads north)

Sample stagnant
water in trench at
fill + follow pathway
down as can get
to Trinity

1450 Return F.M.S Drive
to Jim Miller entrance

- 7/15/99 Michelle Brown

7/15/99

OU-99-03-0001


- to look @ pond to the left of the dirt road
- Take approx. 3 SKS at east pond & at the outflow pathway & PPE to Elam.
- see sketch on pg 11 -
- 1515 M. Brown & B. Khoten-
- berry depart site & head towards office

7/15/99

OU-99-03-0001

(6E#2)

(6E#1)



- 7/15/99 Michelle Greene

Trinity River

8/9/99 06-99-03-0001

START members
 Belle Brown, Maggie Carson,
 Mitchell & Jody Shires
 met at E+E warehouse
 and sampling equipment
 in van. Conduct
 safety meeting
 weather - clear, high
 83°F. Hazards -

trip, fall. Agenda -
 and sampling points +
 select soil / sediment
 samples. PPE - Level D

Arrive at Loop 12
 entrance. Cannot cut
 wire to fence. STARTS
 Carson & Mitchell go to
 hardware store to buy
 wire bolt cutters. STARTS
 Brown & Shires buy

5 Cut lock + drive
 to site from the N.E.
 on John Deer "Gator"
 proceed on road

Mitchell & Carson 8/10/99 -

8/10/99

06-99-03-0001

to the west of fill going
 to the North.

0900 Search for east overflow
 in Gator. Have to hike

to six locations from N.
 10:00 Prepare to begin
 sampling on S. overflow
 - sediment sixes - 5
 toward Trinity

10:30 Begin sampling SDH
 + SD12 ~~7/15/10~~ SD12 + SD13

10:50 Begin sampling SD14
 + SD11

11:00 Begin sampling SD15

11:10 Begin sampling SD11

12:00 - late entry - sixes.

SD12, SD11 sampled by
 START members Shires &
 Mitchell, sixes. SD13, SD14
 + SD15 sampled by

START member Carson.

JAM Bill Rhetenberry

arrived at site at 0900

Found START members

at 10:30

- Mitchell Brown 8/10/99 -

29 06-99-03-0001

210 START members
in Carson, Mitchell
ires leave site w/
Rhotenberry
START Brown + SAM
enberry drive to find
can Elam creek at
12. Identified were
background sk. is to
taken.

START members
live at E+E were -
e. Begin labbing,
packaging samples
cted during the

- Late entry -
sampling locations
red flags placed at
w/ number of sk.
ten on them for
reference.


START members leave
rehouse + go home

8/10/99 Michelle Grown

8/10/99

06-99-03-0001

Sampling locations
for the day



8/10/99 Michelle Grown

8/11/99 06-99-03-0001

0600 START members
Michelle Brown, Maggie Carson,
Jody Shires, Mike Mitchell
meet at E+E Warehouse
conduct site safety
meeting. weather - clear,
high ~ 105°F. Hazards -
te. - stress, snakes, slip
trip, fall. Gator operation.
Agenda - collect soil/
sediment samples. PPE -
Level D

0700 START members
Brown, Carson, Shires &
Mitchell arrive at site

0715 START members
Brown & Carson go for
ice. Mitchell & Shires
set up decan equipment
0740 Prepare sampling
equipment at site & load
in Gator to head towards
East Pond

0830 Mitchell begins
sampling SDQ5 w/ Shires
- 8/11/99 Mitchell Brown

8/11/99

06-99-03-000

0850 Mitchell & Shires begin
sampling SDQ4 (the beginning
of the S. overflow)

0925 Brown & Shires begin
sampling SDQ3 at end
of pond - no photo taken

0955 Mitchell & Shires
begin sampling SDQ2
in the middle portion of
the pond.

1015 Mitchell & Shires begin
sampling SDQ1 at the
~~beginning~~^{beginning} of the
pond close to Jim Miller
entrance

1035 Mitchell & Shires
begin sampling SSQ1
~~next to west trench~~^{mb}
at NE side of landfill
upslope from east pond

1110 Brown begins sampling
SSQ2 from SW of west
pile

1115 Shires begins sampling
SSQ3 - Duplicate of SSQ2

- 8/11/99 Mitchell Brown

06-99-03-00019

7/1/99

Photo Log
 35mm Pentax # 690714
 Roll/Frame | Date/Time | Direction/Location
 1 01 7/1/99 0950 SW Front K/MR
 entry sign
 1 02 7/1/99 SW view of
 1 03 7/1/99 SW view of
 1 04 7/1/99 SW view of
 1 05 7/1/99 SW view of
 1 06 7/1/99 SW view of
 perimeter of landfill
 1 07 7/1/99 SW view of
 landfill from gully
 1 08 7/1/99 SW view of
 water in gully surrounding
 landfill S. S. M
 1 09 7/1/99 SW view of
 w/ floating debris
 1 10 7/1/99 SW view of
 view of fill + gully
 1 12 7/1/99 SW view of
 on eastside of landfill
 1 13 7/1/99 SW view of
 broken fence w/ old gravel
 pit in bkgrd. concrete rocks
 7-1-99 Mitchell Green

06-99-03-0001

START members depart
 e a head for warehouse
 Arrive at E+E ware
 use a begin tagging +
 packaging SKS for shipment
 0-late entry - EPA
 RH employees arrived
 - site approximately 8:45
 observe START members
 options (what Helmick sp?
 Elidin Chang) They
 sort site approximately
 - an hour later
 START members finish
 with sample packaging
 head home.

8/1/99 Mitchell Green

06-99-03-001
11/99 Photo Log cont.
= 1 Dot Time / Dir. / Location / Fly

06-99-03-001

06

06

06

06

06

06

06

06

06

06

06

06

06

7/8/99

Photo Log

06-99-03-001
35 mm Pentax # 696714
R/E Date/Time / Dir / Subject / Fly
11/7/8 10:40 S Vent for
sewage

7/8/99

06

06

06

06

06

06

06

06

06

06

06

06

35mm Pentax # 696714

99 Photo Log 06-99-03-0001

| Date/Time | Dir | Subject | P/W |
|------------------------------|-----|-----------------|-----|
| 7/15 1350 | N | from dirt MB/BR | |
| road toward fill | | | |
| 7/15 1410 | S | showing BR/MB | |
| verflow from fill to | | | |
| inity | | | |
| 7/15 1412 | N | from hill BR/MB | |
| + overflow toward fill MB/BR | | | |
| 7/15 1450 | S | wetland MB/BR | |
| pond to east | | | |
| F fill | | | |
| 7/15 1500 | SE | from fill MB/BR | |
| towards east pond | | | |
| 7/15 1505 | S | trench MB/BR | |
| following fill goes south | | | |
| to outfall | | | |

8/10/99 Photolog 06-99-03-0001

| Date/Time | Dir | Subject | P/W |
|-------------------------|-----|-----------|-------|
| 8/10 0830 | N | Residence | MC/MT |
| w/ swing to N of fill | | | |
| 202 8/10 0832 | NE | Residence | |
| N of fill approx 30 yds | | | |
| 203 8/10 1030 | N | SX SD12 | MB/M |
| 204 8/10 1035 | SW | SX SD12 | MB/M |
| 205 8/10 1111 | N | SX SD15 | |
| 206 8/10 1115 | W | SX SD11 | |
| 207 8/10 1120 | S | SX SD14 | |
| 208 8/10 1125 | NE | shotgun | MB/ |
| casings + footprints | | | |

7/15/97 Michelle Green

8/10/99 Michelle Green

11/99 Photolog 06-99-03-0001

35mm Pentax #696714

F Date Time Dir. Subject P/W

9 8/11 8:45 E Sampling MB/MC

location for SDØ5 PPE
to Elam Creek

Ø 8/11 8:46 NE Just N

of sample SDØ5

11 8/11 9:10 N Sampling

location for SDØ4

12 8/11 ~~10:05~~ 10:05 N Sampling

location for SDØ2 w/
drums in pond in bkgnd.

13 8/11 10:25 NE Sampling MB/MC

location for SDØ1 at

beginning of pond

4 8/11 ~~10:37~~ 10:45 SE MB/MC

Sampling location for SSØ1

5 8/11 11:15 E Sampling MB/MC

location for SSØ2 + SSØ3

8/11/99 Michelle Green

8/12/99 Photolog 06-99-03-0002

35mm Pentax #696714

R/F Date Time Dir Subject P/W

216 8/12 7:25 SE Fishing MB/MC

buoy off of Elam Creek

217 8/12 7:45 SE Sampling

location for SDØ8 + SDØ9

218 8/12 8:05 N Sampling MB/MC

location for SDØ7

219 8/12 8:15 N Evidence of

beavers NE

220 8/12 8:20 beaver evidence

221 8/12 9:05 N Sampling MB/MC

location for SDØ6

222 8/12 9:55 S Sampling MB/MC

location for SDØ1Ø


223 8/12 10:05 S Sampling MB/MC

location for SSØ4

8/12/99 Michelle Green

8/11/99

06-99-03-00

Sampling Locations
For the day

8/12/99 Michelle Gorman

Trinity River

- 8/11/99 Michelle Gorman

8/12/99

06-99-03-coc

0600 START members Michelle Brown, Maggie Carson, Mike Mitchell + Jody Shires arrive at the E+E Warehouse.

Conduct site safety meeting. Weather - clear, hot, high 2. 109°F. Hazards - slip, trip, fall, snakes. Agenda -

collect samples from Elam Creek + 2 background SXS. Ship SXS to labs, clean + put up supplies.

0700 START members arrive at site + start setting up for sampling, - assemble decon

0720 Begin sampling SDØ8 + SDØ9 at Elam creek S. of the dirt road

Sampling done by Mitchell + Shires

0755 Shires begins sampling of SDØ7 at south end of the curve in the creek

0850 Find sampling location
— 8/12/99 Michelle Brown —

8/12/99

Michelle Brown

8/12/99

00-99-03-0001

for SD46 & Mitchell + Shires

begin sampling

0945 Begin sample ^{7MB}

sampling background SX

SD18 on Elam Creek

just south of Loop 12

1020 Begin sampling SS44

background soil sample

at the intersection of

Jim Miller + Gaylen Dr.

1030 START members depart

site + head for ETE

Warehouse

1130 START members

begin taking + labeling

samples for shipment

1310 Called Charles Hutchinson

+ gave him information of

shipping

1330 STARTS Mitchell +

Brown take samples

to FedEx to be shipped

1400 START members

finish w/ cleaning-up at

warehouse + head home

8/12/99 Mitchell Brown


8/12/99

00-99-03-000

Sampling Locations

For the Day

Loop 12



8/12/99 Mitchell Brown Trinity River

11/16/99

06-99-03-0001

Left at 14:00 Late entry
The following observations were made during the field activities conducted between 7/1/99 and 8/12/99:

1. A portion of the northern fence to the property was missing by the nearest residence.
2. The nearest residence was approximately 100 feet north of the site.
3. There was evidence of people trespassing on the south side of the site. There were footprints as well as shotgun casings.
4. There were no containment structures present at the site. The observed waste was uncovered and no liner was seen.
5. There is a park

— Michelle Grewer 11/16/99

11/16/99


06-99-03-0001

located north-east of the site called Woodland Springs.

6. Elam Creek had a low flow. Portions contained growth of algae^{ae mg} on top, it was assumed, based on how the creek looked that the flow was approximately 10 cfs.

Michelle Grewer

11/16/99



Recycled Paper / 568019

Reference 16

United States
Environmental Protection Agency
Criminal Investigation Division

Report of Investigation

| | | | |
|-------------------------------------|-------------------------------------|-----------------|-------------|
| 1. Case Title: | Herman Nethery Landfill | 2. Case Number: | FOIA-(b)(6) |
| 3. Period of Investigation Covered: | August 30, 1996 - December 31, 1996 | 4. Office: | Dallas |

SYNOPSIS:

During September 9-11, 1996, the **Texas Natural Resource Conservation Commission (TNRCC)** and **EPA-CID** executed State **Search Warrants** at three (3) separate properties simultaneously in Dallas County. The warrants for this **Task Force** case were executed without incident and with the full cooperation of local, state and federal officials. Along with documents relating to landfill activities, over **\$200,000** in monies (e.g., U.S. Currency & checks) were seized during the search warrants. The monies seized during the search warrants continue to be a controversial issue as efforts have been made by the suspects to regain the monies. The **Internal Revenue Service (IRS)** has been notified by EPA-CID of this pending case and has provided some support in the assessment of this "hot" issue.

EPA Region Six issued two separate and distinct **Administrative Orders** (AO) requiring that the landfill operation/recycling facility immediately cease and desist discharges to Waters of the United States. Both orders define CWA violations and both describe the illegal discharge of pollutants without a **NPDES** permit. One is related to storm water control while the other is related to discharges into several "abandoned" ponds. Both of the pending orders require action to be taken by the owners/operator of this facility/landfill.

Based on several pending civil actions (City and Federal) the unpermitted landfill was essentially "shut down" as of August 27, 1996. However recent tips to EPA-CID indicated that the landfill was back in operation as early as late October/early November 1996. EPA-CID was advised that the subject landfill was back in operation, and possibly at a new property adjacent to the "original" landfill location. EPA-CID and TNRCC investigated this allegation and confirmed that in fact a "new" dumping operation was active on what later would be defined as part of the original facility/property. This confirmation rekindled surveillance activity at the facility by the EPA/TNRCC Task Force. Heavy rains in the Dallas area, combined with surveillance activity helped confirm suspected storm water drainage pathways from the landfill site. This type of investigative evidence continues to support suspected violations of the **Clean Water Act (CWA) - NPDES Storm Water Permits.**

A) DETAILS OF INVESTIGATION

Reference is made to the last ROI dated 8/29/96.

On August 27, 1996, EPA Region Six issued the [FOIA] primary suspects, [FOIA (b)(6)] and [FOIA (b)(6)] each an Administrative Order (AO) directing them to cease and desist all industrial activity at the facility identified as the "Nethery Recycling Facility" that cause discharges of pollutants to Waters of the United States. This facility is located at the same address and location as what has been previously identified by EPA-CID and TNRC as the **Herman Nethery Landfill**.

On August 28, 1996, EPA-CID and TNRRCC continued surveillance of the landfill operations in preparation of the execution of three search warrants relating to the landfill. The three locations are: a) the landfill; b) the residence/business of

FOIA (b)(6) and c) FOIA (b)(6) of FOIA (b)(6).

| | | |
|---------------------|--|--------------|
| REPORT MADE BY: | Name: FOIA (b)(6) Special Agent | Date Signed: |
| | Signature: [Redacted] | 1/3/97 |
| APPROVING OFFICIAL: | Name: FOIA (b)(6) Special Agent-in-Charge | Date Signed: |
| | Signature: [Redacted] ASAC | 1-6-97 |

United States
Environmental Protection Agency
Criminal Investigation Division

2. Case Number:

FOIA (b)(6)

Continuation Sheet

On September 8, 1996, the warrants were signed by State Criminal District Judge Mark TOLLE, and a subsequently a warrant briefing was conducted by TNRCC and EPA-CID. While TNRCC is the lead State agency for the warrant, State Peace Officer support was provided by the **State Parks and Wildlife** department.

During September 9-11, 1996, state warrants were executed that three locations simultaneously and without incident. While documents were seized from the different locations as expected, over \$200,000 in cash and checks was seized by the State as "fruits of the crime." Seized documents were transported and logged into the EPA-CID evidence room for safe-keeping and accessibility. Seized monies were transported to and secured at a local bank safe depository. See ROI dated August 29, 1996, for details of the monies seizure.

During September 12-28, 1996, EPA-CID and TNRCC maintain a presence at the landfill entrance in order to observe any incoming vehicles attempting to dump illegal loads into the landfill. On three occasions, FOIA (b)(6) spoke with SA FOIA (b)(6) and SAC FOIA (b)(6). Details for these discussions are in MOIs for FOIA (b)(6) dated 9/14/96, 9/17/96 & 9/20/96.

September 27, 1996, EPA Region Six issued FOIA (b)(6) an AO directing him to cease and desist all discharges into several ponds identified as "Waters of the United States" and "Navigable Water" with respect to the CWA. This facility is located at the same address and location as what has been previously identified by EPA-CID and TNRCC as the **Herman Nethery Landfill**.

Throughout September and October, 1996, the investigation continued as information on specifically "how" business was conducted at the landfill was gathered via interviews with several of the known entities that had delivered loads to the landfill between August 1994 - September 1996. Information gathered is in the attached MOIs.

Based on observations and interviews of workers at the landfill, clients of landfill (truck drivers & owners) and the landfill FOIA (b)(6), the following is the simple description of "how it worked" for operations at the **Herman Nethery Landfill** (a.k.a., **Nethery Recycling Center**):

The landfill opened for business in mid-1994 and operated seven days a week from sunrise to sunset (weather permitting). Dallas County records show FOIA (b)(6) as the official FOIA (b)(6) of the approximate 84-acre landfill, while FOIA (b)(6) FOIA (b)(6) a FOIA (b)(6) known as **Fruit of the Spirit** and allegedly FOIA (b)(6) claimed not to have anything to do with the running of the landfill, and identified FOIA (b)(6) as the FOIA (b)(6) running the **Nethery Recycling Center (NRC)**.

The fees for disposal range from \$25 to \$100 per truck load depending on the size and type of material. NRC accepted some materials at "no charge" (e.g., clean soil). Approximately 100-200 truck loads entered the NRC daily via the **Jim Miller Road** entrance. Cash to check ratio varied daily but was estimated by FOIA (b)(6) (landfill worker) was 50-60% of the total take for the day. FOIA (b)(6) claimed that the NRC grossed up to \$4,000/day, and that he and FOIA (b)(6) split the earnings 50/50. Some fees were collected on-site (cash & check), some checks were sent in via U.S. Mail and some were picked up in-person by FOIA (b)(6). Records of each transaction were apparently not kept and receipts were mostly provided upon request. Clients who paid by company check, could produce a paper trail of transactions with the landfill/Fruit of the Spirit (e.g., **Reyes Trucking & Moore Disposal**). FOIA (b)(6) claimed not to have a lease with FOIA (b)(6); also that FOIA (b)(6) acted as the FOIA (b)(6) while FOIA (b)(6) was the FOIA (b)(6) of NRC and claimed that landfill was really a recycling center and that loads are refused if deemed inappropriate.

Loads came in the front gate, dropped their load, then either paid immediately or received a trip ticket as they exited. The trip tickets were apparently found with clients with a large volume of business coming in (e.g., **Reyes Trucking & Moore Disposal**). According to drivers, turnaround times were significantly less at NRC than at the City landfill located due south of the NRC across the Trinity River.

United States
Environmental Protection Agency
Criminal Investigation Division

2. Case Number:
FOIA (b)(6)

Continuation Sheet

Clients who asked for the permit status of the facility, were told that the NRC was a fully-permitted and legally operated landfill (not a *recycling* center). Some clients could produce copies of documents that were provided to them to backup FOIA (b)(6) claim that the NRC was legal. The City of Dallas reviewed each of these documents and has confirmed that the only legal permit the property has, was issued to FOIA (b)(6) and Nethery Recycling Center, for mining, and under the guise of V&V Construction (former owner's company).

Since late October 1996, dumping activity at the landfill had essentially "stopped" and most of the attention by the TNRC and EPA-CID was focused on reviewing evidence collected during the search warrants of September 1996. This comprehensive review was primarily stimulated by the fact that both the suspects FOIA (b)(6) and FOIA (b)(6) had challenged the seizure of the cash during these warrants. The TNRC in conjunction with the Dallas County District Attorney's Office, worked to determine the exact origin of these monies in order to show that in fact this cash was received by the suspects as payment for dumping at the landfill, not as part of legitimate operations as proposed by the suspects. This assessment would require support from EPA-CID.

The District Attorney's office was offered a settlement amount significantly less than that seized (i.e., \$5,000) and prompted continued and enhanced efforts by the Task Force to confirm the origin of the cash. From the Federal standpoint, FOIA (b)(6) contacted FOIA (b)(6) (IRS) and advised him of the status of the case with respect to the monies seized. In addition, the suspects had provided the District Attorney's office with written statements (interrogatories) which included considerable financial data with respect to the "earning" of this cash, including personal Federal Income Tax information for FOIA (b)(6). IRS opened an preliminary lead investigation file on both FOIA (b)(6) and FOIA (b)(6). IRS did not open a full-blown case investigation at the time. During this "review" process, apparently new activity started up at the landfill.

On November 19, 1996, SA FOIA (b)(6) was contacted by FOIA (b)(6), owner of *Moore Disposal*, and was advised that the "landfill" may be open again for business. FOIA (b)(6) stated that his drivers had noted that this was the word on the street, and that the "new" entrance was located near a salvage yard right off of Loop 12, near Jim Miller Road.

On November 22, 1996, ASAC FOIA (b)(6) and State Investigator FOIA (b)(6) conducted on-site surveillance at the suspected location. The investigators visually confirmed on-going dumping of materials identical to those found at the original landfill (located just east of this "new" area) and possible impact into **Waters of the United States**. During this surveillance, the investigators interviewed a witness at this "new" landfill site. Report of interview is pending completion by the State Investigator.

During November 23-24, 1996, TNRC investigators spoke with several "new" landfill personnel and various drivers of the trucks that were dumping at this new area. Reports of these interviews are pending with State Investigators.

On November 25, 1996, FOIA (b)(6) and SA FOIA (b)(6) conducted on-site reconnaissance in an effort to document active storm water discharges from the subject property, and to document any active dumping in the "new" area located just west of the original landfill area.

On November 26, 1996, SA FOIA (b)(6) conducted an aerial overflight (helicopter courtesy of Dallas Police) of the entire landfill property in an effort to further document apparent storm water drainage patterns. During this surveillance action, **active dumping was observed and photo documented.**

United States
Environmental Protection Agency
Criminal Investigation Division

2. Case Number:
FOIA (b)(6)

Continuation Sheet

On November 26, 1996, SA FOIA (b)(6) and FOIA (b)(6) conducted on-site covert surveillance in order to document dumping activity in the "new" dumping area.

On November 26, 1996, ASAC FOIA (b)(6), SAC FOIA (b)(6), RCEC FOIA (b)(6), ADA FOIA (b)(6), SI FOIA (b)(6) and SA FOIA (b)(6) spoke with FOIA (b)(6), EPA Inspector, concerning the current status of the Storm Water AO and issues relevant to the on-going criminal investigation. FOIA (b)(6) agreed not to pursue civil penalties in this case without first advising EPA-CID. FOIA (b)(6) acknowledged receipt of a Storm Water Pollution Prevention Plan from the FOIA (b)(6) and FOIA (b)(6) related to their application for a Storm Water NPDES permit for the landfill (a.k.a., *Nethery Recycling Center*). See Memorandum to the File for FOIA (b)(6) dated 11/26/96.

On November 27, 1996, SA FOIA (b)(6) conducted review of related county records at the Dallas County Appraisal District and the County Records Building in order to define specifically the property owners adjacent to the landfill. This effort confirmed that FOIA (b)(6) had in fact purchased a small piece of property (8.66 acre) that linked his existing 84-acre landfill to the southern-most edge of the rural portion of Longacre Road. This link allowed a continual link between this unused portion of Longacre Road and the original landfill area, normally accessed from Jim Miller Road. This now allowed a western or "back-door" entrance to the "new" landfill area with minimal if any disturbance to the local residences.

On November 29, 1996, SAC FOIA (b)(6) and SA FOIA (b)(6) interviewed FOIA (b)(6), truck driver, located at the intersection of Longacre Road and Loop 12 (entrance to "new" landfill). FOIA (b)(6) denied planning to dump FOIA (b)(6) truck-load of shingles at this "new" landfill and was just "passing by" enroute to the City landfill.

On December 2, 1996, FOIA (b)(6) and SA FOIA (b)(6) interviewed FOIA (b)(6), the consulting firm hired by the suspects to produce a Storm Water Pollution Prevention Plan for the "Nethery Recycling Center." FOIA (b)(6) indicated his role during his on-site inspection of the facility with the project manager, FOIA (b)(6), was to identify the natural outfalls from the property as defined by FOIA (b)(6). FOIA (b)(6) noted FOIA (b)(6) knew very little about the property or the FOIA (b)(6).

On December 2, 1996, SA FOIA (b)(6) interviewed FOIA (b)(6) of Fruit of the Spirit), while standing at the intersection of Longacre Road and Loop 12 (entrance to "new" landfill). FOIA (b)(6) stated that he was not in operation at the "new" location and that he "did not know anything" about any dumping there. FOIA (b)(6) denied discussing anything about dumping with an FOIA (b)(6) of a truck full of wooden shingles, that was coincidentally standing at the entrance to the "new" landfill. FOIA (b)(6) spoke briefly to FOIA (b)(6) (EPA Inspector) about the status of FOIA (b)(6) Storm Water permit application and then departed. FOIA (b)(6) acknowledged the sign posted in front of the Longacre entrance which stated "Recycling, Dirt, Rock, Fill," but stated FOIA (b)(6) had nothing to do with that operation. See MOI for FOIA (b)(6) dated 12/2/96.

On December 2, 1996, SA FOIA (b)(6) interviewed FOIA (b)(6) located at the intersection of Longacre Road and Loop 12 (entrance to "new" landfill). FOIA (b)(6) drove up in a dump truck loaded with wooden shingles shortly after FOIA (b)(6) departed the same location. FOIA (b)(6) told SA FOIA (b)(6) that he was there to dump FOIA (b)(6) truck load and that FOIA (b)(6) had just called FOIA (b)(6) so that FOIA (b)(6) would come and unlock the gate to let FOIA (b)(6) in. FOIA (b)(6) pointed out that FOIA (b)(6) had just drove away in a white Chevy dually pickup before he arrived. FOIA (b)(6) provided SA FOIA (b)(6) the pager number FOIA (b)(6) used to call FOIA (b)(6) and make the arrangements. FOIA (b)(6) indicated that FOIA (b)(6) use to likewise dump at the "old" landfill location when it was open. See MOI for FOIA (b)(6) dated 12/2/96.

United States
Environmental Protection Agency
Criminal Investigation Division

2. Case Number:
FOIA (b)(6)

Continuation Sheet

On December 3, 1996, FOIA (b)(6) and SA FOIA (b)(6) conducted an interview with FOIA (b)(6) of EMI, and FOIA (b)(6) for developing the FOIA (b)(6) for the NRC. FOIA (b)(6) stated based on data provided to FOIA (b)(6) and observation during FOIA (b)(6) on-site visits, FOIA (b)(6) indicated that FOIA (b)(6) did not observe any mining operations nor any dumping operations during FOIA (b)(6) visits (October 9 - November 26, 1996). FOIA (b)(6) stated that FOIA (b)(6) saw only minimal municipal trash and primarily construction debris. FOIA (b)(6) acknowledged that FOIA (b)(6) was not aware of any other facility that operated (recycling) on the same philosophy as NRC's (i.e., 7-yr burial; excavation; shred & sell). FOIA (b)(6) stated FOIA (b)(6) received minimal input from FOIA (b)(6) or FOIA (b)(6). FOIA (b)(6) acknowledged the seriousness of this document (SWPPP) for FOIA (b)(6) clients and acknowledged that FOIA (b)(6) reviewed this issue with both FOIA (b)(6) and FOIA (b)(6) as they were both present at FOIA (b)(6) office for the "approval" and signing of the plan. FOIA (b)(6) noted that the pair reviewed the document for approximately 45 minutes.

On December 5, 1996, SA FOIA (b)(6) and SA FOIA (b)(6) assisted the TNRC in surveillance of potential dumping at the "new" dump site. The Agents observed three (3) trucks dump their loads of construction debris, roofing material and general trash during the cover of darkness and without the use of their headlights. The trucks entered via the Longacre Road entrance by lifting the gate off the hinges and entering with their headlights "off." Once the trucks had finished dumping their loads, the drivers and vehicles were detained, questioned and finally arrested by State Peace Officers from the Texas Parks & Wildlife Department. Agents FOIA (b)(6) and FOIA (b)(6) assisted in the arrests of FOIA (b)(6) for State violations.

On December 6, 1996, SA FOIA (b)(6) and SA FOIA (b)(6) reviewed Dallas County records and confirmed that neither FOIA (b)(6) nor FOIA (b)(6) is officially registered with the county for doing business as (DBA) the following: *Nethery Recycling Center, Nethery Auto Wrecking, Nethery House moving, Nethery Auto Salvage*, FOIA (b)(6) nor FOIA (b)(6) and *Fruit of the Spirit*.

On December 9, 1996, SA FOIA (b)(6) spoke with FOIA (b)(6) EPA Inspector, concerning FOIA (b)(6) recent discussions with FOIA (b)(6) concerning the pending "wetlands" Administrative Order. FOIA (b)(6) provided information that identifies FOIA (b)(6) continued plans to reopen the original dumping location and confirmed FOIA (b)(6) acknowledging "working" in the so-called "new" landfill. See MOI for FOIA (b)(6) dated 12/9/96.

On December 10, 1996, AUSA FOIA (b)(6) was briefed on status of the investigation. Based on the information provided, FOIA (b)(6) agreed to accept the case based on the apparent CWA (Storm Water) violations and thus suggested that surveillance activity continue at the landfill.

On December 12, 1996, FOIA (b)(6) EPA Inspector, conducted an on-site inspection of the "new" facility. FOIA (b)(6) noted that during FOIA (b)(6) inspection, FOIA (b)(6) met with FOIA (b)(6) at the original landfill location, and observed and photo documented the dumping of wastes (i.e., wood shingles) on-site by two dump trucks. FOIA (b)(6) indicated that FOIA (b)(6) claimed no responsibility for any dumping activity, but that it was all FOIA (b)(6) actions. FOIA (b)(6) merely had an arrangement with FOIA (b)(6) to use FOIA (b)(6) heavy machinery. FOIA (b)(6) later stated that his plan was to "mine" the newly acquired "8-acre" area and that FOIA (b)(6) was planning to start mining the following week. FOIA (b)(6) indicated that FOIA (b)(6) advised FOIA (b)(6) that this new mining operation would likewise require a Federal Storm Water permit, specific to FOIA (b)(6) intended activity and location of operation. FOIA (b)(6) noted that FOIA (b)(6) indicated FOIA (b)(6) would take appropriate action to obtain this permit. At the conclusion of this inspection, FOIA (b)(6) delivered a copy of a letter from (EPA enforcement) directly to FOIA (b)(6) that specifically described the types activities considered illegal per the August 27, 1996, AO. EPA simultaneously mailed (certified) out the letter to FOIA (b)(6) FOIA (b)(6) Attorney and Environmental consulting firm that prepared the PPP required by the NPDES permit regulations. See MOI for FOIA (b)(6) dated 12/12/96.

From December 13-31, 1996, surveillance activities at the landfill were enhanced such to include windshield surveys, on-site surveys, photographic and hand-held video (camcorder) coverage of illegal activities. Included in this heightened surveillance was the usage of remote video camera and time-lapse tape-recording system (no audio). The objective of this activity was to document the continuance of the illegal activity in violation of the AO.

United States
Environmental Protection Agency
Criminal Investigation Division

2. Case Number:

FOIA (b)(6)

Continuation Sheet

December 13, 1996, SA FOIA (b)(6) conducted surveillance at the landfill and in the process met with one of the residents living adjacent to the landfill. FOIA (b)(6) gave permission of the use of their private property for surveillance activity. FOIA (b)(6) indicated that FOIA (b)(6) heard "engines running" at 2-3:00 am approximately 2-3 days earlier at the original landfill site. A surveillance log is located in the case file.

On December 13, 1996, SI FOIA (b)(6) observed and video-taped dumping of wastes at the "new" landfill area.

On December 16, 1996, SI FOIA (b)(6) and SA FOIA (b)(6) served a subpoena for the bank records of FOIA (b)(6) to the Records Custodian of Nations Bank, Dallas, Texas.

On December 17, 1996, FOIA (b)(6) and SA FOIA (b)(6) met with AUSA FOIA (b)(6) to discuss status of the case. FOIA (b)(6) requested that additional interviews be conducted with citizens who lived in the neighborhood directly adjacent to the landfill operation.

On December 18, 1996, SA FOIA (b)(6) contacted with FOIA (b)(6) and FOIA (b)(6) of Wholesale Brokers and requested to utilize their property for covert surveillance activity. FOIA (b)(6) agreed to cooperate. This property is located directly across the highway from the "new" entry, or otherwise known as Longacre Road entrance.

On December 18 - 19, 1996, SI FOIA (b)(6) and SA FOIA (b)(6) initiated steps to install a remote video camera/transmitter system intended to provide 24-hour time-lapse recording of activities at the "new" landfill. No audio would be recorded for this type of surveillance. The primary objectives for this type of surveillance are: document evidence of violations; minimize on-site manpower and provide comprehensive coverage of target area.

On December 20, 1996, SA FOIA (b)(6) observed, video-taped (8mm camcorder) and photo documented dumping of wastes in the "new" landfill. Consequently, the dumped material was "dozed," and the unidentified workers left immediately via the Longacre gate. At the gate a dark FOIA (b)(6) series FOIA (b)(6) was "parked" and eventually opened the gate for the departing workers (driving an old FOIA (b)(6)). The FOIA (b)(6) was shown as being registered to FOIA (b)(6) of Dallas, Texas. The driver of the FOIA (b)(6) could not be visually confirmed as the suspect. FOIA (b)(6) who drives an automobile very similar and matched very closely the known physical description of FOIA (b)(6). It did however appear that the driver was "guarding" the gate while the workers bulldozed the recently dumped load and some older piles of trash. Upon exit, the driver opened that Longacre Road gate and let the FOIA (b)(6) out. The FOIA (b)(6) remain facing out at the location for several minutes before departing.

On December 22, 1996, the covert recording was placed to document activity in the "new" landfill area. Review of these tapes has not revealed any illegal activity to date. The system was provided and set up with assistance from the TNRC and the University of Texas/Applied Research Labs (Austin, TX).

On December 28, 1996, a second surveillance package/system was created and covertly placed at the entrance/gate of the "new" landfill (Longacre Road). Review of these tapes has not revealed any illegal activity to date.

B) DEFENDANTS/SUSPECTS

FOIA (b)(6) - See ROI dated 8/27/96

FOIA (b)(6) - See ROI dated 8/27/96

FOIA (b)(6)

United States
Environmental Protection Agency
Criminal Investigation Division

2. Case Number:
FOIA (b)(6)

Continuation Sheet

C) UNDEVELOPED LEADS

EPA-CID will formally refer this case to the U.S. Attorney Office, Northern District - Dallas, in the second quarter of FY97. EPA-CID and TNRCC will continue to investigate this case.

D) ATTACHMENTS

1. MOI with FOIA (b)(6) dated 9/10/96.
2. MOI with FOIA (b)(6) dated 9/10/96.
3. MOI with FOIA (b)(6) dated 9/14/96.
4. MOI with FOIA (b)(6) dated 9/17/96.
5. MOI with FOIA (b)(6) dated 9/20/96.
6. MOI with FOIA (b)(6) dated 10/1/96.
7. MOI with FOIA (b)(6) dated 10/1/96.
8. MOI with FOIA (b)(6) dated 10/3/96.
9. MOI with FOIA (b)(6) dated 10/3/96.
10. MOI with FOIA (b)(6) dated 10/3/96.
11. MOI with FOIA (b)(6) dated 10/4/96.
12. MOI with FOIA (b)(6) dated 10/8/96.
13. MOI with FOIA (b)(6) dated 10/8/96.
14. MOI with FOIA (b)(6) dated 10/8/96.
15. MOI with FOIA (b)(6) dated 10/9/96.
16. MOI with FOIA (b)(6) dated 10/9/96.
17. MOI with FOIA (b)(6) dated 10/9/96.
18. MOI with FOIA (b)(6) dated 10/9/96.
19. MOI with FOIA (b)(6) dated 10/18/96.
20. Memorandum to File for FOIA (b)(6) dated 11/26/96
21. MOI for FOIA (b)(6) dated 12/2/96.
22. MOI for FOIA (b)(6) dated 12/2/96.
23. MOI for FOIA (b)(6) dated 12/9/96.
24. MOI for FOIA (b)(6) dated 12/12/96.

12/31/96

Reference 17

F97-1789

**EMERGENCY RESPONSE REPORT
JIM MILLER LANDFILL FIRE
DALLAS, DALLAS COUNTY, TEXAS**

June 30, 1997

Prepared for:

**Henry Thompson, Jr.
Project Officer
Program Management Branch
EPA - Region 6**

Contract Number: 68-W6-0013



ecology and environment, inc.

International Specialists in the Environment

1999 Bryan Street, Dallas, Texas 75201
Tel: (214) 220-0318, Fax: (214) 855-1422

recycled paper



ecology and environment, inc.

International Specialists in the Environment

1999 Bryan Street

Dallas, Texas 75201

Tel: (214) 220-0318, Fax: (214) 855-1422

F97-1789

Date: June 30, 1997

To: Don Smith, TM
EPA Region 6, Response and Prevention Branch

Thru: Henry Thompson, Jr., PO
Program Management Branch

Thru: Chris Quina, STL
Region 6, Superfund Technical Assistance and Response Team

From: Scott Fraser, PM
Region 6, Superfund Technical Assistance and Response Team

Subject: Jim Miller Landfill Fire, Emergency Response
Dallas, Dallas County, Texas
TDD No. S06-97-02-0016
PAN No. 029201RZXX

LAT: 32° 42' 22.1" N
LONG: 96° 42' 07.5" W

On March 16, 1997, site coordinates for the Command Post located at the landfill were identified with a Trimble Navigation Scoutmaster. Point averaging was used in an autonomous mode based on North American Datum 1927 (NAD 27).

INTRODUCTION

On February 28, 1997, the Region 6 Superfund Technical Assistance and Response Team (START) was tasked by the U.S. Environmental Protection Agency Response and Prevention Branch (EPA-RPB) to conduct on-site monitoring activities in response to a landfill fire. The fire occurred at an unlicensed landfill located in Dallas, Dallas County, Texas (Attachment A: Site Location Map). The owner/operator of the illegal landfill is Herman Nethery, the potentially responsible party (PRP) for the fire. Specific tasks included: respond to the scene and provide emergency response support; provide written and photographic documentation of the incident; coordinate with state and local officials; and brief the Task Monitor (TM) of the situation.

BACKGROUND

The site is southwest of the intersection of Jim Miller Road and Gayglen Drive in Dallas, Dallas County, Texas. The landfill is bordered by a residential neighborhood to the north, the Woodland Springs Park to the east, the Trinity River and McCommas Bluff Park to the south, and non-operational quarry land to the west. The nearest residents are located approximately 30 yards north of landfill operations. An apartment complex is north of the intersection of Jim Miller Road and Gayglen Drive. The site is an unlicensed and unpermitted landfill that accepted construction debris, municipal waste, medical wastes, motor oil, and hydraulic fluid. The landfill covers approximately 30 acres, reaches a depth of 40 feet, and may contain as much as 2 million cubic yards of solid waste.

The City of Dallas took civil action against Mr. Nethery in 1996. In June 1996, the Texas Natural Resource Conservation Commission (TNRCC) and the EPA-Criminal Investigation Division (CID) began to investigate the landfill operations for possible criminal intent. On September 13, 1996, TNRCC and EPA-CID conducted an inspection at the landfill. The inspectors observed a smoldering area within the southern section of the landfill and notified both the Dallas Fire Department (DFD) and EPA-RPB. On September 13, 1996, START responded to the fire, conducted air monitoring, and documented site conditions. Air monitoring equipment was used to detect volatile organic compounds (VOCs), cyanide, hydrogen sulfide, phosgene and radiation. Monitoring results did not indicate the presence of these contaminants in concentrations greater than background levels (TDD No. S06-96-09-0013). EPA issued a cease-and-desist order, which closed the landfill because of the possible migration of surface water runoff from the landfill to the Trinity River.

ACTIONS TAKEN

On February 28, 1997, START members Anan Hammad and David Crow mobilized to the site and arrived at 1245 hours. START met with DFD officials and R. L. Hunt of the City of Dallas Street Department. Fire hoses and heavy equipment, including front-end loaders, trackhoes, and a compactor, were used to extinguish the pockets of smoldering debris (Attachment C: photo Nos. 101, 102 and 103). START completed the on-site investigation at 1405 hours and debriefed OSC Don Smith of site conditions. OSC Smith concluded that no further assistance was necessary, and the START members were instructed to depart from the site.

On March 12, 1997, START members Scott Fraser and Koeby Johnson returned to the site because of additional fire fighting activity related to the landfill. Apparently, construction debris continued to burn below the landfill surface. START met with federal, state, and local officials including OSC Ky Nichols, DFD Fire Chief Wachsman, Mike Rockman of the City of Dallas Water Department, Rodger Jayroe of the City of Dallas Environmental and Health Services, and Norris Stough with the City of Dallas Department of Street, Sanitation and Code Enforcement. OSC Nichols instructed START to conduct air monitoring along the perimeter of the impacted area at the landfill. START utilized a Toxic Vapor Analyzer (TVA) for the detection of VOCs, Monitoxes for the detection of

cyanides and phosgene, and a MSA Passport for the detection of explosive atmosphere, carbon monoxide, and hydrogen sulfide. Elevated levels of VOCs were detected at the source of several smoke plumes, but, this is typical of combustion. Air monitoring conducted in ambient air (breathing zone) did not indicate the presence of an explosive atmosphere, carbon monoxide, hydrogen sulfide, VOCs, cyanide, or phosgene at concentrations greater than background levels. START completed the on-site investigation at 1300 hours and debriefed OSC Nichols of site conditions. OSC Nichols instructed the START members to depart from the site and to return the following day to continue air monitoring support.

START remobilized to the site 11 times to conduct air monitoring activities. Additional contaminants were monitored during subsequent visits to the site. Elevated levels were not detected for the following contaminants: carbon monoxide, phosgene, hydrogen cyanide, hydrogen sulfide, acrolein as formaldehyde, nitrogen dioxide, ammonia, sulfur dioxide, VOCs or combustible gases. For specific locations and results, refer to Attachment B and Attachment E.

On March 6 and March 7, 1997, TNRCC collected three instantaneous canister samples, or "puff samples," which were analyzed for VOCs by the TNRCC laboratory. Two samples were taken from smoke plumes on site, while the third was located in the residential area along the northern border of the site. For the two on-site samples, several VOCs were measured at concentrations exceeding their effects screening levels (ESLs) or odor-thresholds. The level of VOCs detected in the residential sample were below health-based action levels. For a further description of sample results, sampling locations, and ESLs, refer to Attachment M. A response contractor, EmTech Environmental Services, Inc., performed personnel air monitoring for excavation employees working at the site from March 13 through March 14, 1997. The sample results for Industrial Hygiene Metals and Total VOCs were near or below detection limits (Attachment L).

On March 24, 1997, START members Scott Fraser and Jeff D'Agostino mobilized to the site to perform air sampling. Air sampling was conducted at sensitive receptor areas to verify that the public was not at risk from the smoke and plume particulates. Two SKC pumps were used at each of four locations to determine the presence of total particulates, metals, and polynuclear aromatics (PAHs/PNAs). The sampling stations were located at the western end of Western Hills Drive, W. A. Blair Elementary School, Frederick Douglas Elementary School and the southwest side of the landfill excavation near the Trinity River (Attachment B and Attachment F). The results showed that all contaminant levels were near or below detection limits (Attachment G and Attachment H).

CONCLUSION

For the duration of the project, EPA-RPB coordinated air monitoring and air sampling with City of Dallas officials. Air monitoring results were reported to the City of Dallas on an interim basis. Extensive coordination was required to meet the needs of EPA and the City of Dallas.

Reference 18

September 12, 1996

TOPIC: Nethery Recycling Cease and Desist Order

BACKGROUND INFORMATION:

Specific "Industrial Activities" [40 CFR 122.26(b)(14)] are required to have an National Pollutant Discharge Elimination System (NPDES) Storm Water permit and a Storm Water Pollution Prevention Plan to assure storm water runoff will not impact water quality.

Nethery Recycling is a business operating in the Pleasant Grove area of Dallas. The facility is an 82 acre site that receives construction debris and other materials. The facility has received roughly 2 million cubic feet of material since August 1994, when it began operation. The facility site contains an "East Pond" which constitutes a "Waters of the U.S." The East pond receives some of the facility storm water runoff. Much of the storm water runoff and overflow from the East pond discharges through unnamed drainage conveyances to Elam Creek, which then discharges to the Trinity River.

CURRENT STATUS:

The city of Dallas and the State of Texas believe the facility is a landfill and should be permitted as such. Nethery Recycling claims the facility is a recycling operation and does not require landfill permits. The city of Dallas has ordered the facility to cease operations until city permits have been obtained. A judge recently ordered the facility to cease operations. Nethery Recycling has continued operation under the assumption that they do not need city or state permits.

"Industrial Activities" that require NPDES permit coverage include both landfills and recycling operations (SIC 5093). The facility did not have NPDES permit coverage. EPA issued a "cease and desist" Administrative Order on August 27, 1996 requiring the facility to stop any "industrial activity" until it comes into compliance with the Clean Water Act. The facility ceased operations on August 28, 1996.

Nethery Recycling submitted a Notice of Intent (NOI) application to EPA on August 29. A complete NOI gives the applicant NPDES permit coverage 2 days after the postmark of the NOI and Nethery Recycling resumed operation on August 31. The NOI was incomplete (latitude and longitude omitted) and the facility was informed of the deficiency in a telephone call on September 4. The facility has acquired a consultant to prepare the pollution prevention plan and the facility said they would have their consultant complete and resubmit the NOI and drop off a copy at EPA offices.

The facility has obtained NDPES storm water permit coverage through the storm water "Multi-Sector" permit. This permit requires the facility to prepare and implement a storm water pollution prevention plan by September 25, 1996, and to begin sampling in the 4th Quarter of 1996. The NOI indicates the facility is SIC 5093, scrap and waste material recycling.

TECHNICAL CONCERNS:

National Urban Runoff Program reports and CWA 305(b) reports contain effluent data demonstrating that storm water runoff from both landfills and recycling operations adversely impact water quality. This facility is operating under unknown environmental circumstances and impacting at least three waters of the United States. The size of the facility, types of material, and proximity to Waters of the United States were significant in determining that a quick EPA response was necessary.

COMMUNITY CONCERNS:

The local community has many concerns about the facility and asked the city to take action. actions including issuing about However, the city has failed to activity. Channel 4 news high segment in the Summer of 1995.


Mr. Taylor Sharpe
Federal Enforcement
Officer
USEPA, Region 6

FUTURE PROPOSED ACTIONS:



EPA plans to assure compliance reviewing the facility's storm plan when the facility appears "Show Cause" meeting. The fac: prevention plan will be used in action. The facility will be c compliance evaluation inspectio submitting to EPA, storm water quarter of 1996 and EPA will ex effluent quality.

CONTACT/TELEPHONE NUMBER: Taylor Sharpe (214/665-7112)

Reference 19




Maped, edited, and published by the Geological Survey
Control by USGS and USC&GS
Culture and drainage in part compiled from aerial photographs
taken 1952 and 1956. Topography from city of Dallas
surveys 1954 and by planetable surveys 1958
Polyconic projection. 1927 North American datum
10,000 foot grid based on Texas coordinate system,
north central zone
1000 meter Universal Transverse Mercator grid ticks,
zone 14, shown in blue
Red tint indicates areas in which only
landmark buildings are shown
Revisions shown in purple compiled from aerial photographs
taken 1968 and 1973. This information not field checked
Purple tint indicates extension of urban areas




| ROAD CLASSIFICATION | |
|---------------------|-----------------|
| Heavy duty | Light duty |
| Medium duty | Unimproved dirt |
| Interstate Route | U.S. Route |
| | State Route |

WHITE ROCK LAKE, TEX.
SW/4 GARLAND 15 QUADRANGLE
N3245-W9637.5/7.5

1958
PHOTOREVISED 1968 AND 1973
AMS 6649.1 SW. SERIES VR#2





Produced by the United States Geological Survey
Control by USGS and NOS/NOAA

Compiled from aerial photographs taken 1952 and 1956
Topography from City of Dallas surveys 1954 and by plane-table
surveys 1952

North American Datum of 1927 (NAD 27). Projection and
10,000-foot grid ticks: Texas Coordinate System, north central
zone (Lambert Conformal Conic). 1000-meter Universal Transverse
Mercator grid ticks, zone 14, shown in blue.
The difference between NAD 27 and North American Datum of
1983 (NAD 83) for 7.5 minute intersections is given in USGS
Bulletin 1875. The NAD 83 is shown by dashed corner ticks.
Red tint indicates areas in which only landmark buildings are shown.

Revisions shown in purple compiled from aerial photographs
taken 1968 and 1973. This information not field checked.
Purple tint indicates extension of urban areas.

SCALE 1:24,000
1000 0 1000 2000 3000 4000 5000 6000 7000 FEET
1 0 1 2 3 4 5 6 7 8 9 10 KILOMETERS
CONTOUR INTERVAL 10 FEET
NATIONAL GEODETIC VERTICAL DATUM OF 1929

THIS MAP COMPLIES WITH NATIONAL MAP ACCURACY STANDARDS
FOR SALE BY U.S. GEOLOGICAL SURVEY, DENVER, COLORADO 80225, OR RESTON, VIRGINIA 22092
A FOLDER DESCRIBING TOPOGRAPHIC MAPS AND SYMBOLS IS AVAILABLE ON REQUEST




QUADRANGLE LOCATION
3296-313

ROAD CLASSIFICATION
Heavy-duty ——— Light-duty ———
Medium-duty ——— Unimproved dirt ———
○ Interstate Route ○ U.S. Route ○ State Route


HUTCHINS, TEX.
32096 F6 TF-024

1958
PHOTOREVISED 1968 AND 1973
DMA 6649 II NW-SERIES V882



Maped, edited, and published by the Geological Survey
Control by USGS and NOS/NOAA
Culture and drainage in part compiled from aerial photographs
taken 1952 and 1956. Topography from City of Dallas surveys 1954
and by planetable surveys 1958
Polyconic projection. 10,000-foot grid ticks based on Texas coordinate
system, north central zone. 1000-meter Universal Transverse Mercator
grid ticks, zone 14, shown in blue. 1927 North American Datum
To place on the predicted North American Datum 1983 move the projection
lines 11 meters south and 26 meters east as shown by dashed corner ticks
Red tint indicates areas in which only landmark buildings are shown
There may be private inholdings within the boundaries
of the National or State reservations shown on this map

Revisions shown in purple and woodtint compiled from
aerial photographs taken 1979 and other sources. This
information not fic d checked. Map edited 1981
Purple tint indic extension of urban areas



ROAD CLASSIFICATION
Primary highway, all weather, hard surface
Secondary highway, all weather, hard surface
Light duty road, all weather, improved surface
Unimproved road, fair or dry weather
Interstate Route U. S. Route State Route

OAK CLIFF, TEX.
N3237 5-W9645/7 5
1958
PHOTOREVISED 1981
DMA 6649 111 NE-SERIES V882

THIS MAP COMPLIES WITH NATIONAL MAP ACCURACY STANDARDS
FOR SALE BY U.S. GEOLOGICAL SURVEY CENTER, COLORADO 80225, OR RESTON, VIRGINIA 22092
A FOLDER DESCRIBING TOPOGRAPHIC MAPS AND SYMBOLS IS AVAILABLE ON REQUEST

Reference 20

DATA QUALITY ASSURANCE REVIEW

SITE NAME Nethery Landfill
CERCLIS _____
PAN 080801SIXX TDD NUMBER 06-99-03-0001
CASE NUMBER/WORK ORDER 27273/6S256 SDG/PROJ. NUMBER FCX38/MFJS80

E & E has completed a QA review for Case No. 27273/6S256, SDG No. FCX38/MFJS80, Nethery Landfill. Nineteen sediment/soil samples were analyzed for TCL volatiles, TCL semivolatiles, TCL pesticides/PCBs and TAL metals by Southwest Laboratory of Oklahoma, Inc. and DataChem Laboratories, Inc. Sample numbers are listed below.

SAMPLE NUMBERS

| | | |
|--------------|-----------------------------|-----------------------------|
| <u>SS-01</u> | <u>SD-09</u> | <u> </u> |
| <u>SS-02</u> | <u>SD-10</u> | <u> </u> |
| <u>SS-03</u> | <u>SD-11</u> | <u> </u> |
| <u>SS-04</u> | <u>SD-12</u> | <u> </u> |
| <u>SD-01</u> | <u>SD-13</u> | <u> </u> |
| <u>SD-02</u> | <u>SD-14</u> | <u> </u> |
| <u>SD-03</u> | <u>SD-15</u> | <u> </u> |
| <u>SD-04</u> | <u> </u> | <u> </u> |
| <u>SD-05</u> | <u> </u> | <u> </u> |
| <u>SD-06</u> | <u> </u> | <u> </u> |
| <u>SD-07</u> | <u> </u> | <u> </u> |
| <u>SD-08</u> | <u> </u> | <u> </u> |

This data package was validated to determine if Quality Control (QC) specifications were achieved, following *USEPA Contract Laboratory Program National Functional Guidelines for Organic Data Review* (February, 1994), *USEPA Contract Laboratory Program National Functional Guidelines for Inorganic Data Review* (February, 1994), *Quality Assurance/Quality Control Guidance for Removal Activities* (April, 1990), and the Regional Protocol for Holding Times, Blanks, and VOA Preservation (April 13, 1989). Specific data qualifications are listed in the following discussion.

REVIEWER Michelle Brown DATE 11-01-99

Data Qualifiers

Data Qualifier Definitions were supplied by the Office of Solid Waste and Emergency Response (September 1989) and are included in the Functional Guidelines. Data qualifiers may be combined (UJ, QJ) with the corresponding combination of meanings. Additional qualifier may be added to provide additional, more specific information (JL, UB, QJK), modifying the meaning of the primary qualifier. Additional qualifiers utilized by E & E are H, L, K, B, Q, and D.

- U - The material was analyzed for, but was not detected. The associated numerical value is the sample quantitation or detection limit, which has been adjusted for sample weight/sample volume, extraction volume, percent solids, sample dilution or other analysis specific parameters.

An additional qualifier, "B", may be appended to indicate that while the analyte was detected in the sample, the presence of the analyte may be attributable to blank contamination and the analyte is therefore considered undetected with the sample detection or quantitation limit for the analyte being elevated.

- J - The analyte was analyzed for, but the associated numerical value may not be consistent with the amount actually present in the environmental sample or may not be consistent with the sample detection or quantitation limit. The value is an estimated quantity. The data should be seriously considered for decision-making and are usable for many purposes.

An additional qualifier will be appended to the "J" qualifier that indicates the bias in the reported results:

L Low bias

H High bias

K Unknown bias

- Q The reported concentration is less than the sample quantitation limit for the specific analyte in the sample.

The L and H qualifier will only be employed when a single qualification is required. When more than one quality control parameter affects the analytical result and a conflict results in assigning a bias, the result will be flagged JK.

- R - Quality Control indicates that data are unusable for all purposes. The analyte was analyzed for, but the presence or absence of the analyte has not been verified. Resampling and reanalysis are necessary for verification to confirm or deny the presence of an analyte.
- N - The analysis indicates the presence of analyte for which there is presumptive evidence to make a "tentative identification."
- D - The concentration reported was determined in the re-analysis of the sample at a secondary dilution.

CLP DATA REVIEW

A review of the data validation conducted by the ESAT contractor has been completed with an emphasis on HRS criteria. Results of this review follow.

The validation report is complete and no modifications of the qualifications listed are necessary. The data qualifier flags utilized by the ESAT contractor have been modified as described in the cover for this review.

SQL Factors

Inorganic sample quantitation limits (SQLs) were greater than CRDLs in the following samples due to the factors listed below.

| SAMPLE NO | ANALYTE | DF | ASV OR ASW | % SOLIDS | ADV | SQL FACTOR |
|-----------|-----------|----|---------------|----------|-----|---------------|
| SS01 | ICP Hg | | 1.02 | 98.3 | 0.2 | 0.203 |
| | | | 0.2 | 98.3 | 0.1 | 0.509 |
| SS02 | ICP Hg | | 1.0 | 98.9 | 0.2 | 0.198 |
| | | | 0.2 | 98.9 | 0.1 | 0.506 |
| SS03 | ICP Hg | | 1.0 | 98.6 | 0.2 | 0.203 |
| | | | 0.2 | 98.6 | 0.1 | 0.507 |
| SD01 | ICP Hg | | 1.0 | 72.7 | 0.2 | 0.275 |
| | | | 0.2 | 72.7 | 0.1 | 0.688 |
| SD02 | ICP Hg | | 1.0 | 70.6 | 0.2 | 0.283 |
| | | | 0.2 | 70.6 | 0.1 | 0.708 |
| SD03 | ICP Hg | | 1.0 | 72.9 | 0.2 | 0.274 |
| | | | 0.2 | 72.9 | 0.1 | 0.686 |
| SD04 | ICP Hg | | 1.0 | 62.7 | 0.2 | 0.319 |
| | | | 0.2 | 62.7 | 0.1 | 0.797 |
| SD05 | ICP Hg | | 1.0 | 83.5 | 0.2 | 0.240 |
| | | | 0.2 | 83.5 | 0.1 | 0.599 |
| SD06 | ICP Hg | | 1.0 | 76.6 | 0.2 | 0.261 |
| | | | 0.2 | 76.6 | 0.1 | 0.653 |
| SD07 | ICP Hg | | 1.0 | 70.3 | 0.2 | 0.284 |
| | | | 0.2 | 70.3 | 0.1 | 0.711 |
| SD08 | ICP Hg | | 1.0 | 72.5 | 0.2 | 0.276 |
| | | | 0.2 | 72.5 | 0.1 | 0.690 |

| SAMPLE NO | ANALYTE | DF | ASV OR ASW | % SOLIDS | ADV | SQL FACTOR |
|-----------|-----------|----|---------------|--------------|------------|----------------|
| SD09 | ICP Hg | | 1.0 0.2 | 78.5 78.5 | 0.2 0.1 | 0.255 0.637 |
| SD10 | ICP Hg | | 1.0 0.2 | 83.4 83.4 | 0.2 0.1 | 0.240 0.600 |
| SD11 | ICP Hg | | 1.0 0.2 | 78.2 78.2 | 0.2 0.1 | 0.256 0.639 |
| SD12 | IP Hg | | 1.0 0.2 | 71.1 71.1 | 0.2 0.1 | 0.281 0.703 |
| SD13 | ICP Hg | | 1.0 0.2 | 81.8 81.8 | 0.2 0.1 | 0.244 0.611 |
| SD14 | ICP Hg | | 1.0 0.2 | 89.7 89.7 | 0.2 0.1 | 0.223 0.557 |
| SD15 | ICP Hg | | 1.0 0.2 | 90.7 90.7 | 0.2 0.1 | 0.221 0.551 |
| SS04 | ICP Hg | | 1.0 0.2 | 86.2 86.2 | 0.2 0.1 | 0.232 0.580 |

Volatile sample quantitation limits (SQLs) varied from the CRQLs in the following samples due to the factors listed below.

| SAMPLE NO. | LEVEL | % SOLID moisture | SAMPLE WT/VOL (gm/ml) | DF | SEV (ul) | SAV (ul) | SQL FACTOR |
|------------|-------|---------------------|-----------------------------|----|-------------|-------------|---------------|
| SS01 | Low | 2 | | | | | 1.02 |
| SS02 | Low | 2 | | | | | 1.02 |
| SS03 | Low | 2 | | | | | 1.02 |
| SD01 | Low | 26 | | | | | 1.35 |
| SD02 | Low | 20 | | | | | 1.25 |
| SD03 | Low | 33 | | | | | 1.49 |
| SD04 | Low | 38 | | | | | 1.61 |
| SD05 | Low | 16 | | | | | 1.19 |
| SD06 | Low | 16 | | | | | 1.19 |

| SAMPLE NO. | LEVEL | % SOLID moisture | SAMPLE WT/VOL (gm/ml) | DF | SEV (ul) | SAV (ul) | SQL FACTOR |
|------------|-------|------------------|-----------------------|----|----------|----------|------------|
| SD07 | Low | 32 | | | | | 1.47 |
| SD08 | Low | 22 | | | | | 1.28 |
| SD09 | Low | 17 | | | | | 1.20 |
| SD10 | Low | 17 | | | | | 1.20 |
| SD11 | Low | 42 | | | | | 1.72 |
| SD12 | Low | 20 | | | | | 1.25 |
| SD13 | Low | 15 | | | | | 1.18 |
| SD14 | Low | 9 | | | | | 1.10 |
| SD15 | Low | 15 | | | | | 1.18 |
| SS04 | Low | 1 | | | | | 1.01 |

DF = dilution factor, SEV = soil extract volume, SAV = soil aliquot volume

Semivolatile quantitation limits (SQLs) varied from the CRQLs in the following samples due to the factors listed below.

| SAMPLE NO. | LEVEL | % SOLID moisture | SAMPLE WT/VOL (gm/ml) | GPC y/n | DF | CEV (ul) | SQL FACTOR |
|------------|-------|------------------|-----------------------|---------|----|----------|------------|
| SS01 | Low | 2 | 31.2 | y | 2 | | 1.96 |
| SS02 | Low | 2 | 32.4 | y | | | 0.945 |
| SS02RE | Low | 2 | 32.2 | y | | | 0.951 |
| SS03 | Low | 2 | 33.4 | y | | | 0.916 |
| SD01 | Low | 26 | 31.5 | y | | | 1.29 |
| SD01DL | Low | 26 | 31.5 | y | 2 | | 2.57 |
| SD02 | Low | 20 | 30.9 | y | 2 | | 2.43 |
| SD02DL | Low | 20 | 30.9 | y | 4 | | 4.85 |
| SD03 | Low | 33 | 31.1 | y | | | 1.44 |

| SAMPLE NO. | LEVEL | % SOLID moisture | SAMPLE WT/VOL (gm/ml) | GPC y/n | DF | CEV (ul) | SQL FACTOR |
|------------|-------|------------------|-----------------------|---------|----|----------|------------|
| SD04 | Low | 38 | 32.5 | y | | | 1.49 |
| SD05 | Low | 16 | 32.9 | y | | | 1.08 |
| SD06 | Low | 16 | 33.6 | y | | | 1.06 |
| SD07 | Low | 32 | 32.0 | y | | | 1.38 |
| SD08 | Low | 22 | 32.1 | y | | | 1.20 |
| SD09 | Low | 17 | 31.4 | y | | | 1.15 |
| SD10 | Low | 17 | 31.9 | y | | | 1.13 |
| SD10RE | Low | 17 | 32.4 | y | | | 1.12 |
| SD11 | Low | 42 | 31.4 | y | 2 | | 3.29 |
| SD12 | Low | 20 | 31.8 | y | | | 1.18 |
| SD13 | Low | 15 | 31.2 | y | | | 1.13 |
| SD14 | Low | 9 | 33.5 | y | | | 0.984 |
| DS15 | Low | 15 | 31.4 | y | | | 1.12 |
| SS04 | Low | 1 | 33.1 | y | | | 0.915 |

DF = dilution factor, CEV = concentrated extract volume

Pesticide/PCB quantitation limits (SQLs) varied from the CRQLs in the following samples due to the factors listed below.

| SAMPLE NO. | LEVEL | % SOLID moisture | SAMPLE WT (gm) | GPC y/n | DF | CEV (ul) | SQL FACTOR |
|------------|-------|------------------|----------------|---------|-----|----------|------------|
| SS01 | Low | 2 | 30.7 | y | 10 | | 9.97 |
| SS01DL | Low | 2 | 30.7 | y | 100 | | 99.7 |
| SS02 | Low | 2 | 33.2 | y | 10 | | 9.22 |
| SS02DL | Low | 2 | 33.2 | y | 100 | | 92.2 |
| SS03 | Low | 2 | 30.6 | y | 10 | | 10.0 |
| SS03DL | Low | 2 | 30.6 | y | 100 | | 100.0 |
| SD01 | Low | 26 | 30.6 | y | 10 | | 13.2 |

| SAMPLE NO. | LEVEL | % SOLID moisture | SAMPLE WT (gm) | GPC y/n | DF | CEV (ul) | SQL FACTOR |
|------------|-------|------------------|----------------|---------|-----|----------|------------|
| SD01DL | Low | 26 | 30.6 | y | 100 | | 132.5 |
| SD02 | Low | 20 | 33.4 | y | 10 | | 11.2 |
| SD02DL | Low | 20 | 33.4 | y | 100 | | 112.3 |
| SD03 | Low | 33 | 32.1 | y | 10 | | 13.9 |
| SD03DL | Low | 33 | 32.1 | y | 100 | | 139.5 |
| SD04 | Low | 38 | 31.4 | y | 10 | | 15.4 |
| SD04DL | Low | 38 | 31.4 | y | 100 | | 154.1 |
| SD05 | Low | 16 | 32.4 | y | 10 | | 11.0 |
| SD05DL | Low | 16 | 32.4 | y | 100 | | 110.2 |
| SD06 | Low | 16 | 33.2 | y | 10 | | 10.8 |
| SD06DL | Low | 16 | 33.2 | y | 100 | | 107.6 |
| SD07 | Low | 32 | 31.9 | y | 10 | | 13.8 |
| SD07DL | Low | 32 | 31.9 | y | 100 | | 138.3 |
| SD08 | Low | 22 | 32.2 | y | 10 | | 11.9 |
| SD08DL | Low | 22 | 32.2 | y | 100 | | 119.4 |
| SD09 | Low | 17 | 31.7 | y | 10 | | 11.4 |
| SD09DL | Low | 17 | 31.7 | y | 100 | | 114.0 |
| SD10 | Low | 17 | 31.7 | y | 10 | | 11.4 |
| SD10DL | Low | 17 | 31.7 | y | 100 | | 114.0 |
| SD11 | Low | 42 | 30.2 | y | 10 | | 17.1 |
| SD11DL | Low | 42 | 30.2 | y | 100 | | 171.3 |
| SD12 | Low | 20 | 31.0 | y | 10 | | 12.1 |
| SD12DL | Low | 20 | 31.0 | y | 100 | | 121.0 |
| SD13 | Low | 15 | 30.6 | y | 10 | | 11.5 |
| SD13DL | Low | 15 | 30.6 | y | 100 | | 115.3 |
| SD14 | Low | 9 | 31.8 | y | 10 | | 10.4 |
| SD14DL | Low | 9 | 31.8 | y | 100 | | 103.7 |
| SD15 | Low | 15 | 32.3 | y | 10 | | 10.9 |

| SAMPLE NO. | LEVEL | % SOLID moisture | SAMPLE WT (gm) | GPC y/n | DF | CEV (ul) | SQL FACTOR |
|------------|-------|------------------|----------------|---------|-----|----------|------------|
| SD15DL | Low | 15 | 32.3 | y | 100 | | 109.3 |
| SS04 | Low | 15 | 34.0 | y | 10 | | 8.9 |
| SS04DL | Low | 15 | 34.0 | y | 100 | | 89.1 |

DF = dilution factor, CEV = concentrated extract volume

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
REGION 6
HOUSTON BRANCH
10625 FALLSTONE ROAD
HOUSTON, TEXAS 77099

ORGANIC REGIONAL DATA ASSESSMENT

CASE NO. 27273 SITE NETHERY LF
LABORATORY SWOK NO. OF SAMPLES 19
CONTRACT# 68-D5-0026 MATRIX soil
SDG# FCX38 REVIEWER (IF NOT ESD) ESAT
SOW# RAS OLM03.2 REVIEWER'S NAME Mike Fertitta
and Gene Zhu
ACCT#950102DJN64 SF#50102DZZ COMPLETION DATE September 28, 1999

SAMPLE NO.'s: FC-X38 FC-X42 FC-X46 FC-X50 FC-X54
FC-X39 FC-X43 FC-X47 FC-X51 FC-X55
FC-X40 FC-X44 FC-X48 FC-X52 FC-X56
FC-X41 FC-X45 FC-X49 FC-X53

DATA ASSESSMENT SUMMARY

| | VOA | BNA | PEST |
|-------------------------------|-----|-----|------|
| 1. HOLDING TIMES | O | M | O |
| 2. GC/MS TUNE/INSTR. PERFORM. | O | O | O |
| 3. CALIBRATIONS | O | O | O |
| 4. BLANKS | O | M | O |
| 5. SMC/SURROGATES | O | O | O |
| 6. MATRIX SPIKE/DUPLICATE | O | O | O |
| 7. OTHER QC | O | O | O |
| 8. INTERNAL STANDARDS | O | O | N/A |
| 9. COMPOUND ID/QUANTITATION | O | M | O |
| 10. PERFORMANCE/COMPLETENESS | O | O | O |
| 11. OVERALL ASSESSMENT | O | M | O |

O = Data had no problems.

M = Data qualified due to major or minor problems.

Z = Data unacceptable.

NA = Not applicable.

∴

ACTION ITEMS: Two BNA extractions exceeded the contractual holding time limit by eight days. The data package arrived 11 working days late.

AREA OF CONCERN: The laboratory omitted the GC/MS confirmation analysis for dieldrin in Pest/PCB sample FC-X42. Initial Pest/PCB analyses (10X dilution) are not billable because the associated ending PEM calibrations are noncompliant. Some BNA results were qualified because of laboratory contamination and inconsistent reanalysis results.

NOTABLE PERFORMANCE:

COMMENTS/CLARIFICATIONS
REGION 6 CLP QA REVIEW

CASE 27273 SDG FCX38 SITE NETHERY LF LAB SWOK

The following is a summary of sample qualifiers used by Region 6 in reporting this CLP data:

| <u>No.</u> | <u>Acceptable</u> | <u>Provisional</u> | <u>Unacceptable</u> |
|------------|-------------------|--------------------|---------------------|
| VOA | <u>19</u> | <u></u> | <u></u> |
| BNA | <u>15</u> | <u>4</u> | <u>N/A</u> |
| PEST | <u>19</u> | <u></u> | <u></u> |

COMMENTS: The case consisted of 19 soil samples for complete RAS organics analysis by OLM03.2. The OTR/COC Records designated samples FC-X39/FC-X40 and FC-X48/FC-X49 as field duplicate pairs and samples FC-X38 and FC-X46 as laboratory QC samples. The laboratory chose to perform QC on sample FC-X38 since only one set of QC is required by the SOW. The CRQL's require %moisture correction for soil samples and additional dilution correction for diluted samples. Corrected CRQL's are reported by the laboratory and are referred to as sample quantitation limits (SQL') in this report.

The data package contained the following contractually noncompliant items.

- The extractions for BNA samples FC-X39RE and FC-X50RE exceeded the contractual holding time limit by eight days.
- The laboratory omitted the contract-required GC/MS confirmation analysis for dieldrin in Pest/PCB sample FC-X42. Reanalysis is requested.
- All initial Pest/PCB sample analyses (at 10X dilution) are not compliant or billable because they are associated with PEM standards that failed contractual criteria.
- The data package arrived 11 working days late for the required 14-day turnaround time.

All VOA and BNA samples were analyzed at the low level. VOA samples FC-X38 and FC-X51 contained acetone at concentrations above the SQL's.

BNA Samples FC-X41 and FC-X42 required reanalyses at up to 4X dilution because of high concentrations of fluoranthene (up to 10,000 µg/L) and pyrene (up to 6,400 µg/L). Other TCL analytes detected at concentrations above SQL's in the samples for this SDG included bis(2-ethylhexyl)phthalate, carbazole, and PAH's.

ORGANIC QA REVIEW
CONTINUATION PAGE

CASE 27273 SDG FCX38 SITE NETHERY LF LAB SWOK

COMMENTS (continued): The laboratory apparently analyzed samples FC-X38, FC-X38MS/MSD, and FC-X51 at 2X dilution because of high levels of non-target compounds. Samples FC-X39 and FC-X50 were re-extracted and reanalyzed because surrogate recoveries failed QC criteria. The reanalyses corrected the surrogate problems, so only data for samples FC-X39RE and FC-X50RE are to be used. However, the re-extraction was performed 18 days after the collection for both samples.

Pest/PCB With Region 6 approval, the laboratory submitted data for both the initial analysis (at 10X dilution) and the diluted reanalysis (at 100X dilution) for each sample. The initial analyses are associated with ending PEM calibrations that failed contractual criteria, and the laboratory blamed this problem on sample matrix effects. The reviewer recommends that only the diluted reanalysis data be used although the 100X dilution substantially escalated the SQL's. The only target compound reported above the elevated SQL is dieldrin at a high concentration (940 µg/Kg) in sample FC-X42. The laboratory failed to perform the contract-required GC/MS confirmation for dieldrin, and reanalysis is recommended.

Data are provisional for four BNA samples because of problems with holding times, laboratory contamination, and compound quantitation. The technical usability of all reported sample results is indicated by ESAT's final data qualifiers in the Data Summary Table. An Evidence Audit was conducted for the Complete Sample Delivery Group File (CSF), and the results were recorded in the Evidence Inventory Checklist.

NOTE: THE FOLLOWING REVIEW NARRATIVE ADDRESSES BOTH CONTRACTUAL ISSUES (BASED ON THE STATEMENT OF WORK) AND TECHNICAL ISSUES (BASED ON THE NATIONAL FUNCTIONAL GUIDELINES). THE ASSESSMENT MADE FOR EACH QC PARAMETER IS SOLELY BASED ON THE TECHNICAL DATA USABILITY, WHICH MAY NOT NECESSARILY BE AFFECTED BY CONTRACTUAL PROBLEMS. THE ASSESSMENTS ARE DEFINED BELOW.

Acceptable = No results were qualified for any problem associated with this QC parameter.

Provisional = Some results were qualified because of problems associated with this QC parameter.

Unusable = All results are unusable because of major problems associated with this QC parameter.

1. Holding Times: Provisional. All sample extractions and analyses met the contractual holding time requirements with two

ORGANIC QA REVIEW
CONTINUATION PAGE

CASE 27273 SDG FCX38 SITE NETHERY LF LAB SWOK

1. **Holding Times (continued):** exceptions. The extractions of BNA samples FC-X39RE and FC-X50RE exceeded the contractual holding time limit by eight days. Technical holding time criteria have not been established for soil samples. Based on Regional guidelines, the reviewer qualified as estimated all positive hits at concentrations above the SQL's for BNA samples FC-X39RE and FC-X50RE.

2. **Tuning/Performance:** Acceptable. The BFB and DFTPP analyses met the QC criteria. All Pest/PCB sample analyses met instrument performance guidelines.

3. **Calibrations:** Acceptable. VOA and BNA target analytes generally met contractual calibration criteria. Some VOA and BNA analytes failed technical %RSD and/or %D calibration criteria but were not detected at concentrations above the SQL's in the associated samples.

Pest/PCB DDT and methoxychlor failed %D and %breakdown calibration criteria on both columns for the ending PEM calibration verifications associated with all initial sample analyses (at 10X dilution). Since data for the initial analyses are not recommended for use, results were not qualified. The calibrations associated with the diluted reanalyses met contractual calibration criteria.

4. **Blanks:** Provisional. The method, instrument, and storage blanks were contractually compliant. The VOA and Pest/PCB blanks contained no target analytes.

BNA The method blanks contained di-n-butylphthalate and/or bis(2-ethylhexyl)phthalate at concentrations below the CRQL's. The reviewer made the following qualifications because of laboratory contamination.

The bis(2-ethylhexyl)phthalate concentration (>SQL) for sample FC-X40 was qualified as undetected (U) and should be used as a raised QL.

The bis(2-ethylhexyl)phthalate concentration (>SQL) for sample FC-X38 was flagged "B" to indicate a high bias.

The other laboratory "B"-flagged results below the SQL's should be considered undetected because they were less than 10X the associated method blank values.

ORGANIC QA REVIEW
CONTINUATION PAGE

CASE 27273 SDG FCX38 SITE NETHERY LF LAB SWOK

5. System Monitoring Compounds (SMC's)/Surrogates: Acceptable. SMC and surrogate recoveries met the QC criteria with the following exceptions.

BNA Samples FC-X39 and FC-X50 failed QC criteria for surrogate recovery but the re-extractions, samples FC-X39RE and FC-X50RE, had acceptable surrogate recoveries. Since results for samples FC-X39RE and FC-X50RE are designated for use, no data qualification was necessary.

6. Matrix Spike/Matrix Spike Duplicate (MS/MSD): Acceptable. MS/MSD results met QC criteria for precision and %recovery with a few exceptions. The MSD recovery was high for pyrene and the %RPD's were high for acenaphthene, pyrene, and DDT. None of these analytes had concentrations above the SQL's in the unspiked samples, so the reviewer did not qualify the unspiked sample results.

7. Other QC:

Field Duplicates: Acceptable. Field duplicate results were generally consistent.

8. Internal Standards (IS): Acceptable. The IS performance was acceptable for all VOA and BNA samples.

9. Compound Identity (ID)/Quantitation: Provisional. Analytes met the compound identification and quantitation guidelines.

VOA Samples FC-X38 and FC-X51 contained acetone at concentrations above the SQL's. TCL analytes reported at concentrations below the SQL's in some samples included methylene chloride and toluene.

BNA Samples FC-X41 and FC-X42 were diluted up to 4X because of high concentrations of fluoranthene (6,200 µg/Kg and 10,000 µg/Kg, respectively) and pyrene (4,100 µg/Kg and 6,400 µg/Kg, respectively). Many PAH's were reported above the SQL's in samples FC-C39, FC-X40, FC-X41, FC-X42, FC-X43, FC-X48, FC-X49, FC-X50, and FC-X56. Other target compounds reported above the SQL's included carbazole in samples FC-X41 and FC-X42 and bis(2-ethylhexyl)phthalate in sample FC-X38.

The reviewer qualified as estimated all positive results with concentrations above the SQL's for sample FC-X50RE because the

ORGANIC QA REVIEW
CONTINUATION PAGE

CASE 27273 SDG FCX38 SITE NETHERY LF LAB SWOK

9. Compound ID/Quantitation (continued): concentrations were up to 8X the SQL's, but concentrations for these analytes were below or near the SQL's in the original analysis. This inconsistency can not be explained by the high surrogate recoveries for the original analysis. The laboratory "E"-flagged the Form 1 fluoranthene and pyrene results for sample FC-X50RE, indicating that the associated concentrations were above the calibration range. Since the concentrations actually rounded to the upper calibration limit, the reviewer did not qualify the sample results.

Pest/PCB The SQL's were elevated substantially for all diluted reanalyses because of high dilution (100X). The only analyte reported above the elevated SQL was dieldrin at a concentration of 940 µg/Kg in sample FC-X42. The laboratory omitted the contract-required GC/MS confirmation for this analyte, and reanalysis is recommended. All reported sample results, including those below the SQL's, met compound identification criteria. The laboratory reported an extremely low concentration (less than 10 percent of the SQL) for DDT in sample FC-X56DL. The reviewer raised the low concentration to the SQL and flagged it "U" following the Region 6 guidelines.

10. Performance/Completeness: Acceptable. The data package was complete with some minor omissions and problems requiring resolution (see FAX Record Logs).

In response to CCS and one of two Regional requests, the laboratory has already sent some omitted items and needed corrections. The reviewer exchanged or inserted the following documents in the package: SDG Narrative pages 2 and 3; BNA Form 2 (page 244); Forms 1 and quantitation reports for some BNA samples (pages 333 to 337A, 466 to 470, 530 to 535, 592 to 596, 654 to 659, 720 to 724A, 779 to 783, 1044, 1046, 1162 to 1166, and 1738 to 1742); and Pest/PCB standard data (pages 2171A and 2171B). The resubmission cover pages are included at the beginning of the data package.

11. Overall Assessment: Data are acceptable for all VOA and Pest/PCB samples.

BNA Some data are provisional for samples FC-X38, FC-X39RE, FC-X40, and FC-X50RE because of problems with holding times, laboratory contamination, and compound quantitation.

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
REGION 6
HOUSTON BRANCH
10625 FALLSTONE ROAD
HOUSTON, TEXAS 77099

RESUBMITTED DATA REVIEW REPORT

| | | | |
|-------|------------------------|--------|-------------------------------------|
| DATE: | <u>10/06/1999</u> | CASE#: | <u>27273</u> |
| | | SDG#: | <u>FCX38</u> |
| TO: | <u>B. Rhotenberry</u> | LAB: | <u>SWOX</u> |
| | <u>(6SF-RA)</u> | SITE: | <u>Nethery LF</u> |
| FROM: | <u>Gene Zhu (LMSG)</u> | REF: | <u>TDF # 6-9331A</u> |
| | <u>ESAT - Region 6</u> | | <u>ESAT File # O-2049</u> |
| | <u>Page 1 of 1</u> | | <u>ESAT Contract No. 68-D6-0005</u> |

EFFECTS OF RESUBMITTED INFORMATION ON THE ORIGINAL DATA:

Laboratory response to Region 6 FAX request: (received by ESAT on 10/5/99)

A. BNA

1. The laboratory submitted the requested corrections. Please use the resubmitted pages 333, 334, 337, 337A, 720, 721, 724, 724A, 779, 780, 783, 783A, 1040, 1041, and 1044. The changes in sample result are highlighted on the attached revision of the Data Summary Table for semivolatiles. The BNA portion of the original data review report is unaffected by this resubmission.
2. The laboratory failed to submit a blank page 12 to replace the extra alkane report for BNA sample FC-X40. The reviewer generated one that should replace the originally submitted page 12.

B. Pest/PCB

1. Please use the resubmitted standard analysis data for AR123215C (pages 2171A and 2171B).
2. The laboratory performed the GC/MS analysis that confirmed the dieldrin identification for sample FC-X42. Please use the resubmitted Form I's for samples FC-X42 and FC-X42DL (pages 1936 and 1941). Please also use the submitted GC/MS confirmation data for sample FC-X42 (pages 719A to 719C, 1681A, 1681B, 1702A to 1702D, 1811A, and 1811B).
- 3&4. The laboratory submitted the communication logs and the raw data that demonstrated matrix problems for the samples in SDG. The submitted raw data indicated that the laboratory performed the 10X diluted sample analyses for all 19 samples in this SDG within one 12 hour sequence on a different instrument prior to contacting the EPA about the matrix problem. These unpaginated data should be used as supporting document for this case. The resubmitted data had no effect on the original data review report.

ORGANIC DATA SUMMARY

Case No.: 27273

SDG: FCX38

Reviewer: Mike Fertitta

Laboratory: SWOK

Matrix: Soil

Units: ug/Kg

| VOLATILES | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG |
|---------------------------|--------|--------|--------|--------|--------|--------|--------|
| EPA SAMPLE NUMBER: | FC-X38 | FC-X39 | FC-X40 | FC-X41 | FC-X42 | FC-X43 | FC-X44 |
| Chloromethane | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| Bromomethane | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| Vinyl Chloride | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| Chloroethane | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| Methylene Chloride | 6QJK | 6QJK | 3QJK | 14U | 12U | 15U | 16U |
| Acetone | 16 | 10U | 10U | 14U | 12U | 15U | 16U |
| Carbon Disulfide | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| 1,1-Dichloroethene | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| 1,1-Dichloroethane | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| Total 1,2-Dichloroethene | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| Chloroform | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| 1,2-Dichloroethane | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| 2-Butanone | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| 1,1,1-Trichloroethane | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| Carbon Tetrachloride | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| Bromodichloromethane | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| 1,2-Dichloropropane | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| Cis-1,3-Dichloropropene | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| Trichloroethene | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| Dibromochloromethane | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| 1,1,2-Trichloroethane | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| Benzene | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| Trans-1,3-Dichloropropene | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| Bromoform | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| 4-Methyl-2-pentanone | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| 2-Hexanone | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| Tetrachloroethene | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| 1,1,2,2-Tetrachloroethane | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| Toluene | 1QJK | 1QJK | 10U | 14U | 12U | 15U | 16U |
| Chlorobenzene | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| Ethylbenzene | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| Styrene | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| Xylene (total) | 10U | 10U | 10U | 14U | 12U | 15U | 16U |
| Sample wt (g) : | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 |
| %Moisture : | 2 | 2 | 2 | 26 | 20 | 33 | 38 |
| Dilution Factor: | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 |
| Level: | LOW | LOW | LOW | LOW | LOW | LOW | LOW |
| Number of TIC's: | 2 | 5 | 1 | 0 | 0 | 0 | 1 |

Note: For the results listed in the Data Summary Table, ESAT has replaced the laboratory assigned flags with ESAT Organic Data Qualifiers. The ESAT flags indicate the technical usability of the reported results.

ORGANIC DATA SUMMARY

Case No.: 27273

SDG: FCX38

Reviewer: Mike Fertitta

Laboratory: SWOK

Matrix: Soil

Units: ug/Kg

| VOLATILES | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG |
|---------------------------|--------|--------|--------|--------|--------|--------|--------|
| EPA SAMPLE NUMBER: | FC-X45 | FC-X46 | FC-X47 | FC-X48 | FC-X49 | FC-X50 | FC-X51 |
| Chloromethane | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| Bromomethane | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| Vinyl Chloride | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| Chloroethane | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| Methylene Chloride | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| Acetone | 12U | 12U | 15U | 13U | 12U | 12U | 52 |
| Carbon Disulfide | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| 1,1-Dichloroethene | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| 1,1-Dichloroethane | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| Total 1,2-Dichloroethene | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| Chloroform | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| 1,2-Dichloroethane | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| 2-Butanone | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| 1,1,1-Trichloroethane | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| Carbon Tetrachloride | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| Bromodichloromethane | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| 1,2-Dichloropropane | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| Cis-1,3-Dichloropropene | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| Trichloroethene | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| Dibromochloromethane | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| 1,1,2-Trichloroethane | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| Benzene | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| Trans-1,3-Dichloropropene | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| Bromoform | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| 4-Methyl-2-pentanone | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| 2-Hexanone | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| Tetrachloroethene | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| 1,1,2,2-Tetrachloroethane | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| Toluene | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| Chlorobenzene | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| Ethylbenzene | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| Styrene | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| Xylene (total) | 12U | 12U | 15U | 13U | 12U | 12U | 17U |
| Sample wt (g) : | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 |
| %Moisture : | 16 | 16 | 32 | 22 | 17 | 17 | 42 |
| Dilution Factor: | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 |
| Level: | LOW | LOW | LOW | LOW | LOW | LOW | LOW |
| Number of TIC's: | 0 | 0 | 0 | 0 | 0 | 0 | 1 |

Note: For the results listed in the Data Summary Table, ESAT has replaced the laboratory assigned flags with ESAT Organic Data Qualifiers. The ESAT flags indicate the technical usability of the reported results.

ORGANIC DATA SUMMARY

Case No.: 27273

SDG: FCX38

Reviewer: Mike Fertitta

Laboratory: SWOK

Matrix: Soil

Units: ug/Kg

| VOLATILES | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG |
|---------------------------|--------|--------|--------|--------|--------|------|------|
| EPA SAMPLE NUMBER: | FC-X52 | FC-X53 | FC-X54 | FC-X55 | FC-X56 | | |
| Chloromethane | 12U | 12U | 11U | 12U | 10U | | |
| Bromomethane | 12U | 12U | 11U | 12U | 10U | | |
| Vinyl Chloride | 12U | 12U | 11U | 12U | 10U | | |
| Chloroethane | 12U | 12U | 11U | 12U | 10U | | |
| Methylene Chloride | 12U | 12U | 11U | 6QJK | 10U | | |
| Acetone | 12U | 12U | 11U | 12U | 10U | | |
| Carbon Disulfide | 12U | 12U | 11U | 12U | 10U | | |
| 1,1-Dichloroethene | 12U | 12U | 11U | 12U | 10U | | |
| 1,1-Dichloroethane | 12U | 12U | 11U | 12U | 10U | | |
| Total 1,2-Dichloroethene | 12U | 12U | 11U | 12U | 10U | | |
| Chloroform | 12U | 12U | 11U | 12U | 10U | | |
| 1,2-Dichloroethane | 12U | 12U | 11U | 12U | 10U | | |
| 2-Butanone | 12U | 12U | 11U | 12U | 10U | | |
| 1,1,1-Trichloroethane | 12U | 12U | 11U | 12U | 10U | | |
| Carbon Tetrachloride | 12U | 12U | 11U | 12U | 10U | | |
| Bromodichloromethane | 12U | 12U | 11U | 12U | 10U | | |
| 1,2-Dichloropropane | 12U | 12U | 11U | 12U | 10U | | |
| Cis-1,3-Dichloropropene | 12U | 12U | 11U | 12U | 10U | | |
| Trichloroethene | 12U | 12U | 11U | 12U | 10U | | |
| Dibromochloromethane | 12U | 12U | 11U | 12U | 10U | | |
| 1,1,2-Trichloroethane | 12U | 12U | 11U | 12U | 10U | | |
| Benzene | 12U | 12U | 11U | 12U | 10U | | |
| Trans-1,3-Dichloropropene | 12U | 12U | 11U | 12U | 10U | | |
| Bromoform | 12U | 12U | 11U | 12U | 10U | | |
| 4-Methyl-2-pentanone | 12U | 12U | 11U | 12U | 10U | | |
| 2-Hexanone | 12U | 12U | 11U | 12U | 10U | | |
| Tetrachloroethene | 12U | 12U | 11U | 12U | 10U | | |
| 1,1,2,2-Tetrachloroethane | 12U | 12U | 11U | 12U | 10U | | |
| Toluene | 12U | 12U | 11U | 12U | 10U | | |
| Chlorobenzene | 12U | 12U | 11U | 12U | 10U | | |
| Ethylbenzene | 12U | 12U | 11U | 12U | 10U | | |
| Styrene | 12U | 12U | 11U | 12U | 10U | | |
| Xylene (total) | 12U | 12U | 11U | 12U | 10U | | |
| Sample wt (g) : | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | | |
| %Moisture : | 20 | 15 | 9 | 15 | 1 | | |
| Dilution Factor: | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | | |
| Level: | LOW | LOW | LOW | LOW | LOW | | |
| Number of TIC's: | 0 | 0 | 1 | 0 | 0 | | |

Note: For the results listed in the Data Summary Table, ESAT has replaced the laboratory assigned flags with ESAT Organic Data Qualifiers. The ESAT flags indicate the technical usability of the reported results.

ORGANIC DATA SUMMARY

Case No.: 27273

SDG: FCX38

Reviewer: Mike Fertitta

Laboratory: SWOK

Matrix: Soil

Units: ug/Kg

| SEMIVOLATILES | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG |
|---------------------------|--------|--------|----------|--------|--------|----------|------|
| EPA SAMPLE NUMBER: | FC-X38 | FC-X39 | FC-X39RE | FC-X40 | FC-X41 | FC-X41DL | |
| Phenol | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| bis(2-Chloroethyl)ether | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| 2-Chlorophenol | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| 1,3-Dichlorobenzene | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| 1,4-Dichlorobenzene | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| 1,2-Dichlorobenzene | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| 2-Methylphenol | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| 2,2'-oxybis(1-chloropropa | 650U | 160 * | 330U | 330U | 420U | 850U * | |
| 4-Methylphenol | 650U | 330U * | 31QJK | 330U | 420U | 850U * | |
| N-Nitroso-di-n-propylamin | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| Hexachloroethane | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| Nitrobenzene | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| Isophorone | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| 2-Nitrophenol | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| 2,4-Dimethylphenol | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| bis(2-Chloroethoxy)methan | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| 2,4-Dichlorophenol | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| 1,2,4-Trichlorobenzene | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| Naphthalene | 650U | 18 * | 330U | 16QJK | 120QJK | 110 * | |
| 4-Chloroaniline | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| Hexachlorobutadiene | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| 4-Chloro-3-methylphenol | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| 2-Methylnaphthalene | 650U | 330U * | 330U | 330U | 41QJK | 46 * | |
| Hexachlorocyclopentadiene | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| 2,4,6-Trichlorophenol | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| 2,4,5-Trichlorophenol | 1600U | 830U * | 830U | 830U | 1100U | 2100U * | |
| 2-Chloronaphthalene | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| 2-Nitroaniline | 1600U | 830U * | 830U | 830U | 1100U | 2100U * | |
| Dimethylphthalate | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| Acenaphthylene | 650U | 36 * | 330U | 34QJK | 65QJK | 110 * | |
| 2,6-Dinitrotoluene | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| 3-Nitroaniline | 1600U | 830U * | 830U | 830U | 1100U | 2100U * | |
| Acenaphthene | 650U | 48 * | 36QJK | 43QJK | 340QJK | 330 * | |
| 2,4-Dinitrophenol | 1600U | 830U * | 830U | 830U | 1100U | 2100U * | |
| 4-Nitrophenol | 1600U | 830U * | 830U | 830U | 1100U | 2100U * | |
| Dibenzofuran | 650U | 20 * | 330U | 330U | 190QJK | 200 * | |
| 2,4-Dinitrotoluene | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| Diethylphthalate | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| 4-Chlorophenyl-phenylethe | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| Fluorene | 650U | 50 * | 29QJK | 33QJK | 320QJK | 370 * | |
| 4-Nitroaniline | 1600U | 830U * | 830U | 830U | 1100U | 2100U * | |
| 4,6-Dinitro-2-methylpheno | 1600U | 830U * | 830U | 830U | 1100U | 2100U * | |
| N-Nitrosodiphenylamine | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| 4-Bromophenyl-phenylether | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| Hexachlorobenzene | 650U | 330U * | 330U | 330U | 420U | 850U * | |

ORGANIC DATA SUMMARY

Case No.: 27273

SDG: FCX38

Reviewer: Mike Fertitta

Laboratory: SWOK

Matrix: Soil

Units: ug/Kg

| SEMIVOLATILES | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG |
|---------------------------|--------|--------|----------|--------|--------|----------|------|
| EPA SAMPLE NUMBER: | FC-X38 | FC-X39 | FC-X39RE | FC-X40 | FC-X41 | FC-X41DL | |
| Pentachlorophenol | 1600U | 830U * | 830U | 830U | 1100U | 2100U * | |
| Phenanthrene | 270QJK | 710 * | 410 JK | 480 | 3400 | 3200 * | |
| Anthracene | 71QJK | 130 * | 96QJK | 100QJK | 1000 | 960 * | |
| Carbazole | 60QJK | 120 * | 73QJK | 87QJK | 520 | 500 * | |
| Di-n-butylphthalate | 650U | 51 * | 330U | 330U | 420U | 110 * | |
| Fluoranthene | 580QJK | 1700 * | 1200 JK | 1500 | 6300 * | 6200D | |
| Pyrene | 380QJK | 1200 * | 1200 JK | 1100 | 4100 * | 4100D | |
| Butylbenzylphthalate | 650U | 330U * | 23QJK | 330U | 420U | 850U * | |
| 3,3'-Dichlorobenzidine | 650U | 330U * | 330U | 330U | 420U | 850U * | |
| Benzo(a)anthracene | 290QJK | 800 * | 670 JK | 760 | 2800 | 2700 * | |
| Chrysene | 330QJK | 880 * | 710 JK | 840 | 2800 | 2700 * | |
| bis(2-Ethylhexyl)phthalat | 800 B | 250 * | 330 U | 380U | 420U | 150 * | |
| Di-n-octylphthalate | 650U | 41 * | 330U | 17QJK | 37QJK | 850U * | |
| Benzo(b)fluoranthene | 280QJK | 1000 * | 700 JK | 950 | 2300 | 2400 * | |
| Benzo(k)fluoranthene | 280QJK | 510 * | 670 JK | 520 | 2100 | 2000 * | |
| Benzo(a)pyrene | 280QJK | 860 * | 700 JK | 860 | 2600 | 2600 * | |
| Indeno(1,2,3-cd)pyrene | 230QJK | 580 * | 500 JK | 580 | 1500 | 1500 * | |
| Dibenz(a,h)anthracene | 110QJK | 230 * | 220QJK | 270QJK | 780 | 780 * | |
| Benzo(g,h,i)perylene | 250QJK | 630 * | 570 JK | 630 | 1500 | 1500 * | |
| Sample wt (g) : | 31.2 | 32.4 | 32.2 | 33.4 | 31.5 | 31.5 | |
| %Moisture : | 2 | 2 | 2 | 2 | 26 | 26 | |
| Dilution Factor: | 2.0 | 1.0 | 1.0 | 1.0 | 1.0 | 2.0 | |
| Level: | LOW | LOW | LOW | LOW | LOW | LOW | |
| Number of TIC's: | 30 | 30 | 29 | 30 | 30 | 30 | |

Note: For the results listed in the Data Summary Table, ESAT has replaced the laboratory assigned flags with ESAT Organic Data Qualifiers. The ESAT flags indicate the technical usability of the reported results.

ORGANIC DATA SUMMARY

Case No.: 27273

SDG: FCX38

Reviewer: Mike Fertitta

Laboratory: SWOK

Matrix: Soil

Units: ug/Kg

| SEMIVOLATILES | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG |
|---------------------------|--------|----------|--------|--------|--------|--------|--------|
| EPA SAMPLE NUMBER: | FC-X42 | FC-X42DL | FC-X43 | FC-X44 | FC-X45 | FC-X46 | FC-X47 |
| Phenol | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| bis(2-Chloroethyl)ether | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| 2-Chlorophenol | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| 1,3-Dichlorobenzene | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| 1,4-Dichlorobenzene | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| 1,2-Dichlorobenzene | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| 2-Methylphenol | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| 2,2'-oxybis(1-chloropropa | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| 4-Methylphenol | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| N-Nitroso-di-n-propylamin | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| Hexachloroethane | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| Nitrobenzene | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| Isophorone | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| 2-Nitrophenol | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| 2,4-Dimethylphenol | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| bis(2-Chloroethoxy)methan | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| 2,4-Dichlorophenol | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| 1,2,4-Trichlorobenzene | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| Naphthalene | 330QJK | 310 * | 480U | 490U | 360U | 350U | 450U |
| 4-Chloroaniline | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| Hexachlorobutadiene | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| 4-Chloro-3-methylphenol | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| 2-Methylnaphthalene | 110QJK | 100 * | 480U | 490U | 360U | 350U | 450U |
| Hexachlorocyclopentadiene | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| 2,4,6-Trichlorophenol | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| 2,4,5-Trichlorophenol | 2000U | 4000U * | 1200U | 1200U | 900U | 880U | 1100U |
| 2-Chloronaphthalene | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| 2-Nitroaniline | 2000U | 4000U * | 1200U | 1200U | 900U | 880U | 1100U |
| Dimethylphthalate | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| Acenaphthylene | 800U | 100 * | 52QJK | 490U | 360U | 350U | 450U |
| 2,6-Dinitrotoluene | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| 3-Nitroaniline | 2000U | 4000U * | 1200U | 1200U | 900U | 880U | 1100U |
| Acenaphthene | 610QJK | 620 * | 62QJK | 490U | 360U | 350U | 450U |
| 2,4-Dinitrophenol | 2000U | 4000U * | 1200U | 1200U | 900U | 880U | 1100U |
| 4-Nitrophenol | 2000U | 4000U * | 1200U | 1200U | 900U | 880U | 1100U |
| Dibenzofuran | 360QJK | 380 * | 31QJK | 490U | 360U | 350U | 450U |
| 2,4-Dinitrotoluene | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| Diethylphthalate | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| 4-Chlorophenyl-phenylethe | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| Fluorene | 480QJK | 490 * | 51QJK | 490U | 360U | 350U | 450U |
| 4-Nitroaniline | 2000U | 4000U * | 1200U | 1200U | 900U | 880U | 1100U |
| 4,6-Dinitro-2-methylpheno | 2000U | 4000U * | 1200U | 1200U | 900U | 880U | 1100U |
| N-Nitrosodiphenylamine | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| 4-Bromophenyl-phenylether | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| Hexachlorobenzene | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |

ORGANIC DATA SUMMARY

Case No.: 27273

SDG: FCX38

Reviewer: Mike Fertitta

Laboratory: SWOK

Matrix: Soil

Units: ug/Kg

| SEMIVOLATILES | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG |
|---------------------------|--------|----------|--------|--------|--------|--------|--------|
| EPA SAMPLE NUMBER: | FC-X42 | FC-X42DL | FC-X43 | FC-X44 | FC-X45 | FC-X46 | FC-X47 |
| Pentachlorophenol | 2000U | 4000U * | 1200U | 1200U | 900U | 880U | 1100U |
| Phenanthrene | 5400 | 5500 * | 870 | 490U | 21QJK | 59QJK | 27QJK |
| Anthracene | 1400 | 1400 * | 160QJK | 490U | 360U | 350U | 450U |
| Carbazole | 820 | 860 * | 130QJK | 490U | 360U | 19QJK | 450U |
| Di-n-butylphthalate | 800U | 110 * | 480U | 490U | 360U | 350U | 450U |
| Fluoranthene | 9400 * | 10000D | 2000 | 490U | 32QJK | 280QJK | 66QJK |
| Pyrene | 6500 * | 6400D | 1400 | 490U | 27QJK | 240QJK | 54QJK |
| Butylbenzylphthalate | 220QJK | 1600U * | 480U | 490U | 360U | 350U | 450U |
| 3,3'-Dichlorobenzidine | 800U | 1600U * | 480U | 490U | 360U | 350U | 450U |
| Benzo(a)anthracene | 4900 | 4800 * | 810 | 490U | 22QJK | 130QJK | 33QJK |
| Chrysene | 5000 | 5100 * | 970 | 490U | 21QJK | 150QJK | 53QJK |
| bis(2-Ethylhexyl)phthalat | 800U | 350 * | 480U | 490U | 360U | 350U | 450U |
| Di-n-octylphthalate | 44QJK | 1600U * | 480U | 490U | 360U | 350U | 450U |
| Benzo(b)fluoranthene | 4800 | 4600 * | 920 | 490U | 360U | 130QJK | 65QJK |
| Benzo(k)fluoranthene | 2700 | 3200 * | 620 | 490U | 360U | 180QJK | 25QJK |
| Benzo(a)pyrene | 4400 | 4500 * | 850 | 490U | 22QJK | 130QJK | 42QJK |
| Indeno(1,2,3-cd)pyrene | 2600 | 2700 * | 530 | 490U | 360U | 86QJK | 47QJK |
| Dibenz(a,h)anthracene | 1400 | 1200 * | 210QJK | 490U | 360U | 46QJK | 450U |
| Benzo(g,h,i)perylene | 2600 | 2600 * | 580 | 490U | 22QJK | 97QJK | 52QJK |
| Sample wt (g) : | 30.9 | 30.9 | 31.1 | 32.5 | 32.9 | 33.6 | 32.0 |
| %Moisture : | 20 | 20 | 33 | 38 | 16 | 16 | 32 |
| Dilution Factor: | 2.0 | 4.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 |
| Level: | LOW | LOW | LOW | LOW | LOW | LOW | LOW |
| Number of TIC's: | 30 | 30 | 30 | 30 | 30 | 30 | 28 |

Note: For the results listed in the Data Summary Table, ESAT has replaced the laboratory assigned flags with ESAT Organic Data Qualifiers. The ESAT flags indicate the technical usability of the reported results.

ORGANIC DATA SUMMARY

Case No.: 27273

SDG: FCX38

Reviewer: Mike Fertitta

Laboratory: SWOK

Matrix: Soil

Units: ug/Kg

| SEMIVOLATILES | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG |
|----------------------------|--------|--------|--------|----------|--------|--------|--------|
| EPA SAMPLE NUMBER: | FC-X48 | FC-X49 | FC-X50 | FC-X50RE | FC-X51 | FC-X52 | FC-X53 |
| Phenol | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| bis(2-Chloroethyl) ether | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| 2-Chlorophenol | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| 1,3-Dichlorobenzene | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| 1,4-Dichlorobenzene | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| 1,2-Dichlorobenzene | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| 2-Methylphenol | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| 2,2'-oxybis(1-chloropropa | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| 4-Methylphenol | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| N-Nitroso-di-n-propylamin | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| Hexachloroethane | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| Nitrobenzene | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| Isophorone | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| 2-Nitrophenol | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| 2,4-Dimethylphenol | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| bis(2-Chloroethoxy) methan | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| 2,4-Dichlorophenol | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| 1,2,4-Trichlorobenzene | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| Naphthalene | 400U | 380U | 370U * | 63QJK | 1100U | 390U | 370U |
| 4-Chloroaniline | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| Hexachlorobutadiene | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| 4-Chloro-3-methylphenol | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| 2-Methylnaphthalene | 400U | 380U | 370U * | 54QJK | 1100U | 390U | 370U |
| Hexachlorocyclopentadiene | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| 2,4,6-Trichlorophenol | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| 2,4,5-Trichlorophenol | 990U | 960U | 940U * | 920U | 2700U | 980U | 940U |
| 2-Chloronaphthalene | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| 2-Nitroaniline | 990U | 960U | 940U * | 920U | 2700U | 980U | 940U |
| Dimethylphthalate | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| Acenaphthylene | 400U | 380U | 370U * | 71QJK | 1100U | 390U | 370U |
| 2,6-Dinitrotoluene | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| 3-Nitroaniline | 990U | 960U | 940U * | 920U | 2700U | 980U | 940U |
| Acenaphthene | 400U | 380U | 370U * | 180QJK | 70QJK | 390U | 370U |
| 2,4-Dinitrophenol | 990U | 960U | 940U * | 920U | 2700U | 980U | 940U |
| 4-Nitrophenol | 990U | 960U | 940U * | 920U | 2700U | 980U | 940U |
| Dibenzofuran | 400U | 380U | 370U * | 120QJK | 1100U | 390U | 370U |
| 2,4-Dinitrotoluene | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| Diethylphthalate | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| 4-Chlorophenyl-phenylethe | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| Fluorene | 400U | 380U | 370U * | 160QJK | 110QJK | 390U | 370U |
| 4-Nitroaniline | 990U | 960U | 940U * | 920U | 2700U | 980U | 940U |
| 4,6-Dinitro-2-methylpheno | 990U | 960U | 940U * | 920U | 2700U | 980U | 940U |
| N-Nitrosodiphenylamine | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| 4-Bromophenyl-phenylether | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| Hexachlorobenzene | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |

ORGANIC DATA SUMMARY

Case No.: 27273

SDG: FCX38

Reviewer: Mike Fertitta

Laboratory: SWOK

Matrix: Soil

Units: ug/Kg

| SEMIVOLATILES | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG |
|---------------------------|--------|--------|--------|----------|--------|--------|--------|
| EPA SAMPLE NUMBER: | FC-X48 | FC-X49 | FC-X50 | FC-X50RE | FC-X51 | FC-X52 | FC-X53 |
| Pentachlorophenol | 990U | 960U | 940U * | 920U | 2700U | 980U | 940U |
| Phenanthrene | 150QJK | 270QJK | 130 * | 2200JK | 440QJK | 390U | 370U |
| Anthracene | 22QJK | 62QJK | 33 * | 520JK | 130QJK | 390U | 370U |
| Carbazole | 34QJK | 57QJK | 29 * | 290QJK | 1100U | 390U | 370U |
| Di-n-butylphthalate | 400U | 380U | 59 * | 20QJK | 1100U | 390U | 370U |
| Fluoranthene | 460 | 850 | 380 * | 3000JK | 450QJK | 390U | 370U |
| Pyrene | 420 | 770 | 320 * | 3000JK | 580QJK | 28QJK | 370U |
| Butylbenzylphthalate | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| 3,3'-Dichlorobenzidine | 400U | 380U | 370U * | 370U | 1100U | 390U | 370U |
| Benzo(a)anthracene | 160QJK | 340QJK | 220 * | 1500JK | 260QJK | 390U | 370U |
| Chrysene | 230QJK | 390 | 280 * | 1600JK | 250QJK | 390U | 370U |
| bis(2-Ethylhexyl)phthalat | 400U | 380U | 170 * | 370U | 1100U | 390U | 370U |
| Di-n-octylphthalate | 27QJK | 21QJK | 370U * | 370U | 1100U | 390U | 370U |
| Benzo(b)fluoranthene | 240QJK | 320QJK | 260 * | 1400JK | 180QJK | 390U | 370U |
| Benzo(k)fluoranthene | 240QJK | 390 | 140 * | 1000JK | 210QJK | 390U | 370U |
| Benzo(a)pyrene | 200QJK | 320QJK | 210 * | 1300JK | 220QJK | 390U | 370U |
| Indeno(1,2,3-cd)pyrene | 150QJK | 240QJK | 160 * | 820JK | 130QJK | 390U | 370U |
| Dibenz(a,h)anthracene | 63QJK | 110QJK | 62 * | 400JK | 73QJK | 390U | 370U |
| Benzo(g,h,i)perylene | 170QJK | 250QJK | 160 * | 890JK | 150QJK | 390U | 370U |
| Sample wt (g) : | 32.1 | 31.4 | 31.9 | 32.4 | 31.4 | 31.8 | 31.2 |
| %Moisture : | 22 | 17 | 17 | 17 | 42 | 20 | 15 |
| Dilution Factor: | 1.0 | 1.0 | 1.0 | 1.0 | 2.0 | 1.0 | 1.0 |
| Level: | LOW | LOW | LOW | LOW | LOW | LOW | LOW |
| Number of TIC's: | 30 | 30 | 30 | 30 | 30 | 30 | 30 |

Note: For the results listed in the Data Summary Table, ESAT has replaced the laboratory assigned flags with ESAT Organic Data Qualifiers. The ESAT flags indicate the technical usability of the reported results.

ORGANIC DATA SUMMARY

Case No.: 27273

SDG: FCX38

Reviewer: Mike Fertitta

Laboratory: SWOK

Matrix: Soil

Units: ug/Kg

| SEMIVOLATILES | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG |
|---------------------------|--------|--------|--------|------|------|------|------|
| EPA SAMPLE NUMBER: | FC-X54 | FC-X55 | FC-X56 | | | | |
| Phenol | 330U | 370U | 330U | | | | |
| bis(2-Chloroethyl) ether | 330U | 370U | 330U | | | | |
| 2-Chlorophenol | 330U | 370U | 330U | | | | |
| 1,3-Dichlorobenzene | 330U | 370U | 330U | | | | |
| 1,4-Dichlorobenzene | 330U | 370U | 330U | | | | |
| 1,2-Dichlorobenzene | 330U | 370U | 330U | | | | |
| 2-Methylphenol | 330U | 370U | 330U | | | | |
| 2,2'-oxybis(1-chloropropa | 330U | 370U | 330U | | | | |
| 4-Methylphenol | 330U | 370U | 330U | | | | |
| N-Nitroso-di-n-propylamin | 330U | 370U | 330U | | | | |
| Hexachloroethane | 330U | 370U | 330U | | | | |
| Nitrobenzene | 330U | 370U | 330U | | | | |
| Isophorone | 330U | 370U | 330U | | | | |
| 2-Nitrophenol | 330U | 370U | 330U | | | | |
| 2,4-Dimethylphenol | 330U | 370U | 330U | | | | |
| bis(2-Chloroethoxy)methan | 330U | 370U | 330U | | | | |
| 2,4-Dichlorophenol | 330U | 370U | 330U | | | | |
| 1,2,4-Trichlorobenzene | 330U | 370U | 330U | | | | |
| Naphthalene | 330U | 370U | 330U | | | | |
| 4-Chloroaniline | 330U | 370U | 330U | | | | |
| Hexachlorobutadiene | 330U | 370U | 330U | | | | |
| 4-Chloro-3-methylphenol | 330U | 370U | 330U | | | | |
| 2-Methylnaphthalene | 330U | 370U | 330U | | | | |
| Hexachlorocyclopentadiene | 330U | 370U | 330U | | | | |
| 2,4,6-Trichlorophenol | 330U | 370U | 330U | | | | |
| 2,4,5-Trichlorophenol | 830U | 930U | 830U | | | | |
| 2-Chloronaphthalene | 330U | 370U | 330U | | | | |
| 2-Nitroaniline | 830U | 930U | 830U | | | | |
| Dimethylphthalate | 330U | 370U | 330U | | | | |
| Acenaphthylene | 330U | 370U | 330U | | | | |
| 2,6-Dinitrotoluene | 330U | 370U | 330U | | | | |
| 3-Nitroaniline | 830U | 930U | 830U | | | | |
| Acenaphthene | 330U | 370U | 330U | | | | |
| 2,4-Dinitrophenol | 830U | 930U | 830U | | | | |
| 4-Nitrophenol | 830U | 930U | 830U | | | | |
| Dibenzofuran | 330U | 370U | 330U | | | | |
| 2,4-Dinitrotoluene | 330U | 370U | 330U | | | | |
| Diethylphthalate | 330U | 19QJK | 330U | | | | |
| 4-Chlorophenyl-phenylethe | 330U | 370U | 330U | | | | |
| Fluorene | 330U | 370U | 330U | | | | |
| 4-Nitroaniline | 830U | 930U | 830U | | | | |
| 4,6-Dinitro-2-methylpheno | 830U | 930U | 830U | | | | |
| N-Nitrosodiphenylamine | 330U | 370U | 330U | | | | |
| 4-Bromophenyl-phenylether | 330U | 370U | 330U | | | | |
| Hexachlorobenzene | 330U | 370U | 330U | | | | |

ORGANIC DATA SUMMARY

Case No.: 27273

SDG: FCX38

Reviewer: Mike Fertitta

Laboratory: SWOK

Matrix: Soil

Units: ug/Kg

| SEMIVOLATILES | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG |
|---------------------------|--------|--------|--------|------|------|------|------|
| EPA SAMPLE NUMBER: | FC-X54 | FC-X55 | FC-X56 | | | | |
| Pentachlorophenol | 830U | 930U | 830U | | | | |
| Phenanthrene | 99QJK | 42QJK | 120QJK | | | | |
| Anthracene | 18QJK | 370U | 24QJK | | | | |
| Carbazole | 330U | 370U | 30QJK | | | | |
| Di-n-butylphthalate | 330U | 370U | 330U | | | | |
| Fluoranthene | 150QJK | 65QJK | 280QJK | | | | |
| Pyrene | 230QJK | 98QJK | 250QJK | | | | |
| Butylbenzylphthalate | 330U | 370U | 140QJK | | | | |
| 3,3'-Dichlorobenzidine | 330U | 370U | 330U | | | | |
| Benzo(a)anthracene | 100QJK | 48QJK | 160QJK | | | | |
| Chrysene | 120QJK | 66QJK | 210QJK | | | | |
| bis(2-Ethylhexyl)phthalat | 330U | 370U | 330U | | | | |
| Di-n-octylphthalate | 330U | 370U | 330U | | | | |
| Benzo(b)fluoranthene | 120QJK | 59QJK | 220QJK | | | | |
| Benzo(k)fluoranthene | 110QJK | 73QJK | 140QJK | | | | |
| Benzo(a)pyrene | 110QJK | 53QJK | 180QJK | | | | |
| Indeno(1,2,3-cd)pyrene | 64QJK | 43QJK | 170QJK | | | | |
| Dibenz(a,h)anthracene | 330U | 19QJK | 76QJK | | | | |
| Benzo(g,h,i)perylene | 72QJK | 50QJK | 380 | | | | |
| Sample wt (g) : | 33.5 | 31.4 | 33.1 | | | | |
| %Moisture : | 9 | 15 | 1 | | | | |
| Dilution Factor: | 1.0 | 1.0 | 1.0 | | | | |
| Level: | LOW | LOW | LOW | | | | |
| Number of TIC's: | 30 | 30 | 30 | | | | |

Note: For the results listed in the Data Summary Table, ESAT has replaced the laboratory assigned flags with ESAT Organic Data Qualifiers. The ESAT flags indicate the technical usability of the reported results.

ORGANIC DATA SUMMARY

Case No.: 27273

SDG: FCX38

Reviewer: Gene Zhu

Laboratory: SWOK

Matrix: Soil

Units: ug/Kg

| PESTICIDES/PCBs | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG |
|---------------------|---------|----------|---------|----------|---------|----------|---------|
| EPA SAMPLE NUMBER: | FC-X38 | FC-X38DL | FC-X39 | FC-X39DL | FC-X40 | FC-X40DL | FC-X41 |
| alpha-BHC | 17U * | 170U | 16U * | 160U | 17U * | 170U | 22U * |
| beta-BHC | 17U * | 170U | 16U * | 160U | 17U * | 170U | 22U * |
| delta-BHC | 17U * | 170U | 16U * | 160U | 17U * | 170U | 22U * |
| gamma-BHC (Lindane) | 17U * | 170U | 16U * | 160U | 17U * | 170U | 22U * |
| Heptachlor | 3.2 * | 170U | 16U * | 160U | 17U * | 170U | 22U * |
| Aldrin | 17U * | 170U | 16U * | 160U | 17U * | 170U | 22U * |
| Heptachlor Epoxide | 17U * | 170U | 16U * | 160U | 17U * | 170U | 22U * |
| Endosulfan I | 17U * | 170U | 16U * | 160U | 17U * | 170U | 22U * |
| Dieldrin | 16 * | 330U | 30U * | 300U | 33U * | 330U | 120 * |
| 4,4'-DDE | 33U * | 330U | 30U * | 300U | 33U * | 330U | 44U * |
| Endrin | 33U * | 330U | 30U * | 300U | 33U * | 330U | 44U * |
| Endosulfan II | 33U * | 330U | 30U * | 300U | 33U * | 330U | 44U * |
| 4,4'-DDD | 33U * | 330U | 30U * | 300U | 33U * | 330U | 8.4 * |
| Endosulfan Sulfate | 33U * | 330U | 30U * | 300U | 13 * | 330U | 44U * |
| 4,4'-DDT | 25 * | 330U | 30U * | 300U | 33U * | 330U | 25 * |
| Methoxychlor | 170U * | 1700U | 160U * | 1600U | 170U * | 1700U | 49U * |
| Endrin Ketone | 33U * | 330U | 21 * | 300U | 17 * | 330U | 38 * |
| Endrin Aldehyde | 8.0 * | 330U | 30U * | 300U | 33U * | 330U | 5.4 * |
| alpha-Chlordane | 19 * | 170U | 16U * | 160U | 17U * | 170U | 22 * |
| gamma-Chlordane | 24 * | 170U | 16U * | 160U | 17U * | 170U | 24 * |
| Toxaphene | 1700U * | 17000U | 1600U * | 16000U | 1700U * | 17000U | 2200U * |
| Aroclor-1016 | 330U * | 3300U | 300U * | 3000U | 330U * | 3300U | 440U * |
| Aroclor-1221 | 670U * | 6700U | 620U * | 6200U | 670U * | 6700U | 890U * |
| Aroclor-1232 | 330U * | 3300U | 300U * | 3000U | 330U * | 3300U | 440U * |
| Aroclor-1242 | 330U * | 3300U | 300U * | 3000U | 330U * | 3300U | 440U * |
| Aroclor-1248 | 330U * | 3300U | 300U * | 3000U | 330U * | 3300U | 440U * |
| Aroclor-1254 | 330U * | 3300U | 300U * | 3000U | 330U * | 3300U | 440U * |
| Aroclor-1260 | 330U * | 3300U | 300U * | 3000U | 330U * | 3300U | 440U * |
| Sample wt (g) : | 30.7 | 30.7 | 33.2 | 33.2 | 30.6 | 30.6 | 30.6 |
| %Moisture : | 2 | 2 | 2 | 2 | 2 | 2 | 26 |
| Dilution Factor: | 10.0 | 100.0 | 10.0 | 100.0 | 10.0 | 100.0 | 10.0 |

Note: For the results listed in the Data Summary Table, ESAT has replaced the laboratory assigned flags with ESAT Organic Data Qualifiers. The ESAT flags indicate the technical usability of the reported results.

ORGANIC DATA SUMMARY

Case No.: 27273

SDG: FCX38

Reviewer: Gene Zhu

Laboratory: SWOK

Matrix: Soil

Units: ug/Kg

| PESTICIDES/PCBs | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG |
|---------------------|----------|---------|----------|---------|----------|---------|----------|
| EPA SAMPLE NUMBER: | FC-X41DL | FC-X42 | FC-X42DL | FC-X43 | FC-X43DL | FC-X44 | FC-X44DL |
| alpha-BHC | 220U | 19U * | 190U | 24U * | 240U | 26U * | 260U |
| beta-BHC | 220U | 19U * | 190U | 24U * | 240U | 26U * | 260U |
| delta-BHC | 220U | 19U * | 190U | 24U * | 240U | 26U * | 260U |
| gamma-BHC (Lindane) | 220U | 19U * | 190U | 24U * | 240U | 26U * | 260U |
| Heptachlor | 220U | 19U * | 190U | 24U * | 240U | 26U * | 260U |
| Aldrin | 220U | 19U * | 190U | 24U * | 240U | 26U * | 260U |
| Heptachlor Epoxide | 220U | 19U * | 190U | 24U * | 240U | 26U * | 260U |
| Endosulfan I | 220U | 19U * | 190U | 24U * | 240U | 26U * | 260U |
| Dieldrin | 150QJK | 850 * | 940 | 160 * | 200QJK | 51U * | 510U |
| 4,4'-DDE | 440U | 37U * | 370U | 21 * | 460U | 51U * | 510U |
| Endrin | 440U | 37U * | 370U | 46U * | 460U | 51U * | 510U |
| Endosulfan II | 440U | 37U * | 370U | 46U * | 460U | 51U * | 510U |
| 4,4'-DDD | 440U | 37U * | 370U | 46U * | 460U | 51U * | 510U |
| Endosulfan Sulfate | 440U | 37U * | 370U | 46U * | 460U | 51U * | 510U |
| 4,4'-DDT | 440U | 37U * | 370U | 29 * | 120JQ | 51U * | 510U |
| Methoxychlor | 2200U | 190U * | 1900U | 240U * | 2400U | 260U * | 2600U |
| Endrin Ketone | 440U | 54 * | 37QJK | 46U * | 460U | 51U * | 510U |
| Endrin Aldehyde | 440U | 37U * | 370U | 46U * | 460U | 51U * | 510U |
| alpha-Chlordane | 220U | 36 * | 94QJK | 120 * | 130JQ | 26U * | 260U |
| gamma-Chlordane | 220U | 38 * | 73QJK | 120 * | 150JQ | 26U * | 260U |
| Toxaphene | 22000U | 1900U * | 19000U | 2400U * | 24000U | 2600U * | 26000U |
| Aroclor-1016 | 4400U | 370U * | 3700U | 460U * | 4600U | 510U * | 5100U |
| Aroclor-1221 | 8900U | 750U * | 7500U | 930U * | 9300U | 1000U * | 10000U |
| Aroclor-1232 | 4400U | 370U * | 3700U | 460U * | 4600U | 510U * | 5100U |
| Aroclor-1242 | 4400U | 370U * | 3700U | 460U * | 4600U | 510U * | 5100U |
| Aroclor-1248 | 4400U | 370U * | 3700U | 460U * | 4600U | 510U * | 5100U |
| Aroclor-1254 | 4400U | 370U * | 3700U | 460U * | 4600U | 510U * | 5100U |
| Aroclor-1260 | 4400U | 370U * | 3700U | 460U * | 4600U | 510U * | 5100U |
| Sample wt (g) : | 30.6 | 33.4 | 33.4 | 32.1 | 32.1 | 31.4 | 31.4 |
| %Moisture : | 26 | 20 | 20 | 33 | 33 | 38 | 38 |
| Dilution Factor: | 100.0 | 10.0 | 100.0 | 10.0 | 100.0 | 10.0 | 100.0 |

Note: For the results listed in the Data Summary Table, ESAT has replaced the laboratory assigned flags with ESAT Organic Data Qualifiers. The ESAT flags indicate the technical usability of the reported results.

ORGANIC DATA SUMMARY

Case No.: 27273

SDG: FCX38

Reviewer: Gene Zhu

Laboratory: SWOK

Matrix: Soil

Units: ug/Kg

| PESTICIDES/PCBs | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG |
|---------------------|---------|----------|---------|----------|---------|----------|---------|
| EPA SAMPLE NUMBER: | FC-X45 | FC-X45DL | FC-X46 | FC-X46DL | FC-X47 | FC-X47DL | FC-X48 |
| alpha-BHC | 19U * | 190U | 18U * | 180U | 24U * | 240U | 20U * |
| beta-BHC | 19U * | 190U | 18U * | 180U | 24U * | 240U | 20U * |
| delta-BHC | 19U * | 190U | 18U * | 180U | 24U * | 240U | 20U * |
| gamma-BHC (Lindane) | 19U * | 190U | 18U * | 180U | 24U * | 240U | 20U * |
| Heptachlor | 19U * | 190U | 18U * | 180U | 24U * | 240U | 20U * |
| Aldrin | 19U * | 190U | 18U * | 180U | 24U * | 240U | 20U * |
| Heptachlor Epoxide | 19U * | 190U | 18U * | 180U | 24U * | 240U | 20U * |
| Endosulfan I | 19U * | 190U | 18U * | 180U | 24U * | 240U | 20U * |
| Dieldrin | 36U * | 360U | 35U * | 350U | 46U * | 460U | 39U * |
| 4,4'-DDE | 36U * | 360U | 35U * | 350U | 46U * | 460U | 39U * |
| Endrin | 36U * | 360U | 35U * | 350U | 46U * | 460U | 39U * |
| Endosulfan II | 36U * | 360U | 35U * | 350U | 46U * | 460U | 39U * |
| 4,4'-DDD | 36U * | 360U | 35U * | 350U | 46U * | 460U | 39U * |
| Endosulfan Sulfate | 36U * | 360U | 35U * | 350U | 46U * | 460U | 39U * |
| 4,4'-DDT | 36U * | 360U | 35U * | 350U | 46U * | 460U | 39U * |
| Methoxychlor | 190U * | 1900U | 180U * | 1800U | 240U * | 2400U | 200U * |
| Endrin Ketone | 36U * | 360U | 35U * | 350U | 46U * | 460U | 39U * |
| Endrin Aldehyde | 36U * | 360U | 35U * | 350U | 46U * | 460U | 5.0 * |
| alpha-Chlordane | 19U * | 190U | 18U * | 180U | 24U * | 240U | 20U * |
| gamma-Chlordane | 19U * | 190U | 18U * | 180U | 24U * | 240U | 20U * |
| Toxaphene | 1900U * | 19000U | 1800U * | 18000U | 2400U * | 24000U | 2000U * |
| Aroclor-1016 | 360U * | 3600U | 350U * | 3500U | 460U * | 4600U | 390U * |
| Aroclor-1221 | 740U * | 7400U | 720U * | 7200U | 930U * | 9300U | 800U * |
| Aroclor-1232 | 360U * | 3600U | 350U * | 3500U | 460U * | 4600U | 390U * |
| Aroclor-1242 | 360U * | 3600U | 350U * | 3500U | 460U * | 4600U | 390U * |
| Aroclor-1248 | 360U * | 3600U | 350U * | 3500U | 460U * | 4600U | 390U * |
| Aroclor-1254 | 360U * | 3600U | 350U * | 3500U | 460U * | 4600U | 390U * |
| Aroclor-1260 | 360U * | 3600U | 350U * | 3500U | 460U * | 4600U | 390U * |
| Sample wt (g) : | 32.4 | 32.4 | 33.2 | 33.2 | 31.9 | 31.9 | 32.2 |
| %Moisture : | 16 | 16 | 16 | 16 | 32 | 32 | 22 |
| Dilution Factor: | 10.0 | 100.0 | 10.0 | 100.0 | 10.0 | 100.0 | 10.0 |

Note: For the results listed in the Data Summary Table, ESAT has replaced the laboratory assigned flags with ESAT Organic Data Qualifiers. The ESAT flags indicate the technical usability of the reported results.

ORGANIC DATA SUMMARY

Case No.: 27273

SDG: FCX38

Reviewer: Gene Zhu

Laboratory: SWOK

Matrix: Soil

Units: ug/Kg

| PESTICIDES/PCBs | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG |
|---------------------|----------|---------|----------|---------|----------|---------|----------|
| EPA SAMPLE NUMBER: | FC-X48DL | FC-X49 | FC-X49DL | FC-X50 | FC-X50DL | FC-X51 | FC-X51DL |
| alpha-BHC | 200U | 19U * | 190U | 19U * | 190U | 29U * | 290U |
| beta-BHC | 200U | 19U * | 190U | 19U * | 190U | 29U * | 290U |
| delta-BHC | 200U | 19U * | 190U | 19U * | 190U | 29U * | 290U |
| gamma-BHC (Lindane) | 200U | 19U * | 190U | 19U * | 190U | 29U * | 290U |
| Heptachlor | 200U | 19U * | 190U | 19U * | 190U | 29U * | 290U |
| Aldrin | 200U | 19U * | 190U | 19U * | 190U | 29U * | 290U |
| Heptachlor Epoxide | 200U | 19U * | 190U | 19U * | 190U | 29U * | 290U |
| Endosulfan I | 200U | 19U * | 190U | 19U * | 190U | 29U * | 290U |
| Dieldrin | 390U | 38U * | 380U | 38U * | 380U | 56U * | 560U |
| 4,4'-DDE | 390U | 38U * | 380U | 38U * | 380U | 56U * | 560U |
| Endrin | 390U | 38U * | 380U | 38U * | 380U | 56U * | 560U |
| Endosulfan II | 390U | 38U * | 380U | 38U * | 380U | 56U * | 560U |
| 4,4'-DDD | 390U | 38U * | 380U | 38U * | 380U | 56U * | 560U |
| Endosulfan Sulfate | 390U | 38U * | 380U | 38U * | 380U | 56U * | 560U |
| 4,4'-DDT | 390U | 4.1 * | 380U | 38U * | 380U | 56U * | 560U |
| Methoxychlor | 2000U | 190U * | 1900U | 190U * | 1900U | 290U * | 2900U |
| Endrin Ketone | 390U | 38U * | 380U | 38U * | 380U | 6.6 * | 560U |
| Endrin Aldehyde | 390U | 38U * | 380U | 38U * | 380U | 56U * | 560U |
| alpha-Chlordane | 200U | 19U * | 190U | 19U * | 190U | 29U * | 290U |
| gamma-Chlordane | 200U | 19U * | 190U | 19U * | 190U | 29U * | 290U |
| Toxaphene | 20000U | 1900U * | 19000U | 1900U * | 19000U | 2900U * | 29000U |
| Aroclor-1016 | 3900U | 380U * | 3800U | 380U * | 3800U | 560U * | 5600U |
| Aroclor-1221 | 8000U | 760U * | 7600U | 760U * | 7600U | 1100U * | 11000U |
| Aroclor-1232 | 3900U | 380U * | 3800U | 380U * | 3800U | 560U * | 5600U |
| Aroclor-1242 | 3900U | 380U * | 3800U | 380U * | 3800U | 560U * | 5600U |
| Aroclor-1248 | 3900U | 380U * | 3800U | 380U * | 3800U | 560U * | 5600U |
| Aroclor-1254 | 3900U | 380U * | 3800U | 380U * | 3800U | 560U * | 5600U |
| Aroclor-1260 | 3900U | 380U * | 3800U | 380U * | 3800U | 560U * | 5600U |
| Sample wt (g) : | 32.2 | 31.7 | 31.7 | 31.7 | 31.7 | 30.2 | 30.2 |
| %Moisture : | 22 | 17 | 17 | 17 | 17 | 42 | 42 |
| Dilution Factor: | 100.0 | 10.0 | 100.0 | 10.0 | 100.0 | 10.0 | 100.0 |

Note: For the results listed in the Data Summary Table, ESAT has replaced the laboratory assigned flags with ESAT Organic Data Qualifiers. The ESAT flags indicate the technical usability of the reported results.

ORGANIC DATA SUMMARY

Case No.: 27273

SDG: FCX38

Reviewer: Gene Zhu

Laboratory: SWOK

Matrix: Soil

Units: ug/Kg

| PESTICIDES/PCBs | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG |
|---------------------|---------|----------|---------|----------|---------|----------|---------|
| EPA SAMPLE NUMBER: | FC-X52 | FC-X52DL | FC-X53 | FC-X53DL | FC-X54 | FC-X54DL | FC-X55 |
| alpha-BHC | 20U * | 200U | 20U * | 200U | 18U * | 180U | 18U * |
| beta-BHC | 20U * | 200U | 20U * | 200U | 18U * | 180U | 18U * |
| delta-BHC | 20U * | 200U | 20U * | 200U | 18U * | 180U | 18U * |
| gamma-BHC (Lindane) | 20U * | 200U | 20U * | 200U | 18U * | 180U | 18U * |
| Heptachlor | 20U * | 200U | 20U * | 200U | 18U * | 180U | 18U * |
| Aldrin | 20U * | 200U | 20U * | 200U | 18U * | 180U | 18U * |
| Heptachlor Epoxide | 20U * | 200U | 20U * | 200U | 18U * | 180U | 18U * |
| Endosulfan I | 20U * | 200U | 20U * | 200U | 18U * | 180U | 18U * |
| Dieldrin | 40U * | 400U | 38U * | 380U | 8.6 * | 340U | 36U * |
| 4,4'-DDE | 40U * | 400U | 38U * | 380U | 34U * | 340U | 36U * |
| Endrin | 40U * | 400U | 38U * | 380U | 34U * | 340U | 36U * |
| Endosulfan II | 40U * | 400U | 38U * | 380U | 34U * | 340U | 36U * |
| 4,4'-DDD | 40U * | 400U | 38U * | 380U | 34U * | 340U | 36U * |
| Endosulfan Sulfate | 40U * | 400U | 38U * | 380U | 34U * | 340U | 36U * |
| 4,4'-DDT | 15 * | 400U | 38U * | 380U | 34U * | 340U | 36U * |
| Methoxychlor | 200U * | 2000U | 200U * | 2000U | 180U * | 1800U | 180U * |
| Endrin Ketone | 40U * | 400U | 38U * | 380U | 34U * | 340U | 36U * |
| Endrin Aldehyde | 40U * | 400U | 38U * | 380U | 34U * | 340U | 36U * |
| alpha-Chlordane | 20U * | 200U | 20U * | 200U | 18U * | 180U | 18U * |
| gamma-Chlordane | 20U * | 200U | 20U * | 200U | 18U * | 180U | 18U * |
| Toxaphene | 2000U * | 20000U | 2000U * | 20000U | 1800U * | 18000U | 1800U * |
| Aroclor-1016 | 400U * | 4000U | 380U * | 3800U | 340U * | 3400U | 360U * |
| Aroclor-1221 | 810U * | 8100U | 770U * | 7700U | 690U * | 6900U | 730U * |
| Aroclor-1232 | 400U * | 4000U | 380U * | 3800U | 340U * | 3400U | 360U * |
| Aroclor-1242 | 400U * | 4000U | 380U * | 3800U | 340U * | 3400U | 360U * |
| Aroclor-1248 | 400U * | 4000U | 380U * | 3800U | 340U * | 3400U | 360U * |
| Aroclor-1254 | 400U * | 4000U | 380U * | 3800U | 340U * | 3400U | 360U * |
| Aroclor-1260 | 400U * | 4000U | 380U * | 3800U | 340U * | 3400U | 360U * |
| Sample wt (g) : | 31.0 | 31.0 | 30.6 | 30.6 | 31.8 | 31.8 | 32.3 |
| %Moisture : | 20 | 20 | 15 | 15 | 9 | 9 | 15 |
| Dilution Factor: | 10.0 | 100.0 | 10.0 | 100.0 | 10.0 | 100.0 | 10.0 |

Note: For the results listed in the Data Summary Table, ESAT has replaced the laboratory assigned flags with ESAT Organic Data Qualifiers. The ESAT flags indicate the technical usability of the reported results.

ORGANIC DATA SUMMARY

Case No.: 27273

SDG: FCX38

Reviewer: Gene Zhu

Laboratory: SWOK

Matrix: Soil

Units: ug/Kg

| PESTICIDES/PCBs | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG |
|---------------------|----------|---------|----------|------|------|------|------|
| EPA SAMPLE NUMBER: | FC-X55DL | FC-X56 | FC-X56DL | | | | |
| alpha-BHC | 180U | 15U * | 150U | | | | |
| beta-BHC | 180U | 15U * | 150U | | | | |
| delta-BHC | 180U | 15U * | 150U | | | | |
| gamma-BHC (Lindane) | 180U | 15U * | 150U | | | | |
| Heptachlor | 180U | 15U * | 150U | | | | |
| Aldrin | 180U | 15U * | 150U | | | | |
| Heptachlor Epoxide | 180U | 15U * | 150U | | | | |
| Endosulfan I | 180U | 15U * | 150U | | | | |
| Dieldrin | 360U | 14 * | 36QJK | | | | |
| 4,4'-DDE | 360U | 29U * | 290U | | | | |
| Endrin | 360U | 29U * | 290U | | | | |
| Endosulfan II | 360U | 29U * | 290U | | | | |
| 4,4'-DDD | 360U | 29U * | 290U | | | | |
| Endosulfan Sulfate | 360U | 29U * | 290U | | | | |
| 4,4'-DDT | 360U | 8.9 * | 290U | | | | |
| Methoxychlor | 1800U | 23 * | 1500U | | | | |
| Endrin Ketone | 360U | 29U * | 290U | | | | |
| Endrin Aldehyde | 360U | 21 * | 290U | | | | |
| alpha-Chlordane | 180U | 6.5 * | 150U | | | | |
| gamma-Chlordane | 180U | 15U * | 150U | | | | |
| Toxaphene | 18000U | 1500U * | 15000U | | | | |
| Aroclor-1016 | 3600U | 290U * | 2900U | | | | |
| Aroclor-1221 | 7300U | 600U * | 6000U | | | | |
| Aroclor-1232 | 3600U | 290U * | 2900U | | | | |
| Aroclor-1242 | 3600U | 290U * | 2900U | | | | |
| Aroclor-1248 | 3600U | 290U * | 2900U | | | | |
| Aroclor-1254 | 3600U | 290U * | 2900U | | | | |
| Aroclor-1260 | 3600U | 290U * | 2900U | | | | |
| Sample wt (g) : | 32.3 | 34.0 | 34.0 | | | | |
| %Moisture : | 15 | 1 | 1 | | | | |
| Dilution Factor: | 100.0 | 10.0 | 100.0 | | | | |

Note: For the results listed in the Data Summary Table, ESAT has replaced the laboratory assigned flags with ESAT Organic Data Qualifiers. The ESAT flags indicate the technical usability of the reported results.

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
REGION 6
HOUSTON BRANCH
10625 FALLSTONE ROAD
HOUSTON, TEXAS 77099

INORGANIC REGIONAL DATA ASSESSMENT

CASE NO. 27273 SITE Nethery Landfill
LABORATORY DATAC NO. OF SAMPLES 19
CONTRACT# 68-D5-0133 MATRIX soil
SDG# MEJS80 REVIEWER (IF NOT ESD) ESAT
SOW# ILM04.0 REVIEWER'S NAME Sonya Meekins
ACCT# 950102DJN64 SF# 50102DZZ COMPLETION DATE September 17, 1999

| | | | | | |
|------------|----------------|----------------|----------------|----------------|----------------|
| SAMPLE NO. | <u>MFJ-S80</u> | <u>MFJ-S84</u> | <u>MFJ-S88</u> | <u>MFJ-S92</u> | <u>MFJ-S96</u> |
| | <u>MFJ-S81</u> | <u>MFJ-S85</u> | <u>MFJ-S89</u> | <u>MFJ-S93</u> | <u>MFJ-S97</u> |
| | <u>MFJ-S82</u> | <u>MFJ-S86</u> | <u>MFJ-S90</u> | <u>MFJ-S94</u> | <u>MFJ-S98</u> |
| | <u>MFJ-S83</u> | <u>MFJ-S87</u> | <u>MFJ-S91</u> | <u>MFJ-S95</u> | |

DATA ASSESSMENT SUMMARY

| | ICP | HG |
|------------------------|----------|----------|
| 1. HOLDING TIMES | <u>O</u> | <u>O</u> |
| 2. CALIBRATIONS | <u>O</u> | <u>O</u> |
| 3. BLANKS | <u>M</u> | <u>O</u> |
| 4. MATRIX SPIKES | <u>M</u> | <u>O</u> |
| 5. DUPLICATE ANALYSIS | <u>M</u> | <u>O</u> |
| 6. ICP QC | <u>M</u> | |
| 7. FAA QC | | |
| 8. LCS | <u>O</u> | <u>O</u> |
| 9. SAMPLE VERIFICATION | <u>O</u> | <u>O</u> |
| 10. OTHER QC | <u>M</u> | <u>O</u> |
| 11. OVERALL ASSESSMENT | <u>M</u> | <u>O</u> |

O = Data had no problems.

M = Data qualified because of major or minor problems.

Z = Data unacceptable.

N/A= Not applicable

ACTION ITEMS: The laboratory failed to meet the turnaround time requirement.

AREAS OF CONCERN: The laboratory failed to enclose the sample tags in a plastic bag. Laboratory blank concentrations affected some cadmium, chromium, copper, nickel, vanadium, and sodium sample results. Matrix spike recoveries were below 75 percent for antimony, silver, and zinc. The lead and zinc laboratory duplicate differences were above 35 percent. Coefficients of variation were greater than 20 percent for 18 antimony, 9 cadmium, 1 cobalt, 1 copper, and 12 nickel analyses. Field duplicate copper results were inconsistent.

NOTABLE PERFORMANCE:

**COMMENTS/CLARIFICATIONS
REGION 6 CLP QA REVIEW**

Case 27273 SDG MFJS80 Site Nethery Landfill Lab DATA

COMMENTS: The package consisted of data for 19 soil samples for total metals analysis by ILM04.0. The sampler designated samples MFJ-S81/MFJ-S82 and MFJ-S90/MFJ-S91 as field duplicate pairs and samples MFJ-S80 and MFJ-S88 as the QC samples. Although both QC samples were prepared in the same batch, the QC problems demonstrated by one sample were not confirmed by the other sample. In the reviewers opinion, neither of these two designated QC samples should be used to characterize the entire SDG. Therefore, qualifications resulting from the QC problems were applied only to the QC samples. The reviewer noted the following contractually noncompliant item.

- The laboratory failed to enclose the sample tags in a clear plastic bag.
- The laboratory submitted the package 4 working days late for the 14-day turnaround time.

Fifty-one percent of the reported results were above the CRDL's. Some results were qualified because of problems with blank concentrations, matrix spike recoveries, laboratory duplicate differences, inconsistent instrument readings, and field duplicate differences. The technical usability of all reported results is indicated in the Data Summary Table (DST).

NOTE: THE FOLLOWING REVIEW NARRATIVE ADDRESSES BOTH CONTRACTUAL ISSUES (BASED ON THE STATEMENT OF WORK) AND TECHNICAL ISSUES (BASED ON THE NATIONAL FUNCTIONAL GUIDELINES). THE ASSESSMENT MADE FOR EACH QC PARAMETER IS SOLELY BASED ON THE TECHNICAL DATA USABILITY, WHICH MAY NOT NECESSARILY BE AFFECTED BY CONTRACTUAL PROBLEMS. THE ASSESSMENTS ARE DEFINED BELOW.

Acceptable = No results were qualified for any problems associated with this QC parameter.
Provisional = Some results were qualified because of problems associated with this QC parameter.
Unusable = All results are unusable because of major problems associated with this QC parameter.

1. **Holding Times:** Acceptable. All samples met contractual holding time criteria. Technical holding time criteria have not yet been established for soil samples. The laboratory reported a cooler temperature of 25.0°C, which is above the required 4°C (± 2°C) limit for soil samples. Without established guidelines from the Agency, the reviewer can not assess the effect of the elevated shipping temperature on the sample results.
2. **Calibrations:** Acceptable. All calibrations met contractual requirements. The CRDL standard results indicated that instrument performance near the CRDL's was acceptable.

INORGANIC QA REVIEW
CONTINUATION PAGE

Case 27273 SDG MFJS80 Site Nethery Landfill Lab DATA

3. **Blanks:** Provisional. Preparation and calibration blanks met contractual requirements although the laboratory reported 13 analytes in the blanks. The cadmium result below the CRDL for sample MFJ-S98 is flagged "J" on the DST with no bias indication because the associated laboratory blanks had positive as well as negative readings. The reviewer made the following qualifications because of laboratory blank concentrations.

The cadmium result for sample MFJ-S91 and the chromium results for samples MFJ-S88 and MFJ-S93 are qualified as undetected.

The copper results for samples MFJ-S92, MFJ-S93, MFJ-S94, and MFJ-S95; the sodium results for samples MFJ-S92 and MFJ-S98; and the vanadium result for sample MFJ-S93 are qualified as undetected.

The chromium results for samples MFJ-S87 and MFJ-S92 and the nickel result for sample MFJ-S98 are qualified as estimated and biased low.

4. **Pre-digestion Matrix Spike Recovery:** Provisional. The laboratory reported matrix spike recoveries below the QC limits for antimony in QC sample MFJ-S80 and silver and zinc in QC sample MFJ-S88. As a result, the reviewer qualified the antimony result for sample MFJ-S80 and the silver and zinc results for sample MFJ-S88 as estimated and biased low.
5. **Duplicate Analysis:** Provisional. The reviewer qualified as estimated the lead and zinc results for sample MFJ-S88 because the associated laboratory duplicate difference failed to meet technical QC criteria. The manganese laboratory duplicate difference for sample MFJ-S88 only marginally exceeded the technical QC limit, so the reviewer did not qualify the associated manganese result.
6. **ICP Quality Control:** ::

Serial Dilution: Acceptable. The laboratory performed serial dilution on sample MFJ-S80 with four of the analytes (arsenic, lead, selenium, and thallium) on one instrument and the others on another instrument. However, the validity of the arsenic, lead, selenium, and thallium results is questionable based on the available data. Since an additional serial dilution analysis was performed on sample MFJ-S88 solely for these four analytes, the results from the additional analysis were used to evaluate the serial dilution performance for arsenic, lead, selenium, and thallium. All analytes met the acceptance criteria for serial dilution differences.

**INORGANIC QA REVIEW
CONTINUATION PAGE**

Case 27273 SDG MFJS80 Site Nethery Landfill Lab DATAC

6. ICP Quality Control, continued:

Interference Check Sample: Acceptable. Acceptable ICS results indicated satisfactory interelement and background correction.

Coefficient of Variation: Provisional. The reviewer qualified the following results as estimated because replicate ICP readings were inconsistent:

all antimony results except for sample MFJ-S88;

the cadmium results for samples MFJ-S83, MFJ-S85, MFJ-S86, MFJ-S87, MFJ-S88, MFJ-S89, MFJ-S91, MFJ-S95, and MFJ-S98;

the cobalt result for sample MFJ-S91;

the copper result for sample MFJ-S86; and

the nickel results for samples MFJ-S80, MFJ-S81, MFJ-S83, MFJ-S85, MFJ-S86, MFJ-S89, MFJ-S92, MFJ-S93, MFJ-S94, MFJ-S95, MFJ-S97, and MFJ-S98.

7. Furnace Atomic Absorption Quality Control: Not Applicable.

8. Laboratory Control Sample: Acceptable. Acceptable LCS results indicated satisfactory sample preparation and analysis.

9. Sample Verification: Acceptable. The laboratory correctly reported all field sample results. The reviewer detected a few minor reporting errors that did not affect sample results, and the laboratory was contacted for correction (see FAX Record Log).

10. Other QC:

Field Duplicate: Provisional. The reviewer qualified as estimated the copper result for field duplicate samples MFJ-S81 and MFJ-S82 because they had inconsistent concentrations. Field duplicate differences were acceptable for samples MFJ-S90 and MFJ-S91.

11. Overall Assessment: Sample result qualifications are summarized below.

The reviewer qualified one cadmium, four chromium, four copper, one nickel, one vanadium, and two sodium results because of laboratory blank effects.

INORGANIC DATA SUMMARY

Case No.: 27273

SDG: MFJS80

Reviewer: S. Meekins

Laboratory: DATAC

Matrix: Soil

Units: MG/KG

| EPA TR #=> | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG | FLAG |
|------------|----------|----------|----------|----------|----------|----------|----------|
| | MFJ-S80 | MFJ-S81 | MFJ-S82 | MFJ-S83 | MFJ-S84 | MFJ-S85 | MFJ-S86 |
| Aluminum | 12200 | 5180 | 5370 | 11900 | 10800 | 9890 | 5830 |
| Antimony | 10.7 UJL | 10.7 UJK | 10.7 UJK | 14.5 UJK | 14.9 UJK | 14.5 UJK | 16.8 UJK |
| Arsenic | 4.5 | 4.2 | 3.1 | 5.2 | 7.2 | 4.8 | 4.4 |
| Barium | 106 | 37.5 Q | 37.9 Q | 80.2 | 74.0 | 139 | 43.1 Q |
| Beryllium | 0.60 Q | 0.06 U | 0.06 U | 0.08 U | 0.21 Q | 0.08 U | 0.10 U |
| Cadmium | 0.61 U | 0.61 U | 0.61 U | 0.96 QJL | 0.85 U | 0.82 UJK | 0.96 UJK |
| Calcium | 52700 | 77300 | 90400 | 71400 | 125000 | 119000 | 86700 |
| Chromium | 16.0 | 11.5 | 10.2 | 18.5 | 14.9 | 18.0 | 13.9 |
| Cobalt | 7.1 Q | 6.1 Q | 5.2 Q | 6.4 Q | 5.9 Q | 4.4 Q | 4.7 U |
| Copper | 13.7 | 7700 JK | 9.9 JK | 9.9 | 10.5 | 15.4 | 7.4 QJK |
| Iron | 13100 | 11800 | 8080 | 13900 | 14000 | 10700 | 19300 |
| Lead | 65.0 | 11.7 | 18.8 | 31.0 | 36.8 | 280 | 16.6 |
| Magnesium | 2430 | 1470 | 1520 | 2460 | 2550 | 2250 | 1400 Q |
| Manganese | 357 | 256 | 245 | 398 | 331 | 465 | 551 |
| Mercury | 0.05 U | 0.05 U | 0.05 U | 0.07 U | 0.07 U | 0.18 | 0.08 U |
| Nickel | 11.6 JK | 12.5 JK | 10.8 | 13.3 JK | 7.2 U | 18.3 JK | 12.5 QJK |
| Potassium | 1330 | 757 Q | 904 Q | 1460 | 1530 | 1200 Q | 1050 Q |
| Selenium | 0.35 U | 0.34 U | 0.34 U | 0.47 U | 0.48 U | 0.47 U | 0.54 U |
| Silver | 0.87 U | 0.87 U | 0.87 U | 1.2 U | 1.2 U | 1.2 U | 1.4 U |
| Sodium | 224 Q | 171 Q | 220 Q | 173 Q | 480 Q | 335 Q | 218 Q |
| Thallium | 0.49 U | 0.49 U | 0.49 U | 0.66 U | 0.68 U | 0.66 U | 0.77 U |
| Vanadium | 28.3 | 19.2 | 14.7 | 32.4 | 31.1 | 25.8 | 24.1 |
| Zinc | 72.8 | 47.6 | 54.0 | 63.2 | 75.2 | 244 | 42.4 |
| % Solids | 98.3 | 98.9 | 98.6 | 72.7 | 70.6 | 72.9 | 62.7 |

INORGANIC DATA SUMMARY

Case No.: 27273

SDG: MFJS80

Reviewer: S. Meekins

Laboratory: DATAC

Matrix: Soil

Units: MG/KG

| EPA TR | #=> | FLAG MFJ-S87 | FLAG MFJ-S88 | FLAG MFJ-S89 | FLAG MFJ-S90 | FLAG MFJ-S91 | FLAG MFJ-S92 | FLAG MFJ-S93 |
|-----------|-----|-----------------|-----------------|-----------------|-----------------|-----------------|-----------------|-----------------|
| Aluminum | | 2520 | 3430 | 31300 | 8500 | 12400 | 1530 | 1120 |
| Antimony | | 12.6 UJK | 13.8 U | 15.0 UJK | 14.5 UJK | 13.4 UJK | 12.6 UJK | 13.5 UJK |
| Arsenic | | 5.1 | 5.0 | 7.3 | 4.3 | 4.9 | 4.5 | 1.2 Q |
| Barium | | 11.4 Q | 27.7 Q | 136 | 71.8 | 70.8 | 33.2 Q | 54.4 |
| Beryllium | | 0.07 U | 0.08 U | 1.5 | 0.62 Q | 0.67 Q | 0.07 U | 0.11 Q |
| Cadmium | | 1.1 QJK | 0.78 UJK | 0.85 UJK | 0.83 U | 0.89 UBJK | 0.72 U | 0.77 U |
| Calcium | | 54400 | 73300 | 59800 | 75600 | 63700 | 79300 | 66800 |
| Chromium | | 6.9 JL | 6.5 UB | 39.8 | 14.5 | 19.2 | 7.9 JL | 3.6 UB |
| Cobalt | | 6.7 Q | 6.1 Q | 9.2 Q | 7.0 Q | 11.9 QJK | 8.4 Q | 3.8 U |
| Copper | | 9.6 | 6.5 Q | 17.8 | 9.9 | 12.1 | 3.3 UB | 4.5 UB |
| Iron | | 13400 | 8170 | 25800 | 13000 | 14300 | 15300 | 2990 |
| Lead | | 12.5 | 41.3 JK | 57.0 | 18.5 | 42.0 | 54.6 | 3.9 |
| Magnesium | | 679 Q | 1830 | 4910 | 1820 | 2180 | 587 Q | 790 Q |
| Manganese | | 137 | 238 | 405 | 360 | 445 | 404 | 342 |
| Mercury | | 0.06 U | 0.07 U | 0.07 U | 0.07 U | 0.06 U | 0.06 U | 0.06 U |
| Nickel | | 6.1 U | 8.0 Q | 25.0 JK | 7.0 U | 19.1 | 8.3 QJK | 6.5 UJK |
| Potassium | | 398 Q | 363 Q | 4740 | 1310 Q | 1700 | 201 Q | 238 Q |
| Selenium | | 0.41 U | 0.44 U | 0.48 U | 0.49 Q | 0.43 U | 0.41 U | 0.43 U |
| Silver | | 1.0 U | 1.1 UJL | 1.2 U | 1.2 U | 1.1 U | 1.0 U | 1.1 U |
| Sodium | | 142 Q | 168 Q | 369 Q | 166 Q | 151 Q | 74.7 UB | 173 Q |
| Thallium | | 0.57 U | 0.63 U | 0.68 U | 0.66 U | 0.61 U | 0.58 U | 0.61 U |
| Vanadium | | 14.1 | 21.7 | 59.3 | 23.1 | 29.8 | 18.7 | 4.5 UB |
| Zinc | | 22.9 | 121 JL | 115 | 73.3 | 167 | 122 | 31.8 |
| % Solids | | 83.5 | 76.6 | 70.3 | 72.5 | 78.5 | 83.4 | 78.2 |

INORGANIC DATA SUMMARY

Case No.: 27273

SDG: MFJS80

Reviewer: S. Meekins

Laboratory: DATAC

Matrix: Soil

Units: MG/KG

| EPA TR | #=> | FLAG MFJ-S94 | FLAG MFJ-S95 | FLAG MFJ-S96 | FLAG MFJ-S97 | FLAG MFJ-S98 | FLAG | FLAG |
|-----------|-----|-----------------|-----------------|-----------------|-----------------|-----------------|------|------|
| Aluminum | | 5370 | 6060 | 5820 | 14800 | 4950 | | |
| Antimony | | 14.8 UJK | 12.9 UJK | 11.8 UJK | 11.6 UJK | 12.2 UJK | | |
| Arsenic | | 1.5 Q | 3.0 | 3.7 | 4.3 | 4.8 | | |
| Barium | | 42.0 Q | 34.4 Q | 47.8 | 61.9 | 52.7 | | |
| Beryllium | | 0.13 Q | 0.09 Q | 0.28 Q | 0.69 Q | 0.13 Q | | |
| Cadmium | | 0.84 U | 0.73 UJK | 0.67 U | 0.66 U | 0.81 QJK | | |
| Calcium | | 32200 | 31600 | 83600 | 120000 | 12700 | | |
| Chromium | | 11.0 | 9.9 | 10.1 | 20.7 | 22.2 | | |
| Cobalt | | 5.9 Q | 4.0 Q | 4.7 Q | 7.7 Q | 5.9 Q | | |
| Copper | | 4.6 UB | 5.8 UB | 9.7 | 14.8 | 12.5 | | |
| Iron | | 6280 | 7880 | 9140 | 13700 | 9270 | | |
| Lead | | 10.7 | 8.1 | 55.0 | 18.6 | 748 | | |
| Magnesium | | 1020 Q | 1360 | 1290 | 3110 | 754 Q | | |
| Manganese | | 125 | 145 | 828 | 621 | 240 | | |
| Mercury | | 0.07 U | 0.06 U | 0.06 U | 0.06 U | 0.06 U | | |
| Nickel | | 7.4 QJK | 10.8 JK | 10.8 | 11.6 JK | 16.5 JL | | |
| Potassium | | 1100 Q | 911 Q | 900 Q | 2430 | 1000 Q | | |
| Selenium | | 0.48 U | 0.42 U | 0.38 U | 0.37 U | 0.39 U | | |
| Silver | | 1.2 U | 1.1 U | 0.96 U | 0.95 U | 1.0 U | | |
| Sodium | | 139 Q | 125 Q | 246 Q | 364 Q | 45.5 UB | | |
| Thallium | | 0.68 U | 0.59 U | 0.54 U | 0.53 U | 0.56 U | | |
| Vanadium | | 12.0 Q | 15.5 | 17.1 | 32.4 | 14.4 | | |
| Zinc | | 65.9 | 89.7 | 46.8 | 76.1 | 140 | | |
| % Solids | | 71.1 | 81.8 | 89.7 | 90.7 | 86.2 | | |

Reference 21

**SITE INSPECTION WORK PLAN
FOR
NETHERY LANDFILL
DALLAS, DALLAS COUNTY, TEXAS**

July 19,1999

Prepared for:

**Henry Thompson Jr.
Project Officer
Response and Prevention Branch
EPA Region 6**

Contract Number 68-W6-0013

TABLE OF CONTENTS

| <u>Section</u> | | <u>Page</u> |
|-----------------|---|-------------|
| 1.0 | INTRODUCTION..... | 1 |
| | 1.1 SITE INSPECTION OBJECTIVES..... | 1 |
| | 1.2 SITE DESCRIPTION AND OPERATIONAL HISTORY..... | 1 |
| | 1.3 SITE SPECIFIC OBJECTIVES..... | 3 |
| 2.0 | DATA REVIEW AND DATA COLLECTION..... | 6 |
| | 2.1 PREVIOUS SAMPLING DATA..... | 6 |
| | 2.2 SOURCE WASTE CHARACTERIZATION..... | 7 |
| | 2.3 GROUND WATER PATHWAY..... | 7 |
| | 2.4 SURFACE WATER PATHWAY..... | 7 |
| | 2.5 SOIL EXPOSURE PATHWAY..... | 8 |
| | 2.6 AIR MIGRATION PATHWAY..... | 9 |
| 3.0 | PROJECT MANAGEMENT..... | 9 |
| | 3.1 KEY PERSONNEL..... | 9 |
| | 3.2 IDW PROCEDURES..... | 9 |
| | 3.3 SCHEDULE..... | 10 |
| | 3.4 COMMUNITY RELATIONS..... | 10 |
| <u>Appendix</u> | | |
| A | Sample Description and Rationale..... | A |

LIST OF ILLUSTRATIONS

| <u>Figure</u> | | <u>Page</u> |
|---------------|--------------------------|-------------|
| 1 | Site Location Map..... | 4 |
| 2 | Sample Location Map..... | 5 |

1.0 INTRODUCTION

The Superfund Technical Assessment and Response Team (START) was tasked by the U.S. Environmental Protection Agency (EPA) under Technical Directive Document (TDD) S06-99-03-0001 to conduct a Site Inspection (SI) for the Nethery Landfill in Dallas, Dallas County, Texas.

1.1 SITE INSPECTION OBJECTIVES

The SI is the initial sampling stage of the site assessment process. The SI characterizes the site through the Hazard Ranking System (HRS) documentation and evaluates the site for imminent and substantial endangerment (ISE) conditions and removal potential. The SI includes target data collection, analytical data generated from collection of environmental samples, and an HRS PRescore. Information obtained during the SI supports the management decision of whether the site warrants additional removal action, proceeds to an Expanded Site Inspection (ESI) or to an HRS scoring package for proposal to the National Priorities List (NPL), or receives the classification of No Further Remedial Action Planned (NFRAP) under the Superfund Amendments and Reauthorization Act (SARA).

1.2 SITE DESCRIPTION AND OPERATIONAL HISTORY

The Nethery landfill is located at 500 Deepwood Street in Dallas, Dallas County, Texas. The geographical coordinates of the site are 32°42' 22.1" north latitude and 96° 42' 0.75" west longitude. The landfill occupies approximately 84 acres and is bordered by a residential neighborhood to the north, the Woodland Spring Park to the east, the Trinity River and McCommas Bluff Park to the south, and non-operational quarry land to the west. The nearest residents are located approximately 30 yards north of the landfill. An apartment complex is north of the intersection of Jim Miller Road and Gaylen Drive.

The landfill can be divided into three primary areas: the North Disposal Area, the South Side and the West Side. The North Side Disposal Area contains the majority of the debris and comprises approximately 35 acres with waste reaching a depth of 20-30 feet. The South Side consists of low-lying areas not utilized in the day to day operations of the facility and comprises approximately 24 acres. The West Side, approximately 25 acres, consists of low-lying areas and had limited use as a disposal area.

The site was an unlicensed and unpermitted landfill that accepted primarily construction materials from mid-1994 until mid-1996. There are no manifests or records of wastes that the landfill received and there are documented episodes of illegal dumping of unknown materials at night.

The City of Dallas took civil action against Mr. Nethery, the site owner, in 1996. In June 1996, the Texas Natural Resource Conservation Commission (TNRCC) and the EPA-criminal Investigation Division (CID) began to investigate the landfill operations for possible criminal intent. On September 13, 1996, TNRCC and EPA-CID conducted an inspection at the landfill. The inspectors observed a smoldering area within the landfill and the Superfund Technical Assistance and Response Team (START) responded to the fire, conducting air monitoring, and documenting site conditions. Air monitoring equipment was used to detect volatile organic compounds (VOCs), cyanide, hydrogen sulfide, phosgene and radiation. Monitoring results did not indicate the presence of these contaminants at concentrations greater than background levels (TDD S06-96-09-0013). EPA issued a cease-and-desist order, which closed the landfill, because of the possible migration of surface water runoff from the landfill to the Trinity River. No cap has been placed on the landfill and the waste is exposed.

Based on a review of site files and information obtained during the July 1, 8, and 15th 1999 site reconnaissances, it has been determined that the North Disposal Area warrants further investigation to evaluate the possible presence and migration of contaminants. The North

Disposal Area has been identified as a possible source and will therefore be the focus of this SI.


1.3 SITE-SPECIFIC OBJECTIVES

The objectives of the SI are to obtain HRS-quality analytical data to characterize the landfill and to determine if surrounding surface waters, which meet the HRS definition of wetlands, have been contaminated by material from Nethery Landfill. See Appendix A for description, location and rationale of the samples to be collected during the SI.

To meet the objectives of the SI, a total of 19 samples, including field duplicates, will be collected. Four grab soil samples, including a duplicate and a background, will be collected from the North Disposal Area. These samples will be collected from a depth of 0 to 6 inches in the trench along the east side of the pile. Five sediment samples will be collected from the overflow south of the waste pile at approximately 100 foot intervals. Three sediment samples will be collected from the pond east of the waste pile. Two sediment samples will be collected from the overflow at the south end of the pond. Five sediment samples, including a duplicate and background, will be collected from Elam Creek. These samples will be collected at approximately 200 foot intervals beginning at the Probable Point of Entry (PPE).

All soil and sediment samples will be analyzed by Contract Laboratory Program (CLP) laboratories for Target Compound List (TCL) and Target Analyte List (TAL) constituents.

All surface soil and sediment samples from the site will be collected utilizing dedicated stainless steel trowels and homogenized (with the exception of the volatile fraction) either in place or in dedicated stainless steel mixing bowels prior to transfer to sample jars. All soil samples will be preserved by placing bagged ice into the shipping containers. No chemical preservatives will be used to preserve the samples.



QUADRANGLE LOCATION




ecology and environment, inc.
Superfund Technical Assessment
& Response Team Region 6

CERCLIS/CASE#: NA

TDD# S06-99-03-0001

SOURCE: U.S.G.S. 7.5 MIN. TOPOGRAPHIC QUADRANGLE
HUTCHINS, TEXAS 1958

FIGURE 1
SITE LOCATION MAP



All samples will be iced to 4°C for shipment to the appropriate laboratory.

Samples collected by START during the course of the SI will be packaged according to EPA protocols found in EPA/540/P-87/001, *"A Compendium of Superfund Field Operations Methods"*. All samples will be shipped for overnight delivery, via Federal Express, to the designated laboratory.

2.0 DATA REVIEW AND DATA COLLECTION

This section summarizes previous sampling and non-sampling data collected and identifies additional data collection needs for each pathway of concern.

2.1 PREVIOUS SAMPLING DATA

Areas of the site have been sampled by TNRCC, START, and City of Dallas-Dallas Water Utilities.

Initial sampling at the landfill was conducted by the TNRCC in late August and early September of 1996. Metals, Base Neutral Acids (BNA), Total Petroleum Hydrocarbons (TPH), Total Solids and Volatile Organics (VOA) analyses were conducted on water and soil samples. The BNA results were not available to START. Low levels of metals and VOAs were detected in the soil samples analyzed, and all of the samples contained petroleum hydrocarbon.

START performed air sampling in March of 1997 during a fire at the site. The results showed that all contaminant levels were near or below detection limits.

Also in March of 1997, during the fire, the City of Dallas-Dallas Water Utilities analyzed three water samples. Results indicated only one analysis that was slightly elevated, with the effluent

from the landfill containing Benzene at 7.1 ppb. The state limit for benzene is 5.0 ppb. No other sampling has taken place since March of 1997.

2.2 SOURCE WASTE CHARACTERIZATION

Based on review of site files and the site reconnaissance, the North Disposal Area has been identified as the source. This area occupies approximately 35 acres and has a waste thickness of 20 to 30 feet in some areas.

2.3 GROUND WATER PATHWAY

The site is located on the Trinity aquifer. The Trinity aquifer occurs in rocks of Cretaceous age and consists primarily of dolomitic limestone with interbedded sand, shale, and clay. Underlying the Trinity aquifer is a confining unit consisting of clay and shale.

There are no wells used for drinking water within four miles of the landfill. All potable water in the area is supplied by reservoirs located to the north of the site.

The ground water pathway is not of concern due to lack of targets.

2.4 SURFACE WATER PATHWAY

The landfill is located between Elam Creek to the east and the Trinity River to the south, between a 500 year and 100 year floodplain. The two-year, 24 hour rainfall is approximately 4 inches.

Several small ponds are scattered throughout the site with abundant hydrophytic vegetation at the pond margins. A pond located on the east side of the North Disposal Area drains to the southeast approximately 1000 feet into Elam Creek, the PPE into surfacewater. Elam Creek flows

approximately 1500 feet from the PPE into the Trinity River. Surface water runoff from the south of the North Disposal Area flows approximately 500 feet into the Trinity River.

The Trinity River is a fishery and has no water intakes within the fifteen mile Target Distance Limit (TDL). The annual minimum 7 day flow according to the United States Geological Survey (USGS) in 1995 was approximately 390 cubic feet per second.

According to the National Wetlands Inventory (NWI) maps and 40 CFR 230.3, the landfill is surrounded by eligible HRS wetlands. Eligible wetlands border Elam Creek and parts of the Trinity River, south of the North Disposal Area. Several federal and listed threatened and endangered species, including the Black-capped Vireo, the Interior Least Tern, Migrant Loggerhead Shrike and the Texas Garter Snake may inhabit areas along the 15-mile TDL; however, they have not been officially documented as being present.

Due to the potential environmental threat, sediment samples will be collected by START from the wetlands to determine whether the surface water pathway has been affected by potential site-related contaminants.

2.5 SOIL EXPOSURE PATHWAY

The entrance to the landfill is fenced and locked. A fence surrounds the northern perimeter of the landfill. To the east of the landfill is Elam Creek, to the south is the Trinity River and to the west are abandoned gravel pits. There is evidence that local residents may trespass on the property with egress from southeast of the site. The nearest residence is approximately 100 feet to the north. The population within a 1-mile radius is approximately 7,537. The surrounding areas to the north and east are highly populated, but no schools or daycare facilities are located within 200 feet of the landfill. Soil samples will be collected to determine whether hazardous substances are present in the surface soils.

2.6 AIR MIGRATION PATHWAY

The population within the 4-mile radius is 80,447. The landfill is moderately vegetated, which would limit the potential for gaseous or particulate release to the air. There were no odors detected upon the site reconnaissance.

No air samples will be collected at this time.

3.0 PROJECT MANAGEMENT

Key personnel, Investigation Derived Wastes (IDW), schedule and community relations are addressed in this section.

3.1 KEY PERSONNEL

Michelle Brown is the Task Manager for this SI. Her responsibilities will include the planning and implementation of all field activities and preparation of the final report. A Site Safety Officer will be assigned who will prepare and implement the site safety plan. Two additional START members will be utilized in the sampling operations conducted at the site.

3.2 IDW PROCEDURES

With the collection of the environmental samples during the SI, the contractor will generate different types of investigation derived wastes (IDW) that could possibly contain Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) and Resource Conservation and Recovery Act (RCRA) classified wastes. The IDW may include used personal protective equipment and disposable sampling equipment. Based on the potential liability of CERCLA and RCRA classified wastes, all generated IDW will be managed in a manner

consistent with EPA guidance set forth in EPA/540/G-91/9009, *Management of Investigation Derived Wastes During Site Inspections*.

All field and sampling equipment will be properly decontaminated according to the EPA protocol found in EPA/540/P-87/001 *A Compendium of Superfund Field Operations Methods*. PPE, disposable sampling equipment, and trash generated during the SI will be double-bagged and disposed of in a RCRA Subtitle-D regulated landfill.

3.3 SCHEDULE

The SI is scheduled for the week of August 9, 1999. The SI activities are anticipated to last from 3 to 4 days.

3.4 COMMUNITY RELATIONS

Persons requesting site information will be instructed to submit a Freedom of Information Request to: Freedom of Information Officer, U.S. EPA Region 6, 1445 Ross Avenue, Dallas, Texas, 75202-2733. Reporters will be instructed to contact the Office of External Affairs at 214/665-2200.

APPENDIX A

Appendix A
SAMPLE DESCRIPTION AND RATIONALE

| <u>Sample Number</u> | <u>Description Rationale</u> |
|----------------------|---|
| SS01 | Source soil sample collected from 0" to 6" in depth in the North Disposal Area. Sample location will be field determined. This sample will be designated as a MS/MSD. Rationale: This sample will serve to characterize the contents of the landfill. |
| SS02 | Source soil sample collected from 0" to 6" in depth in the North Disposal Area. Sample location will be field determined. Rationale: This sample will serve to characterize the contents of the landfill. |
| SS03 | Duplicate sample of SS02. This sample will serve as a soil matrix duplicate sample as required by regional guidance. Rationale: To check field and laboratory procedures. |
| SS04 | Background soil sample collected from 0" to 6" in depth. Sample will serve as a background sample and the location will be field determined. Rationale: To determine the ambient concentrations of organic compounds and inorganic analytes. |
| SD01 | Target sediment sample collected from the pond east of the North Disposal Area. Rationale: To determine if hazardous substances from the landfill have migrated into the pond. |
| SD02 | Target sediment sample collected from the pond east of the North Disposal Area. Rationale: To determine if hazardous substances from the landfill have migrated into the pond. |

| <u>Sample Number</u> | <u>Description Rationale</u> |
|----------------------|--|
| SD03 | <p>Target sediment sample collected from the pond east of the North Disposal Area.</p> <p>Rationale: To determine if hazardous substances from the landfill have migrated into the pond.</p> |
| SD04 | <p>Target sediment sample collected from the overflow at the south end of the pond.</p> <p>Rationale: To determine if hazardous substances from the pond have migrated to the overflow</p> |
| SD05 | <p>Target sediment sample collected at the PPE from the overflow into Elam Creek.</p> <p>Rationale: To determine if hazardous substances from the overflow have migrated to Elam Creek.</p> |
| SD06 | <p>Target sediment sample collected from Elam Creek. This sample will be designated as a MS/MSD.</p> <p>Rationale: To determine if hazardous substances have entered a HRS criteria wetland.</p> |
| SD07 | <p>Target sediment sample collected from Elam Creek.</p> <p>Rationale: To determine if hazardous substances have entered a HRS criteria wetland.</p> |
| SD08 | <p>Target sediment sample collected from Elam Creek.</p> <p>Rationale: To determine if hazardous substances have entered a HRS criteria wetland.</p> |
| SD09 | <p>Duplicate of sample SD07. This sample will serve as a sediment matrix duplicate sample as required by regional guidance.</p> <p>Rationale: To check field and laboratory procedures.</p> |
| SD10 | <p>Background sediment sample collected upstream of the PPE in Elam Creek.</p> <p>Rationale: To determine the ambient concentrations of organic compounds and inorganic analytes.</p> |

Sample Number

Description Rationale

SD11

Target sediment sample collected from the overflow south of the North Disposal Area..

Rationale: To determine if hazardous substances from the landfill have migrated to the overflow.

SD12

Target sediment sample collected from the overflow south of the North Disposal Area.

Rationale: To determine if hazardous substances have entered the drainage pathway to the Trinity River.

SD13

Target sediment sample collected from the overflow south of the North Disposal Area.

Rationale: To determine if hazardous substances have entered the drainage pathway to the Trinity River.

SD14

Target sediment sample collected from the overflow south of the North Disposal Area.

Rationale: To determine if hazardous substances have entered the drainage pathway to the Trinity River.

SD15

Target sediment sample collected from the overflow south of the North Disposal Area.

Rationale: To determine if hazardous substances have entered the drainage pathway to the Trinity River.

Reference 22

MAXIM

TECHNOLOGIES INC

2575 Lone Star Drive P.O. Box 224227 * Dallas, Texas 75222 * 214-631-2700

Client ERNIE HEYER
TX. NATURAL RESOURCE CONS.COM
P.O. BOX 13087
AUSTIN, TX 787113087

Client No. 4175350
Report No. D6-09-044
Report Date 11/04/96 13:48

Project N. L. Site

Phone: 512-239-1000 Fax: 512-463-8310

Date Sampled 09/11/96

Sampled By Danny McReynolds, Guy Tidmore

Sample Type Liquid and Solid

Transported by Roger Potts

P.O. # 582-6-41380

Date Received 09/12/96

Lab No.

D6-09-044-01
D6-09-044-02
D6-09-044-03
D6-09-044-04
D6-09-044-05
D6-09-044-06
D6-09-044-07
D6-09-044-08
D6-09-044-09

Sample Identification

Sample #1
Sample #2
Sample #3
Sample #4
Sample #5
Sample #6A
Sample #7 Liquid Layer
Sample #8
Sample #9

Our letters and reports are for the exclusive use of the client to whom they are addressed and shall not be reproduced except in full without the approval of the testing laboratory. The use of our name must receive our prior written approval.

MAXIM

Maury J. Gase
Reviewed By

William J. Gase
William J. Gase, Supervisor

Order # D6-09-044

Page 2 of 5

11/04/96 13:48

TEST RESULTS BY SAMPLE

Client: TX. NATURAL RESOURCE CONS.COM

Sample: 01A Sample #1

Collected: 09/11/96 09:39

Category: S

| <u>Test Name</u> | <u>Method</u> | <u>Result</u> | <u>Units</u> | <u>Limit</u> | <u>Detection Date</u> | <u>Analyst</u> |
|----------------------------|---------------|---------------|--------------|--------------|-----------------------|----------------|
| Base Neutral Acid | SW846-8270A | Enclosure | Date Com | | 09/23/96 | MT |
| Total Petroleum Hydrocrbns | EPA 418.1 | 352000 | mg/kg | 40000 | 09/25/96 | JA |
| Total Solids | EPA 160.3 | 92.8 | % | 0.02 | 09/24/96 | JLA |
| Volatile Organics | SW846-8260 | Enclosure | Date Com | | 09/20/96 | CLU |

Sample: 02A Sample #2

Collected: 09/11/96 09:59

Category: S

| <u>Test Name</u> | <u>Method</u> | <u>Result</u> | <u>Units</u> | <u>Limit</u> | <u>Detection Date</u> | <u>Analyst</u> |
|----------------------------|---------------|---------------|--------------|--------------|-----------------------|----------------|
| Base Neutral Acid | SW846-8270A | Enclosure | Date Com | | 09/26/96 | MT |
| Total Petroleum Hydrocrbns | EPA 418.1 | 129000 | mg/kg | 4000 | 09/25/96 | JA |
| Total Solids | EPA 160.3 | 91.0 | % | 0.02 | 09/24/96 | JLA |
| Volatile Organics | SW846-8260 | Enclosure | Date Com | | 09/20/96 | CLU |

Sample: 03A Sample #3

Collected: 09/11/96 10:21

Category: W

| <u>Test Name</u> | <u>Method</u> | <u>Result</u> | <u>Units</u> | <u>Limit</u> | <u>Detection Date</u> | <u>Analyst</u> |
|----------------------------|---------------|---------------|--------------|--------------|-----------------------|----------------|
| Base Neutral Acid | SW846-8270A | Enclosure | Date Com | | 09/27/96 | MT |
| Total Petroleum Hydrocrbns | EPA 418.1 | 911000 | mg/L | 500000 | 09/20/96 | JA |
| Volatile Organics | SW846-8260 | Enclosure | Date Com | | 09/20/96 | CLU |

Sample: 04A Sample #4

Collected: 09/11/96 10:33

Category: S

| <u>Test Name</u> | <u>Method</u> | <u>Result</u> | <u>Units</u> | <u>Limit</u> | <u>Detection Date</u> | <u>Analyst</u> |
|----------------------------|---------------|---------------|--------------|--------------|-----------------------|----------------|
| Base Neutral Acid | SW846-8270A | Enclosure | Date Com | | 09/26/96 | MT |
| Total Petroleum Hydrocrbns | EPA 418.1 | 196000 | mg/kg | 10000 | 09/25/96 | JA |
| Total Solids | EPA 160.3 | 87.7 | % | 0.02 | 09/24/96 | JLA |
| Volatile Organics | SW846-8260 | Enclosure | Date Com | | 09/23/96 | CLU |

Order # D6-09-044

Page 3 of 5

11/04/96 13:48

TEST RESULTS BY SAMPLE

Client: TX. NATURAL RESOURCE CONS.COM

Sample: 05A Sample #5

Collected: 09/11/96 11:21

Category: S

| <u>Test Name</u> | <u>Method</u> | <u>Result</u> | <u>Units</u> | <u>Limit</u> | <u>Detection Date</u> | <u>Analyst</u> |
|------------------------------|---------------|---------------|--------------|--------------|-----------------------|----------------|
| Base Neutral Acid | SW846-8270A | Enclosure | Date Com | | 09/26/96 | MT |
| Total Petroleum Hydrocarbons | EPA 418.1 | 157000 | mg/kg | 10000 | 09/25/96 | JA |
| Total Solids | EPA 160.3 | 86.6 | % | 0.02 | 09/24/96 | JLA |
| Volatile Organics | SW846-8260 | Enclosure | Date Com | | 09/20/96 | CLU |

Sample: 06A Sample #6A

Collected: 09/11/96 12:12

Category: W

Job: RCRAMW RCRA - Metals Only

| <u>Test Name</u> | <u>Method</u> | <u>Result</u> | <u>Units</u> | <u>Limit</u> | <u>Detection Date</u> | <u>Analyst</u> |
|------------------|---------------|---------------|--------------|--------------|-----------------------|----------------|
| Arsenic | EPA 206.2 | 0.022 | mg/L | 0.01 | 10/03/96 | BG |
| Barium | EPA 200.7 | 0.136 | mg/L | 0.1 | 09/25/96 | TAM |
| Cadmium | EPA 200.7 | <0.02 | mg/L | 0.02 | 09/25/96 | TAM |
| Chromium | EPA 200.7 | <0.05 | mg/L | 0.05 | 09/25/96 | TAM |
| Lead | EPA 200.7 | <0.10 | mg/L | 0.1 | 09/25/96 | TAM |
| Mercury | EPA 245.1 | <0.002 | mg/L | 0.002 | 09/25/96 | TAM |
| Selenium | EPA 270.2 | <0.005 | mg/L | 0.005 | 10/17/96 | BG |
| Silver | EPA 272.1 | <0.02 | mg/L | 0.02 | 10/04/96 | CL |
| Water Digestion | SW 3010/3020 | 09/17/96 | Date Com | | | DC |

Sample: 06B Sample #6

Collected: 09/11/96 12:12

Category: W

| <u>Test Name</u> | <u>Method</u> | <u>Result</u> | <u>Units</u> | <u>Limit</u> | <u>Detection Date</u> | <u>Analyst</u> |
|-------------------|---------------|---------------|--------------|--------------|-----------------------|----------------|
| Base Neutral Acid | SW846-8270A | Enclosure | Date Com | | 09/27/96 | MT |
| Volatile Organics | SW846-8260 | Enclosure | Date Com | | 09/17/96 | CLU |

Order # D6-09-044

Page 4 of 5

11/04/96 13:48

TEST RESULTS BY SAMPLE

Client: TX. NATURAL RESOURCE CONS.COM

Sample: 07A Sample #7 Liquid Layer

Collected: 09/11/96 15:01

Category: W

| <u>Test Name</u> | <u>Method</u> | <u>Result</u> | <u>Units</u> | <u>Limit</u> | <u>Detection Date</u> | <u>Analyst</u> |
|------------------------------|---------------|---------------|--------------|--------------|-----------------------|----------------|
| Arsenic | EPA 206.2 | 0.010 | mg/L | 0.01 | 10/03/96 | BG |
| Barium | EPA 200.7 | <0.10 | mg/L | 0.1 | 09/25/96 | TAM |
| Base Neutral Acid | SW846-8270A | Enclosure | Date Com | | 09/27/96 | MT |
| Cadmium | EPA 200.7 | <0.02 | mg/L | 0.02 | 09/25/96 | TAM |
| Chromium | EPA 200.7 | <0.05 | mg/L | 0.05 | 09/25/96 | TAM |
| Lead | EPA 200.7 | <0.10 | mg/L | 0.1 | 09/25/96 | TAM |
| Mercury | EPA 245.1 | <0.002 | mg/L | 0.002 | 09/25/96 | TAM |
| Selenium | EPA 270.2 | <0.005 | mg/L | 0.005 | 10/17/96 | BG |
| Silver | EPA 272.1 | 0.03 | mg/L | 0.02 | 10/04/96 | CL |
| Total Petroleum Hydrocarbons | EPA 418.1 | 586 | mg/L | 100 | 09/20/96 | JA |
| Volatile Organics | SW846-8260 | Enclosure | Date Com | | 09/20/96 | CLJ |
| Water Digestion | SW 3010/3020 | 09/17/96 | Date Com | | | DC |

Sample: 07B Sample #7 Solid Layer

Collected: 09/11/96 15:01

Category: W

| <u>Test Name</u> | <u>Method</u> | <u>Result</u> | <u>Units</u> | <u>Limit</u> | <u>Detection Date</u> | <u>Analyst</u> |
|------------------------------|---------------|---------------|--------------|--------------|-----------------------|----------------|
| Arsenic | SW846-7060A | <1.0 | mg/kg | 1 | 10/07/96 | BG |
| Barium | SW846-6010A | 6.23 | mg/kg | 0.02 | 10/09/96 | DC |
| Base Neutral Acid | SW846-8270A | Enclosure | Date Com | | 09/27/96 | MT |
| Cadmium | SW846-6010A | < 2 | mg/kg | 2 | 10/09/96 | CL |
| Chromium | SW846-6010A | < 5 | mg/kg | 5 | 10/09/96 | CL |
| Digestion of Solid | SW846-3050A | 09/27/96 | Date Com | | | DC |
| Lead | SW846-6010A | <10 | mg/kg | 10 | 10/02/96 | DC |
| Mercury | SW846-7471A | < 0.6 | mg/kg | 0.6 | 09/25/96 | TAM |
| Selenium | SW846-7740 | <0.5 | mg/kg | 0.5 | 10/07/96 | BG |
| Silver | SW846-7760A | <2.0 | mg/kg | 2 | 10/04/96 | CL |
| Total Petroleum Hydrocarbons | EPA 418.1 | 30800 | mg/kg | 10000 | 09/20/96 | JA |
| Volatile Organics | SW846-8260 | Enclosure | Date Com | | 09/20/96 | CLJ |

Sample: 08A Sample #8

Collected: 09/11/96 16:08

Category: W

| <u>Test Name</u> | <u>Method</u> | <u>Result</u> | <u>Units</u> | <u>Limit</u> | <u>Detection Date</u> | <u>Analyst</u> |
|------------------------------|---------------|---------------|--------------|--------------|-----------------------|----------------|
| Ignitability | SW846-1010 | >160 | DEG. F | | 09/25/96 | JA |
| Total Petroleum Hydrocarbons | EPA 418.1 | 928000 | mg/L | 200000 | 09/20/96 | JA |

Order # D6-09-044

Page 5 of 5

11/04/96 13:48

TEST RESULTS BY SAMPLE

Client: TX. NATURAL RESOURCE CONS.COM

Sample: 09A Sample #9

Collected: 09/11/96 16:19

Category: W

| <u>Test Name</u> | <u>Method</u> | <u>Result</u> | <u>Units</u> | <u>Detection</u> | <u>Date</u> | <u>Limit</u> | <u>Analyzed</u> | <u>Analyst</u> |
|------------------------------|---------------|---------------|--------------|------------------|-------------|--------------|-----------------|----------------|
| Ignitability | SW846-1010 | >160 | DEG. F | | | | 09/25/96 | JA |
| Total Petroleum Hydrocarbons | EPA 418.1 | 928000 | mg/L | | | 200000 | 09/20/96 | JA |

Analysis Request and Chain of Custody Record

Page _____ of _____



- ☐ HOUSTON EAS 222 CAVALCADE ST., HOUSTON, TEXAS 77009 (713) 692-9151
- ☒ DALLAS EAS 2575 LONE STAR DR., DALLAS, TEXAS 75212 (214) 631-2700
- ☐ MIDLAND EAS 1703 WEST INDUSTRIAL, MIDLAND, TEXAS 79701 (915) 683-3349

| Project no. | | Client/Project | | | | | | P.O.# | | | |
|-------------------------|----------------------------------|---|------|---------------------------------|-------------------------------|--|--------------|---------------------------------|--------------------|---|--|
| | | N. L. Site Texas Natural Resource Conservation Comm., Special Investigations | | | | | | | | | |
| Lab ID No. | Field Sample No./ Identification | Date and Time | Grab | Comp | Sample Container (Size/Mat'l) | Sample Type (Liquid Sludge, Etc.) | Preservative | ANALYSIS REQUESTED | LABORATORY REMARKS | | |
| ✓ | Sample #1 | 9/11/96 9:39 AM | X | | 8oz glass | Liquid | Ice | TPH, GC/ms | | | |
| ✓ | Sample #2 | 9/11/96 9:58 AM | X | | 8oz glass | Liquid | Ice | TPH, GC/ms | | | |
| ✓ | Sample #3 | 9/11/96 10:21 AM | X | | 8oz glass | Liquid | Ice | TPH, GC/ms | | | |
| ✓ | Sample #4 | 9/11/96 10:33 AM | X | | 8oz glass | Liquid | Ice | TPH, GC/ms | | | |
| ✓ | Sample #5 | 9/11/96 11:21 AM | X | | 8oz glass | Liquid | Ice | TPH, GC/ms | | | |
| ✓ | Sample #6A | 9/11/96 12:12 PM | X | | 12oz glass Cul. taken | Liquid | Ice | Total metals | | | |
| ✓ | Sample #6 | 9/11/96 12:12 PM | X | | 8oz glass | Liquid | Ice | GC/ms | | | |
| ✓ | Sample #7 | 9/11/96 3:01 PM | X | | 8oz glass | Liquid | Ice | TPH, GC/ms, Total metals | | | |
| ✓ | Sample #8 | 9/11/96 4:08 PM | X | | 8oz glass | Liquid | Ice | TPH, Ignitability | | | |
| ✓ | Sample #9 | 9/11/96 4:19 PM | X | | 8oz glass | Liquid | Ice | TPH, Ignitability | | | |
| Samplers: (Print) | | Relinquished by: | | Date: | | Received by: | | Date: | | COC Seal No. | |
| Danny McReynolds | | (Signature) | | | | (Signature) | | | | REC'D. ON ICE | |
| Guy Tidmore | | (Signature) | | | | (Signature) | | | | Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> | |
| Affiliation | | (Signature) | | | | (Signature) | | | | Intact: <input checked="" type="checkbox"/> | |
| THRC EPA | | (Signature) | | Date: 9/12/96 Time: 11:00 AM | | Received by Laboratory: (Signature) | | Date: 9/12/96 Time: 11:00 AM | | Laboratory No. | |
| Results by | | REMARKS: | | | | Data Results To: | | | | | |
| Rush Charges Authorized | | | | | | 1. Earnest Hoyer | | | | Db09044 | |
| Yes _____ No _____ | | | | | | 2. James Navarette | | | | | |

Order # D6-09-006

Page 3 of 4

09/23/96 10:30

TEST RESULTS BY SAMPLE

Client: TX. NATURAL RESOURCE CONS.COM

Sample: 03A 183917

Collected: 08/28/96 13:50

Category: W

Job: RCRAMW RCRA - Metals Only

| <u>Test Name</u> | <u>Method</u> | <u>Result</u> | <u>Units</u> | <u>Limit</u> | <u>Detection Date</u> | <u>Analyst</u> |
|------------------|---------------|---------------|--------------|--------------|-----------------------|----------------|
| Arsenic | EPA 206.2 | <0.01 | mg/L | 0.01 | 09/13/96 | TAM |
| Barium | EPA 200.7 | <0.1 | mg/L | 0.1 | 09/12/96 | TAM |
| Cadmium | EPA 200.7 | <0.02 | mg/L | 0.02 | 09/12/96 | TAM |
| Chromium | EPA 200.7 | <0.05 | mg/L | 0.05 | 09/12/96 | TAM |
| Lead | EPA 200.7 | <0.1 | mg/L | 0.1 | 09/12/96 | TAM |
| Mercury | EPA 245.1 | <0.002 | mg/L | 0.002 | 09/10/96 | TAM |
| Selenium | EPA 270.2 | <0.005 | mg/L | 0.005 | 09/13/96 | TAM |
| Silver | EPA 272.1 | <0.02 | mg/L | 0.02 | 09/11/96 | TAM |
| Water Digestion | SW 3010/3020 | 09/11/96 | | | | DC |

Sample: 04A 183947

Collected: 08/28/96 13:55

Category: W

| <u>Test Name</u> | <u>Method</u> | <u>Result</u> | <u>Units</u> | <u>Limit</u> | <u>Detection Date</u> | <u>Analyst</u> |
|------------------|---------------|---------------|--------------|--------------|-----------------------|----------------|
| Arsenic | EPA 206.2 | <0.4 | mg/L | 0.4 | 09/13/96 | TAM |
| Barium | EPA 200.7 | <1 | mg/L | 1 | 09/12/96 | TAM |
| Cadmium | EPA 200.7 | 0.005 | mg/L | 0.2 | 09/12/96 | TAM |
| Chromium | EPA 200.7 | 44.5 | mg/L | 0.5 | 09/12/96 | TAM |
| Lead | EPA 200.7 | 14.1 | mg/L | 1 | 09/12/96 | TAM |
| Mercury | EPA 245.1 | 0.135 | mg/L | 0.02 | 09/10/96 | TAM |
| Selenium | EPA 270.2 | <0.2 | mg/L | 0.2 | 09/13/96 | TAM |
| Silver | EPA 272.1 | <0.02 | mg/L | 0.02 | 09/11/96 | TAM |
| Water Digestion | SW 3010/3020 | 09/11/96 | | | | DC |
| pH | EPA 150.1 | <1 | pH units | | 09/04/96 | KB |

Lab Name: Maxim Technologies, Inc.
 Lab Code: 05-17 Dallas
 Matrix: (soil/water) Soil
 Sample wt/vol: 0.8 (g/mL) G
 Level: (low/med) Low
 Dilution Factor: 1
 % Moisture: 7.2

Lab Number: D609044-01
 Client: TNRCC
 Sample ID: SAMPLE #1
 Lab File ID: >AT771
 Date Received: 09/12/96
 Date Analyzed: 9/20/96

| CAS NO. | COMPOUND | CONCENTRATION UNITS: (ug/L or ug/Kg) ug/Kg | Q |
|----------|-----------------------------|---|---|
| 67-64-1 | Acetone | 1700. | E |
| 78-93-3 | 2-Butanone (MEK) | 670. | U |
| 107-02-8 | Acrolein | 340. | U |
| 107-13-1 | Acrylonitrile | 340. | U |
| 591-78-6 | 2-Hexanone | 340. | U |
| 108-10-1 | 4-Methyl-2-pentanone (MIBK) | 670. | U |
| 108-05-4 | Vinyl Acetate | 340. | U |
| 74-83-9 | Bromomethane | 67. | U |
| 75-00-3 | Chloroethane | 67. | U |
| 110-75-8 | 2-Chloroethyl Vinyl Ether | 67. | U |
| 74-87-3 | Chloromethane | 67. | U |
| 75-71-8 | Dichlorodifluoromethane | 67. | U |
| 75-69-4 | Trichlorofluoromethane | 67. | U |
| 75-01-4 | Vinyl Chloride | 67. | U |
| 108-86-1 | Bromobenzene | 34. | U |
| 75-97-5 | Bromochloromethane | 34. | U |
| 75-27-4 | Bromodichloromethane | 34. | U |
| 75-25-2 | Bromoform | 34. | U |
| 104-51-8 | n-Butylbenzene | 34. | U |
| 135-98-8 | sec-Butylbenzene | 34. | U |
| 98-06-6 | tert-Butylbenzene | 34. | U |
| 75-15-0 | Carbon Disulfide | 670. | U |
| 56-23-5 | Carbon Tetrachloride | 34. | U |
| 108-90-7 | Chlorobenzene | 34. | U |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
 D - The result is from a diluted sample.
 B - The compound was found in the method blank.
 E - Exceeds upper calibration limit.

VOLATILE ORGANICS ANALYSIS DATA SHEET
EPA METHOD 8260

Lab Name: Maxim Technologies, Inc.
Lab Code: 05-17 Dallas
Matrix: (soil/water) Soil
Sample wt/vol: 0.8 (g/mL) G
Level: (low/mod) Low
Dilution Factor: 1
% Moisture: 7.2

Lab Number: D609044-01
Client: TNRCC
Sample ID: SAMPLE #1
Lab File ID: >AT771
Date Received: 09/12/96
Date Analyzed: 9/20/96

| CAS NO. | COMPOUND | CONCENTRATION UNITS: (ug/L or ug/Kg) ug/Kg | Q |
|-----------------|-----------------------------|---|---|
| 124-48-1----- | Chlorodibromomethane | 34. | U |
| 67-66-3----- | Chloroform | 34. | U |
| 95-49-8----- | 2-Chlorotoluene | 34. | U |
| 106-43-4----- | 4-Chlorotoluene | 34. | U |
| 96-12-8----- | 1,2-Dibromo-3-chloropropane | 34. | U |
| 106-93-4----- | 1,2-Dibromoethane | 34. | U |
| 74-95-3----- | Dibromomethane | 34. | U |
| 95-50-1----- | 1,2-Dichlorobenzene | 34. | U |
| 541-73-1----- | 1,3-Dichlorobenzene | 34. | U |
| 106-46-7----- | 1,4-Dichlorobenzene | 34. | U |
| 110-57-6----- | 1,4-Dichloro-2-butene | 34. | U |
| 75-34-3----- | 1,1-Dichloroethane | 34. | U |
| 107-06-2----- | 1,2-Dichloroethane | 34. | U |
| 75-35-4----- | 1,1-Dichloroethene | 34. | U |
| 78-87-5----- | 1,2-Dichloropropane | 34. | U |
| 156-59-2----- | cis-1,2-Dichloroethene | 34. | U |
| 156-60-5----- | trans-1,2-Dichloroethene | 34. | U |
| 78-87-5----- | 1,2-Dichloropropane | 34. | U |
| 142-28-9----- | 1,3-Dichloropropane | 34. | U |
| 594-20-7----- | 2,2-Dichloropropane | 34. | U |
| 563-58-6----- | 1,1-Dichloropropene | 34. | U |
| 10061-01-5----- | cis-1,3-Dichloropropene | 34. | U |
| 10061-02-6----- | trans-1,3-Dichloropropene | 34. | U |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
D - The result is from a diluted sample.
B - The compound was found in the method blank.

VOIATILE ORGANICS ANALYSIS DATA SHEET
EPA METHOD 8260

Lab Name: Maxim Technologies, Inc.
Lab Code: 05-17 Dallas
Matrix: (soil/water) Soil
Sample wt/vol: 0.8 (g/mL) G
Level: (low/med) Low
Dilution Factor: 1
% Moisture: 7.2

Lab Number: D609044-01
Client: TNRCC
Sample ID: SAMPLE #1
Lab File ID: >AT771
Date Received: 09/12/96
Date Analyzed: 9/20/96

| CAS NO. | COMPOUND | CONCENTRATION UNITS: | | Q |
|----------|---------------------------------|----------------------|-------|---|
| | | (ug/L or ug/Kg) | ug/Kg | |
| 97-63-2 | -----Ethyl Methacrylate | 34. | | U |
| 87-68-3 | -----Hexachlorobutadiene | 34. | | U |
| 98-82-8 | -----Isopropyl benzene (Cumene) | 34. | | U |
| 99-87-6 | -----4-Isopropyltoluene | 34. | | U |
| 75-09-2 | -----Methylene Chloride | 67. | | U |
| 91-20-3 | -----Naphthalene | 34. | | U |
| 103-65-1 | -----n-Propylbenzene | 34. | | U |
| 100-42-5 | -----Styrene | 34. | | U |
| 630-20-6 | -----1,1,1,2-Tetrachloroethane | 34. | | U |
| 79-34-5 | -----1,1,2,2-Tetrachloroethane | 34. | | U |
| 127-18-4 | -----Tetrachloroethene | 34. | | U |
| 87-61-6 | -----1,2,3-Trichlorobenzene | 34. | | U |
| 120-82-1 | -----1,2,4-Trichlorobenzene | 34. | | U |
| 71-55-6 | -----1,1,1-Trichloroethane | 34. | | U |
| 79-00-5 | -----1,1,2-Trichloroethane | 34. | | U |
| 79-01-6 | -----Trichloroethene | 35. | | |
| 96-18-4 | -----1,2,3-Trichloropropane | 34. | | U |
| 95-63-6 | -----1,2,4-Trimethylbenzene | 34. | | U |
| 108-67-8 | -----1,3,5-Trimethylbenzene | 34. | | U |
| 71-43-2 | -----Benzene | 34. | | U |
| 108-67-8 | -----1,3,5-Trimethylbenzene | 34. | | U |
| 71-43-2 | -----Benzene | 34. | | U |
| 100-41-4 | -----Ethylbenzene | 34. | | U |
| 108-88-3 | -----Toluene | 34. | | U |
| 133-02-7 | -----Xylene (total) | 34. | | U |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
D - The result is from a diluted sample.
B - The compound was found in the method blank.

VOLATILE ORGANICS ANALYSIS DATA SHEET
EPA METHOD 8260

Lab Name: Maxim Technologies, Inc.
Lab Code: 05-17 Dallas
Matrix: (soil/water) Soil
Sample wt/vol: 1.5 (g/mL) C
Level: (low/med) Low
Dilution Factor: 40
% Moisture: 9

Lab Number: D609044-02
Client: TNRCC
Sample ID: SAMPLE #2
Lab File ID: >AT778
Date Received: 09/12/96
Date Analyzed: 9/20/96

| CAS NO. | COMPOUND | CONCENTRATION UNITS: | |
|---------------|-----------------------------|----------------------|-------|
| | | (ug/L or ug/Kg) | ug/Kg |
| | | | Q |
| 67-64-1----- | Acetone ^{109.2} | 15000. | U D |
| 78-93-3----- | 2-Butanone (MEK) | 15000. | U D |
| 107-02-8----- | Acrolein | 7300. | U D |
| 107-13-1----- | Acrylonitrile | 7300. | U D |
| 591-78-6----- | 2-Hexanone | 7300. | U D |
| 108-10-1----- | 4-Methyl-2-pentanone (MIBK) | 7300. | U D |
| 108-05-4----- | Vinyl Acetate | 7300. | U D |
| 74-83-9----- | Bromomethane | 1500. | U D |
| 75-00-3----- | Chloroethane | 1500. | U D |
| 110-75-8----- | 2-Chloroethyl Vinyl Ether | 1500. | U D |
| 74-87-3----- | Chloromethane | 1500. | U D |
| 75-71-8----- | Dichlorodifluoromethane | 1500. | U D |
| 75-69-4----- | Trichlorofluoromethane | 1500. | U D |
| 75-01-4----- | Vinyl Chloride | 1500. | U D |
| 108-86-1----- | Bromobenzene | 730. | U D |
| 75-97-5----- | Bromochloromethane | 730. | U D |
| 75-27-4----- | Bromodichloromethane | 730. | U D |
| 75-27-4----- | Bromodichloromethane | 730. | U D |
| 75-25-2----- | Bromoform | 730. | U D |
| 104-51-8----- | n-Butylbenzene | 730. | U D |
| 135-98-8----- | sec-Butylbenzene | 730. | U D |
| 98-06-6----- | tert-Butylbenzene | 730. | U D |
| 75-15-0----- | Carbon Disulfide | 15000. | U D |
| 56-23-5----- | Carbon Tetrachloride | 730. | U D |
| 108-90-7----- | Chlorobenzene | 730. | U D |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
D - The result is from a diluted sample.
B - The compound was found in the method blank.

VOLATILE ORGANICS ANALYSIS DATA SHEET
EPA METHOD 8260

Lab Name: Maxim Technologies, Inc.
 Lab Code: 05-17 Dallas
 Matrix: (soil/water) Soil
 Sample wt/vol: 1.5 (g/mL) G
 Level: (low/med) Low
 Dilution Factor: 40
 % Moisture: 9

Lab Number: D609044-02
 Client: TNRCC
 Sample ID: SAMPLE #2
 Lab File ID: >AT778
 Date Received: 09/12/96
 Date Analyzed: 9/20/96

CONCENTRATION UNITS:
 (ug/L or ug/Kg) ug/Kg Q

| CAS NO. | COMPOUND | CONCENTRATION UNITS: (ug/L or ug/Kg) ug/Kg | Q |
|-----------------|-----------------------------|---|-----|
| 124-48-1----- | Chlorodibromomethane | 730. | U D |
| 67-66-3----- | Chloroform | 730. | U D |
| 95-49-8----- | 2-Chlorotoluene | 730. | U D |
| 106-43-4----- | 4-Chlorotoluene | 730. | U D |
| 96-12-8----- | 1,2-Dibromo-3-chloropropane | 730. | U D |
| 106-93-4----- | 1,2-Dibromoethane | 730. | U D |
| 74-95-3----- | Dibromomethane | 730. | U D |
| 95-50-1----- | 1,2-Dichlorobenzene | 730. | U D |
| 541-73-1----- | 1,3-Dichlorobenzene | 730. | U D |
| 106-46-7----- | 1,4-Dichlorobenzene | 730. | U D |
| 110-57-6----- | 1,4-Dichloro-2-butene | 730. | U D |
| 75-34-3----- | 1,1-Dichloroethane | 730. | U D |
| 107-06-2----- | 1,2-Dichloroethane | 730. | U D |
| 75-35-4----- | 1,1-Dichloroethene | 730. | U D |
| 78-87-5----- | 1,2-Dichloropropane | 730. | U D |
| 156-59-2----- | cis-1,2-Dichloroethene | 730. | U D |
| 156-60-5----- | trans-1,2-Dichloroethene | 730. | U D |
| 78-87-5----- | 1,2-Dichloropropane | 730. | U D |
| 142-28-9----- | 1,3-Dichloropropane | 730. | U D |
| 594-20-7----- | 2,2-Dichloropropane | 730. | U D |
| 563-58-6----- | 1,1-Dichloropropene | 730. | U D |
| 10061-01-5----- | cis-1,3-Dichloropropene | 730. | U D |
| 10061-02-6----- | trans-1,3-Dichloropropene | 730. | U D |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
 D - The result is from a diluted sample.
 B - The compound was found in the method blank.

VOLATILE ORGANICS ANALYSIS DATA SHEET
EPA METHOD 8260

Lab Name: Maxim Technologies, Inc.
Lab Code: 05-17 Dallas
Matrix: (soil/water) Soil
Sample wt/vol: 1.5 (g/mL) G
Level: (low/med) Low
Dilution Factor: 40
% Moisture: 9

Lab Number: D609044-02
Client: TNRCC
Sample ID: SAMPLE #2
Lab File ID: >AT778
Date Received: 09/12/96
Date Analyzed: 9/20/96

| CAS NO. | COMPOUND | CONCENTRATION UNITS: | |
|---------------|----------------------------|----------------------|-------|
| | | (ug/L or ug/Kg) | ug/Kg |
| 97-63-2----- | Ethyl Methacrylate | 730. | U D |
| 87-68-3----- | Hexachlorobutadiene | 730. | U D |
| 98-82-8----- | Isopropyl benzene (Cumene) | 730. | U D |
| 99-87-6----- | 4-Isopropyltoluene | 730. | U D |
| 75-09-2----- | Methylene chloride | 1500. | U D |
| 91-20-3----- | Naphthalene | 1300. | D |
| 103-65-1----- | n-Propylbenzene | 730. | U D |
| 100-42-5----- | Styrene | 730. | U D |
| 630-20-6----- | 1,1,1,2-Tetrachloroethane | 730. | U D |
| 79-34-5----- | 1,1,2,2-Tetrachloroethane | 730. | U D |
| 127-18-4----- | Tetrachloroethane | 730. | U D |
| 87-61-6----- | 1,2,3-Trichlorobenzene | 730. | U D |
| 120-82-1----- | 1,2,4-Trichlorobenzene | 730. | U D |
| 71-55-6----- | 1,1,1-Trichloroethane | 730. | U D |
| 79-00-5----- | 1,1,2-Trichloroethane | 730. | U D |
| 79-01-6----- | Trichloroethane | 810. | D |
| 94-19-4----- | 1,2,2-Trichloropropane | 730. | U D |
| 79-01-6----- | Trichloroethene | 810. | D |
| 96-18-4----- | 1,2,3-Trichloropropane | 730. | U D |
| 95-63-6----- | 1,2,4-Trimethylbenzene | 730. | U D |
| 108-67-8----- | 1,3,5-Trimethylbenzene | 730. | U D |
| 71-43-2----- | Benzene | 730. | U D |
| 100-41-4----- | Ethylbenzene | 730. | U D |
| 108-88-3----- | Toluene | 730. | U D |
| 133-02-7----- | Xylene (total) | 730. | U D |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
D - The result is from a diluted sample.
R - The compound was found in the method blank.

VOLATILE ORGANICS ANALYSIS DATA SHEET
EPA METHOD 8260

Lab Name: Maxim Technologies, Inc.
 Lab Code: 05-17 Dallas
 Matrix: (soil/water) Soil
 Sample wt/vol: 0.6 (g/mL) G
 Level: (low/med) Low
 Dilution Factor: 40
 ‡ Moisture: 1

Lab Number: D609044-03
 Client: TNRCC
 Sample ID: SAMPLE #3
 Lab File ID: >AT779
 Date Received: 09/12/96
 Date Analyzed: 9/20/96

| CAS NO. | COMPOUND | CONCENTRATION UNITS: | | Q |
|---------------|-----------------------------|----------------------|-------|-----|
| | | (ug/L or ug/Kg) | ug/Kg | |
| 67-64-1----- | Acetone | 34000. | | U D |
| 78-93-3----- | 2-Butanone_(MEK) | 34000. | | U D |
| 107-02-8----- | Acrolein | 17000. | | U D |
| 107-13-1----- | Acrylonitrile | 17000. | | U D |
| 591-78-6----- | 2-Hexanone | 17000. | | U D |
| 108-10-1----- | 4-Methyl-2-pentanone_(MIBK) | 17000. | | U D |
| 108-05-4----- | Vinyl Acetate | 17000. | | U D |
| 74-83-9----- | Bromomethane | 3400. | | U D |
| 75-00-3----- | Chloroethane | 3400. | | U D |
| 110-75-8----- | 2-Chloroethyl Vinyl Ether | 3400. | | U U |
| 74-87-3----- | Chloromethane | 3400. | | U U |
| 75-71-8----- | Dichlorodifluoromethane | 3400. | | U U |
| 75-69-4----- | Trichlorofluoromethane | 3400. | | U D |
| 75-01-4----- | Vinyl Chloride | 3400. | | U D |
| 108-86-1----- | Bromobenzene | 1700. | | U D |
| 75-97-5----- | Bromochloromethane | 1700. | | U D |
| 75-27-4----- | Bromodichloromethane | 1700. | | U D |
| 75-25-2----- | Bromoform | 1700. | | U D |
| 104-51-8----- | n-Butylbenzene | 1700. | | U D |
| 135-98-8----- | sec-Butylbenzene | 1700. | | U D |
| 98-06-6----- | tert-Butylbenzene | 1700. | | U D |
| 75-15-0----- | Carbon Disulfide | 34000. | | U D |
| 56-23-5----- | Carbon Tetrachloride | 1700. | | U D |
| 108-90-7----- | Chlorobenzene | 1700. | | U D |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
 U - The result is from a diluted sample.
 B - The compound was found in the method blank.

VOLATILE ORGANICS ANALYSIS DATA SHEET
EPA METHOD 8260

Lab Name: Maxim Technologies, Inc.
 Lab Code: 05-17 Dallas
 Matrix: (soil/water) Soil
 Sample wt/vol: 0.6 (g/mL) G
 Level: (low/mod) Low
 Dilution Factor: 40
 % Moisture: 1

Lab Number: D609044-03
 Client: TNRCC
 Sample ID: SAMPLE #3
 Lab File ID: >AT779
 Date Received: 09/12/96
 Date Analyzed: 9/20/96

| CAS NO. | COMPOUND | CONCENTRATION UNITS: | |
|-----------------|-----------------------------|----------------------|-------|
| | | (ug/L or ug/Kg) | ug/Kg |
| 124-48-1----- | Chlorodibromomethane | 1700. | U D |
| 67-66-3----- | Chloroform | 1700. | U D |
| 95-49-8----- | 2-Chlorotoluene | 1700. | U D |
| 106-43-4----- | 4-Chlorotoluene | 1700. | U D |
| 96-12-8----- | 1,2-Dibromo-3-chloropropane | 1700. | U D |
| 106-93-4----- | 1,2-Dibromoethane | 1700. | U D |
| 74-95-3----- | Dibromomethane | 1700. | U D |
| 95-50-1----- | 1,2-Dichlorobenzene | 1700. | U D |
| 541-73-1----- | 1,3-Dichlorobenzene | 1700. | U D |
| 106-46-7----- | 1,4-Dichlorobenzene | 1700. | U D |
| 110-57-6----- | 1,4-Dichloro-2-butene | 1700. | U D |
| 75-34-3----- | 1,1-Dichloroethane | 1700. | U D |
| 107-06-2----- | 1,2-Dichloroethane | 1700. | U D |
| 75-35-4----- | 1,1-Dichloroethene | 1700. | U D |
| 78-87-5----- | 1,2-Dichloropropane | 1700. | U D |
| 156-59-2----- | cis-1,2-Dichloroethene | 1700. | U D |
| 156-60-5----- | trans-1,2-Dichloroethene | 1700. | U D |
| 78-87-5----- | 1,2-Dichloropropane | 1700. | U D |
| 142-28-9----- | 1,3-Dichloropropane | 1700. | U D |
| 594-20-7----- | 2,2-Dichloropropane | 1700. | U D |
| 563-58-6----- | 1,1-Dichloropropene | 1700. | U D |
| 10061-01-5----- | cis-1,3-Dichloropropene | 1700. | U D |
| 10061-03-6----- | trans-1,3-Dichloropropene | 1700. | U D |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
 D - The result is from a diluted sample.
 B - The compound was found in the method blank.

VOLATILE ORGANICS ANALYSIS DATA SHEET
EPA METHOD 8260

Lab Name: Maxim Technologies, Inc.
 Lab Code: 05-17 Dallas
 Matrix: (soil/water) Soil
 Sample wt/vol: 0.6 (g/mL) G
 Level: (low/med) Low
 Dilution Factor: 40
 % Moisture: 1

Lab Number: D609044-03
 Client: TNRCC
 Sample ID: SAMPLE #3
 Lab File ID: >AT779
 Date Received: 09/12/96
 Date Analyzed: 9/20/96

| CAS NO. | COMPOUND | CONCENTRATION UNITS: | |
|---------------|----------------------------|----------------------|-------|
| | | (ug/L or ug/Kg) | ug/Kg |
| | | | Q |
| 97-63-2----- | Ethyl Methacrylate | 1700. | U D |
| 87-68-3----- | Hexachlorobutadiene | 1700. | U D |
| 98-82-8----- | Isopropyl benzene (Cumene) | 1700. | U D |
| 99-87-6----- | 4-Isopropyltoluene | 1700. | U D |
| 75-09-2----- | Methylene Chloride | 3400. | U D |
| 91-20-3----- | Naphthalene | 27000. | D |
| 103-65-1----- | n-Propylbenzene | 1700. | U D |
| 100-42-5----- | Styrene | 1700. | U D |
| 630-20-6----- | 1,1,1,2-Tetrachloroethane | 1700. | U D |
| 79-34-5----- | 1,1,2,2-Tetrachloroethane | 1700. | U D |
| 127-18-4----- | Tetrachloroethene | 1700. | U D |
| 87-61-6----- | 1,2,3-Trichlorobenzene | 1700. | U D |
| 120-82-1----- | 1,2,4-Trichlorobenzene | 1700. | U D |
| 71-55-6----- | 1,1,1-Trichloroethane | 1700. | U D |
| 79-00-5----- | 1,1,2-Trichloroethane | 1700. | U D |
| 79-01-6----- | Trichloroethene | 1700. | U D |
| 96-18-4----- | 1,2,3-Trichloropropane | 1700. | U D |
| 95-63-6----- | 1,2,4-Trimethylbenzene | 5000. | D |
| 108-67-8----- | 1,3,5-Trimethylbenzene | 1700. | U D |
| 71-43-2----- | Benzene | 1700. | U D |
| 100-41-4----- | Ethylbenzene | 1700. | U D |
| 108-88-3----- | Toluene | 1700. | U D |
| 133-02-7----- | Xylene (total) | 1700. | U D |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
 D - The result is from a diluted sample.
 B - The compound was found in the method blank.

VOLATILE ORGANICS ANALYSIS DATA SHEET
EPA METHOD 8260

Lab Name: Maxim Technologies, Inc.
Lab Code: 05-17 Dallas
Matrix: (soil/water) Soil
Sample wt/vol: 1.7 (g/mL) C
Level: (low/med) Low
Dilution Factor: 20
% Moisture: 12.3

Lab Number: D609044-04
Client: TNRCC
Sample ID: SAMPLE #4
Lab File ID: >AT798
Date Received: 09/12/96
Date Analyzed: 9/23/96

| CAS NO. | COMPOUND | CONCENTRATION UNITS: | |
|----------|-----------------------------|----------------------|-------|
| | | (ug/L or ug/Kg) | ug/Kg |
| | | | Q |
| 67-64-1 | Acetone | 6700. | U D |
| 78-93-3 | 2-Butanone (MEK) | 6700. | U D |
| 107-02-8 | Acrolein | 3400. | U D |
| 107-13-1 | Acrylonitrile | 3400. | U D |
| 591-78-6 | 2-Hexanone | 3400. | U D |
| 108-10-1 | 4-Methyl-2-pentanone (MIBK) | 3400. | U D |
| 108-05-4 | Vinyl Acetate | 670. | U D |
| 74-83-9 | Bromomethane | 670. | U D |
| 75-00-3 | Chloroethane | 670. | U D |
| 110-75-8 | 2-Chloroethyl Vinyl Ether | 670. | U D |
| 74-87-3 | Chloromethane | 670. | U D |
| 75-71-8 | Dichlorodifluoromethane | 670. | U D |
| 75-69-4 | Trichlorofluoromethane | 670. | U D |
| 75-01-4 | Vinyl Chloride | 340. | U D |
| 108-86-1 | Bromobenzene | 340. | U D |
| 75-97-5 | Bromochloromethane | 340. | U D |
| 75-27-4 | Bromodichloromethane | 340. | U D |
| 75-97-5 | Bromochloromethane | 340. | U D |
| 75-27-4 | Bromodichloromethane | 340. | U D |
| 75-25-2 | Bromoform | 340. | U D |
| 104-51-8 | n-Butylbenzene | 340. | U D |
| 135-98-8 | sec-Butylbenzene | 340. | U D |
| 98-06-6 | tert-Butylbenzene | 340. | U D |
| 75-15-0 | Carbon Disulfide | 6700. | U D |
| 56-23-5 | Carbon Tetrachloride | 340. | U D |
| 108-90-7 | Chlorobenzene | 340. | U D |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
D - The result is from a diluted sample.
B - The compound was found in the method blank.

VOLATILE ORGANICS ANALYSIS DATA SHEET
EPA METHOD 8260

Lab Name: Maxim Technologies, Inc.
 Lab Code: 05-17 Dallas
 Matrix: (soil/water) Soil
 Sample wt/vol: 1.7 (g/mL) G
 Level: (low/med) Low
 Dilution Factor: 20
 % Moisture: 12.3

Lab Number: D609044-04
 Client: TNRCC
 Sample ID: SAMPLE #4
 Lab File ID: >AT798
 Date Received: 09/12/96
 Date Analyzed: 9/23/96

| CAS NO. | COMPOUND | CONCENTRATION UNITS: | | Q |
|-----------------|-----------------------------|----------------------|-------|-----|
| | | (ug/L or ug/Kg) | ug/Kg | |
| 124-48-1----- | Chlorodibromomethane | 340. | | U D |
| 67-66-3----- | Chloroform | 340. | | U D |
| 95-49-8----- | 2-Chlorotoluene | 340. | | U D |
| 106-43-4----- | 4-Chlorotoluene | 340. | | U D |
| 96-12-8----- | 1,2-Dibromo-3-chloropropane | 340. | | U D |
| 106-93-4----- | 1,2-Dibromoethane | 340. | | U D |
| 74-95-3----- | Dibromomethane | 340. | | U D |
| 95-50-1----- | 1,2-Dichlorobenzene | 340. | | U D |
| 541-73-1----- | 1,3-Dichlorobenzene | 340. | | U D |
| 106-46-7----- | 1,4-Dichlorobenzene | 340. | | U D |
| 110-57-6----- | 1,4-Dichloro-2-butene | 340. | | U D |
| 75-34-3----- | 1,1-Dichloroethane | 340. | | U D |
| 107-06-2----- | 1,2-Dichloroethane | 340. | | U D |
| 75-35-4----- | 1,1-Dichloroethene | 340. | | U D |
| 78-87-5----- | 1,2-Dichloropropane | 340. | | U D |
| 156-59-2----- | cis-1,2-Dichloroethene | 340. | | U D |
| 156-60-5----- | trans-1,2-Dichloroethene | 340. | | U D |
| 78-87-5----- | 1,2-Dichloropropane | 340. | | U D |
| 142-28-9----- | 1,3-Dichloropropane | 340. | | U D |
| 594-20-7----- | 2,2-Dichloropropane | 340. | | U D |
| 563-58-6----- | 1,1-Dichloropropene | 340. | | U D |
| 10061-01-5----- | cis-1,3-Dichloropropene | 340. | | U D |
| 10061-02-6----- | trans-1,3-Dichloropropene | 340. | | U D |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
 D - The result is from a diluted sample.
 B - The compound was found in the method blank.

VOLATILE ORGANICS ANALYSIS DATA SHEET
EPA METHOD 8260

Lab Name: Maxim Technologies, Inc.
 Lab Code: 05-17 Dallas
 Matrix: (soil/water) Soil
 Sample wt/vol: 1.7 (g/mL) G
 Level: (low/med) Low
 Dilution Factor: 20
 % Moisture: 12.3

Lab Number: D609044-04
 Client: TNRCC
 Sample ID: SAMPLE #4
 Lab File ID: >AT798
 Date Received: 09/12/96
 Date Analyzed: 9/23/96

| CAS NO. | COMPOUND | CONCENTRATION UNITS: | | Q |
|---------------|----------------------------|----------------------|-------|-----|
| | | (ug/L or ug/Kg) | ug/Kg | |
| 97-63-2----- | Ethyl Methacrylate | 340. | | U D |
| 87-68-3----- | Hexachlorobutadiene | 340. | | U D |
| 98-82-8----- | Isopropyl benzene (Cumene) | 340. | | U D |
| 99-87-6----- | 4-Isopropyltoluene | 340. | | U D |
| 75-09-2----- | Methylene Chloride | 670. | | U D |
| 91-20-3----- | Naphthalene | 2900. | | D |
| 103-65-1----- | n-Propylbenzene | 340. | | U D |
| 100-42-5----- | Styrene | 340. | | U D |
| 630-20-6----- | 1,1,1,2-Tetrachloroethane | 340. | | U D |
| 79-34-5----- | 1,1,2,2-Tetrachloroethane | 340. | | U D |
| 127-18-4----- | Tetrachloroethane | 340. | | U D |
| 87-61-6----- | 1,2,3-Trichlorobenzene | 340. | | U D |
| 120-82-1----- | 1,2,4-Trichlorobenzene | 340. | | U D |
| 71-55-6----- | 1,1,1-Trichloroethane | 340. | | U D |
| 79-00-5----- | 1,1,2-Trichloroethane | 340. | | U D |
| 79-01-6----- | Trichloroethene | 340. | | U D |
| 96-18-4----- | 1,2,3-Trichloropropane | 340. | | U D |
| 95-63-6----- | 1,2,4-Trimethylbenzene | 2800. | | D |
| 108-67-8----- | 1,3,5-Trimethylbenzene | 340. | | U D |
| 71-43-2----- | Benzene | 340. | | U D |
| 100-41-4----- | Ethylbenzene | 340. | | U D |
| 108-88-3----- | Toluene | 340. | | U D |
| 133-02-7----- | Xylene (total) | 440. | | D |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
 D - The result is from a diluted sample.
 B - The compound was found in the method blank.

VOLATILE ORGANICS ANALYSIS DATA SHEET
EPA METHOD 8260

Lab Name: Maxim Technologies, Inc.
Lab Code: 05-17 Dallas
Matrix: (soil/water) Soil
Sample wt/vol: 2.2 (g/mL) G
Level: (low/med) Low
Dilution Factor: 40
Moisture: 13.4

Lab Number: D609044-05
Client: TNRCC
Sample ID: SAMPLE #5
Lab File ID: >AT781
Date Received: 09/12/96
Date Analyzed: 9/20/96

| CAS NO. | COMPOUND | CONCENTRATION UNITS: | |
|----------|-----------------------------|----------------------|-------|
| | | (ug/L or ug/Kg) | ug/Kg |
| 67-64-1 | Acetone | 10000. | U D |
| 78-93-3 | 2-Butanone (MEK) | 10000. | U D |
| 107-02-8 | Acrolein | 5200. | U D |
| 107-13-1 | Acrylonitrile | 5200. | U D |
| 591-78-6 | 2-Hexanone | 5200. | U D |
| 108-10-1 | 4-Methyl-2-pentanone (MIBK) | 5200. | U D |
| 108-05-4 | Vinyl Acetate | 5200. | U D |
| 74-83-9 | Bromomethane | 1000. | U D |
| 75-00-3 | Chloroethane | 1000. | U D |
| 110-75-8 | 2-Chloroethyl Vinyl Ether | 1000. | U D |
| 74-87-3 | Chloromethane | 1000. | U D |
| 75-71-8 | Dichlorodifluoromethane | 1000. | U D |
| 75-69-4 | Trichlorofluoromethane | 1000. | U D |
| 75-01-4 | Vinyl Chloride | 1000. | U D |
| 108-86-1 | Bromobenzene | 520. | U D |
| 75-97-5 | Bromochloromethane | 520. | U D |
| 75-27-4 | Bromodichloromethane | 520. | U D |
| 75-25-2 | Bromoform | 520. | U D |
| 104-51-8 | n-Butylbenzene | 520. | U D |
| 135-98-8 | sec-Butylbenzene | 520. | U D |
| 98-06-6 | tert-Butylbenzene | 520. | U D |
| 75-15-0 | Carbon Disulfide | 10000. | U D |
| 56-23-5 | Carbon Tetrachloride | 520. | U D |
| 108-90-7 | Chlorobenzene | 520. | U D |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
D - The result is from a diluted sample.
B - The compound was found in the method blank.

VOLATILE ORGANICS ANALYSIS DATA SHEET
EPA METHOD 8260

Lab Name: Maxim Technologies, Inc.
Lab Code: 05-17 Dallas
Matrix: (soil/water) Soil
Sample wt/vol: 2.2 (g/mL) G
Level: (low/med) Low
Dilution Factor: 40
* Moisture: 13.4

Lab Number: D609044-05
Client: TNRCC
Sample ID: SAMPLE #5
Lab File ID: >AT781
Date Received: 09/12/96
Date Analyzed: 9/20/96

| CAS NO. | COMPOUND | CONCENTRATION UNITS: | | Q |
|------------|----------------------------------|----------------------|-------|-----|
| | | (ug/L or ug/Kg) | ug/Kg | |
| 124-48-1 | -----Chlorodibromomethane | 520. | | U D |
| 67-66-3 | -----Chloroform | 520. | | U D |
| 95-49-8 | -----2-Chlorotoluene | 520. | | U D |
| 106-43-4 | -----4-Chlorotoluene | 520. | | U D |
| 96-12-8 | -----1,2-Dibromo-3-chloropropane | 520. | | U D |
| 106-93-4 | -----1,2-Dibromoethane | 520. | | U D |
| 74-95-3 | -----Dibromomethane | 520. | | U D |
| 95-50-1 | -----1,2-Dichlorobenzene | 520. | | U D |
| 541-73-1 | -----1,3-Dichlorobenzene | 520. | | U D |
| 106-46-7 | -----1,4-Dichlorobenzene | 520. | | U D |
| 110-57-6 | -----1,4-Dichloro-2-butene | 520. | | U D |
| 75-34-3 | -----1,1-Dichloroethane | 520. | | U D |
| 107-06-2 | -----1,2-Dichloroethane | 520. | | U D |
| 75-35-4 | -----1,1-Dichloroethene | 520. | | U D |
| 78-87-5 | -----1,2-Dichloropropane | 520. | | U D |
| 156-59-2 | -----cis-1,2-Dichloroethene | 520. | | U D |
| 156-60-5 | -----trans-1,2-Dichloroethene | 520. | | U D |
| 78-87-5 | -----1,2-Dichloropropane | 520. | | U D |
| 142-28-9 | -----1,3-Dichloropropane | 520. | | U D |
| 594-20-7 | -----2,2-Dichloropropane | 520. | | U D |
| 563-58-6 | -----1,1-Dichloropropene | 520. | | U D |
| 10061-01-5 | -----cis-1,3-Dichloropropene | 520. | | U D |
| 10061-02-6 | -----trans-1,3-Dichloropropene | 520. | | U D |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
D - The result is from a diluted sample.
B - The compound was found in the method blank.

VOLATILE ORGANICS ANALYSIS DATA SHEET
EPA METHOD 8260

Lab Name: Maxim Technologies, Inc.
Lab Code: 05-17 Dallas
Matrix: (soil/water) Soil
Sample wt/vol: 2.2 (g/mL) G
Level: (low/med) Low
Dilution Factor: 40
% Moisture: 13.4

Lab Number: D609044-05
Client: TNRCC
Sample ID: SAMPLE #5
Lab File ID: >AT781
Date Received: 09/12/96
Date Analyzed: 9/20/96

| CAS NO. | COMPOUND | CONCENTRATION UNITS: | |
|---------------|----------------------------|----------------------|-------|
| | | (ug/L or ug/Kg) | ug/Kg |
| | | | Q |
| 97-63-2----- | Ethyl Methacrylate | 520. | U D |
| 87-68-3----- | Hexachlorobutadiene | 520. | U D |
| 98-82-8----- | Isopropyl benzene (Cumene) | 520. | U D |
| 99-87-6----- | 4-Isopropyltoluene | 520. | U D |
| 75-09-2----- | Methylene Chloride | 1000. | U D |
| 91-20-3----- | Naphthalene | 870. | D |
| 103-65-1----- | n-Propylbenzene | 520. | U D |
| 100-42-5----- | Styrene | 520. | U D |
| 630-20-6----- | 1,1,1,2-Tetrachloroethane | 520. | U D |
| 79-34-5----- | 1,1,2,2-Tetrachloroethane | 520. | U D |
| 127-18-4----- | Tetrachloroethene | 520. | U D |
| 87-61-6----- | 1,2,3-Trichlorobenzene | 520. | U D |
| 120-82-1----- | 1,2,4-Trichlorobenzene | 520. | U D |
| 71-55-6----- | 1,1,1-Trichloroethane | 520. | U D |
| 79-00-5----- | 1,1,2-Trichloroethane | 520. | U D |
| 79-01-6----- | Trichloroethene | 520. | D |
| 96-18-4----- | 1,2,3-Trichloropropane | 520. | U D |
| 95-63-6----- | 1,2,4-Trimethylbenzene | 520. | U D |
| 108-67-8----- | 1,3,5-Trimethylbenzene | 520. | U D |
| 71-43-2----- | Benzene | 520. | U D |
| 100-41-4----- | Ethylbenzene | 520. | U D |
| 108-88-3----- | Toluene | 520. | U D |
| 133-02-7----- | Xylene (total) | 520. | U D |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
D - The result is from a diluted sample.
R - The compound was found in the method blank.

VOLATILE ORGANICS ANALYSIS DATA SHEET
EPA METHOD 8260

Lab Name: Maxim Technologies, Inc.
Lab Code: 05-17 Dallas
Matrix: (soil/water) Water
Sample wt/vol: 1 (g/mL) ml
Level: (low/med) Low
Dilution Factor: 1
% Moisture: 100

Lab Number: D609044-06
Client: TNRCC
Sample ID: SAMPLE#6
Lab File ID: >AT706
Date Received: 09/12/96
Date Analyzed: 9/17/96

| CAS NO. | COMPOUND | CONCENTRATION UNITS: (ug/L or ug/Kg) ug/L | Q |
|---------------|-----------------------------|--|---|
| 67-64-1----- | Acetone | 500. | U |
| 78-93-3----- | 2-Butanone_(MEK) | 500. | U |
| 107-02-8----- | Acrolein | 250. | U |
| 107-13-1----- | Acrylonitrile | 250. | U |
| 591-78-6----- | 2-Hexanone | 250. | U |
| 108-10-1----- | 4-Methyl-2-pentanone_(MIBK) | 250. | U |
| 108-05-4----- | Vinyl Acetate | 250. | U |
| 74-83-9----- | Bromomethane | 50. | U |
| 75-00-3----- | Chloroethane | 50. | U |
| 110-75-8----- | 2-Chloroethyl Vinyl Ether | 50. | U |
| 74-87-3----- | Chloromethane | 50. | U |
| 75-71-8----- | Dichlorodifluoromethane | 50. | U |
| 75-69-4----- | Trichlorofluoromethane | 50. | U |
| 75-01-4----- | Vinyl Chloride | 50. | U |
| 108-86-1----- | Bromobenzene | 25. | U |
| 75-97-5----- | Bromochloromethane | 25. | U |
| 75-27-4----- | Bromodichloromethane | 25. | U |
| 75-25-2----- | Bromoform | 25. | U |
| 104-51-8----- | n-Butylbenzene | 25. | U |
| 135-98-8----- | sec-Butylbenzene | 25. | U |
| 98-06-6----- | tert-Butylbenzene | 25. | U |
| 75-15-0----- | Carbon Disulfide | 500. | U |
| 56-23-5----- | Carbon Tetrachloride | 25. | U |
| 108-90-7----- | Chlorobenzene | 25. | U |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
D - The result is from a diluted sample.
B - The compound was found in the method blank.

VOLATILE ORGANICS ANALYSIS DATA SHEET
EPA METHOD 8260

Lab Name: Maxim Technologies, Inc.
 Lab Code: 05-17 Dallas
 Matrix: (soil/water) water
 Sample wt/vol: 1 (g/mL) ml
 Level: (low/med) Low
 Dilution Factor: 1
 % Moisture: 100

Lab Number: D609044-06
 Client: TNRCC
 Sample ID: SAMPLE#6
 Lab File ID: >AT706
 Date Received: 09/12/96
 Date Analyzed: 9/17/96

| CAS NO. | COMPOUND | CONCENTRATION UNITS: | |
|-----------------|-----------------------------|----------------------|------|
| | | (ug/L or ug/Kg) | ug/L |
| 124-48-1----- | Chlorodibromomethane | 25. | U |
| 67-66-3----- | Chloroform | 25. | U |
| 95-49-8----- | 2-Chlorotoluene | 25. | U |
| 106-43-4----- | 4-Chlorotoluene | 25. | U |
| 96-12-8----- | 1,2-Dibromo-3-chloropropane | 25. | U |
| 106-93-4----- | 1,2-Dibromoethane | 25. | U |
| 74-95-3----- | Dibromomethane | 25. | U |
| 95-50-1----- | 1,2-Dichlorobenzene | 25. | U |
| 541-73-1----- | 1,3-Dichlorobenzene | 25. | U |
| 106-46-7----- | 1,4-Dichlorobenzene | 25. | U |
| 110-57-6----- | 1,4-Dichloro-2-butene | 25. | U |
| 75-34-3----- | 1,1-Dichloroethane | 25. | U |
| 107-06-2----- | 1,2-Dichloroethane | 25. | U |
| 75-35-4----- | 1,1-Dichloroethene | 25. | U |
| 78-87-5----- | 1,2-Dichloropropane | 25. | U |
| 156-59-2----- | cis-1,2-Dichloroethene | 25. | U |
| 156-60-5----- | trans-1,2-Dichloroethene | 25. | U |
| 78-87-5----- | 1,2-Dichloropropane | 25. | U |
| 142-28-9----- | 1,3-Dichloropropane | 25. | U |
| 594-20-7----- | 2,2-Dichloropropane | 25. | U |
| 563-58-6----- | 1,1-Dichloropropene | 25. | U |
| 10061-01-5----- | cis-1,3-Dichloropropene | 25. | U |
| 10061-02-6----- | trans-1,3-Dichloropropene | 25. | U |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
 D - The result is from a diluted sample.
 B - The compound was found in the method blank.

| | | |
|--|-----|---|
| 106-93-4-----1,2-Dibromoethane | 25. | U |
| 74-95-3-----Dibromomethane | 25. | U |
| 95-50-1-----1,2-Dichlorobenzene | 25. | U |
| 541-73-1-----1,3-Dichlorobenzene | 25. | U |
| 106-46-7-----1,4-Dichlorobenzene | 25. | U |
| 110-57-6-----1,4-Dichloro-2-butene | 25. | U |
| 75-34-3-----1,1-Dichloroethane | 25. | U |
| 107-06-2-----1,2-Dichloroethane | 25. | U |
| 75-35-4-----1,1-Dichloroethene | 25. | U |
| 78-87-5-----1,2-Dichloropropane | 25. | U |
| 156-59-2-----cis-1,2-Dichloroethene | 25. | U |
| 156-60-5-----trans-1,2-Dichloroethene | 25. | U |
| 78-87-5-----1,2-Dichloropropane | 25. | U |
| 142-28-9-----1,3-Dichloropropane | 25. | U |
| 594-20-7-----2,2-Dichloropropane | 25. | U |
| 563-58-6-----1,1-Dichloropropene | 25. | U |
| 10061-01-5-----cis-1,3-Dichloropropene | 25. | U |
| 10061-02-6-----trans-1,3-Dichloropropene | 25. | U |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
D - The result is from a diluted sample.
B - The compound was found in the method blank.

VOLATILE ORGANICS ANALYSIS DATA SHEET
EPA METHOD 8260

Lab Name: Maxim Technologies, Inc.
Lab Code: 05-17 Dallas
Matrix: (soil/water) Water
Sample wt/vol: 1 (g/mL) ml
Level: (low/med) Low
Dilution Factor: 1
% Moisture: 100

Lab Number: D609044-06
Client: TNRCC
Sample ID: SAMPLE#6
Lab File ID: >AT706
Date Received: 09/12/96
Date Analyzed: 9/17/96

| CAS NO. | COMPOUND | CONCENTRATION UNITS: (ug/L or ug/Kg) ug/L | Q |
|---------------|----------------------------|--|---|
| 97-63-2----- | Ethyl Methacrylate | 25. | U |
| 87-68-3----- | Hexachlorobutadiene | 25. | U |
| 98-82-8----- | Isopropyl benzene (Cumene) | 25. | U |
| 99-87-6----- | 4-Isopropyltoluene | 25. | U |
| 75-09-2----- | Methylene Chloride | 25. | U |
| 91-20-3----- | Naphthalene | 25. | U |
| 103-65-1----- | n-Propylbenzene | 25. | U |
| 100-42-5----- | Styrene | 25. | U |
| 630-20-6----- | 1,1,1,2-Tetrachloroethane | 25. | U |
| 79-34-5----- | 1,1,2,2-Tetrachloroethane | 25. | U |
| 127-18-4----- | Tetrachloroethene | 25. | U |
| 87-61-6----- | 1,2,3-Trichlorobenzene | 25. | U |
| 120-82-1----- | 1,2,4-Trichlorobenzene | 25. | U |
| 71-55-6----- | 1,1,1-Trichloroethane | 25. | U |
| 79-00-5----- | 1,1,2-Trichloroethane | 25. | U |
| 79-01-6----- | Trichloroethene | 25. | U |
| 96-18-4----- | 1,2,3-Trichloropropane | 25. | U |
| 95-63-6----- | 1,2,4-Trimethylbenzene | 25. | U |
| 108-67-8----- | 1,3,5-Trimethylbenzene | 25. | U |
| 71-43-2----- | Benzene | 25. | U |
| 100-41-4----- | Ethylbenzene | 25. | U |
| 108-88-3----- | Toluene | 25. | U |
| 133-02-7----- | Xylene (total) | 25. | U |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
D - The result is from a diluted sample.
B - The compound was found in the method blank.

VOLATILE ORGANICS ANALYSIS DATA SHEET
EPA METHOD 8260

Lab Name: Maxim Technologies, Inc.
Lab Code: 05-17 Dallas
Matrix: (soil/water) Water
Sample wt/vol: 0.01 (g/mL) ml
Level: (low/med) LOW
Dilution Factor: 100
% Moisture: 100

Lab Number: D609044-07W
Client: TNRCC
Sample ID: SAMPLE #7
Lab File ID: >AT777
Date Received: 09/12/96
Date Analyzed: 9/20/96

| CAS NO. | COMPOUND | CONCENTRATION UNITS: (ug/L or ug/Kg) ug/L | Q |
|---------------|-----------------------------|--|-----|
| 67-64-1----- | Acetone | 5000000. | U D |
| 78-93-3----- | 2-Butanone_(MEK) | 5000000. | U D |
| 107-02-8----- | Acrolein | 2500000. | U D |
| 107-13-1----- | Acrylonitrile | 2500000. | U D |
| 591-78-6----- | 2-Hexanone | 2500000. | U D |
| 108-10-1----- | 4-Methyl-2-pentanone_(MIBK) | 2500000. | U D |
| 108-05-4----- | Vinyl Acetate | 2500000. | U D |
| 74-83-9----- | Bromomethane | 500000. | U D |
| 75-00-3----- | Chloroethane | 500000. | U D |
| 110-75-8----- | 2-Chloroethyl Vinyl Ether | 500000. | U D |
| 74-87-3----- | Chloromethane | 500000. | U D |
| 75-71-8----- | Dichlorodifluoromethane | 500000. | U D |
| 75-69-4----- | Trichlorofluoromethane | 500000. | U D |
| 75-01-4----- | Vinyl Chloride | 500000. | U D |
| 108-86-1----- | Bromobenzene | 250000. | U D |
| 75-97-5----- | Bromochloromethane | 250000. | U D |
| 75-27-4----- | Bromodichloromethane | 250000. | U D |
| 75-25-2----- | Bromoform | 250000. | U D |
| 104-51-8----- | n-Butylbenzene | 250000. | U D |
| 135-98-8----- | sec-Butylbenzene | 250000. | U D |
| 98-06-6----- | tert-Butylbenzene | 250000. | U D |
| 75-15-0----- | Carbon Disulfide | 5000000. | U D |
| 56-23-5----- | Carbon Tetrachloride | 250000. | U D |
| 108-90-7----- | Chlorobenzene | 250000. | U D |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
D - The result is from a diluted sample.
B - The compound was found in the method blank.

VOLATILE ORGANICS ANALYSIS DATA SHEET
EPA METHOD 8260

Lab Name: Maxim Technologies, Inc.
 Lab Code: 05-17 Dallas
 Matrix: (soil/water) Water
 Sample wt/vol: 0.01 (g/mL) ml
 Level: (low/med) Low
 Dilution Factor: 100
 % Moisture: 100

Lab Number: D609044-07W
 Client: TNRCC
 Sample ID: SAMPLE #7
 Lab File ID: >AT777
 Date Received: 09/12/96
 Date Analyzed: 9/20/96

| CAS NO. | COMPOUND | CONCENTRATION UNITS: (ug/L or ug/Kg) ug/L | Q |
|------------|----------------------------------|--|-----|
| 124-48-1 | -----Chlorodibromomethane | 250000. | U D |
| 67-66-3 | -----Chloroform | 250000. | U D |
| 95-49-8 | -----2-Chlorotoluene | 250000. | U D |
| 106-43-4 | -----4-Chlorotoluene | 250000. | U D |
| 96-12-8 | -----1,2-Dibromo-3-chloropropane | 250000. | U D |
| 106-93-4 | -----1,2-Dibromoethane | 250000. | U D |
| 71-95-3 | -----Dibromomethane | 250000. | U D |
| 95-50-1 | -----1,2-Dichlorobenzene | 250000. | U D |
| 541-73-1 | -----1,3-Dichlorobenzene | 250000. | U D |
| 106-46-7 | -----1,4-Dichlorobenzene | 250000. | U D |
| 110-57-6 | -----1,4-Dichloro-2-butene | 250000. | U D |
| 75-34-3 | -----1,1-Dichloroethane | 250000. | U D |
| 107-06-2 | -----1,2-Dichloroethane | 250000. | U D |
| 75-35-4 | -----1,1-Dichloroethene | 250000. | U D |
| 78-87-5 | -----1,2-Dichloropropane | 250000. | U D |
| 156-59-2 | -----cis-1,2-Dichloroethene | 250000. | U D |
| 156-60-5 | -----trans-1,2-Dichloroethene | 250000. | U D |
| 78-87-5 | -----1,2-Dichloropropane | 250000. | U D |
| 142-28-9 | -----1,3-Dichloropropane | 250000. | U D |
| 594-20-7 | -----2,2-Dichloropropane | 250000. | U D |
| 563-58-6 | -----1,1-Dichloropropene | 250000. | U D |
| 10061-01-5 | -----cis-1,3-Dichloropropene | 250000. | U D |
| 10061-02-6 | -----trans-1,3-Dichloropropene | 250000. | U D |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
 D - The result is from a diluted sample.
 B - The compound was found in the method blank.

VOLATILE ORGANICS ANALYSIS DATA SHEET
EPA METHOD 8260

Lab Name: Maxim Technologies, Inc.
Lab Code: 05-17 Dallas
Matrix: (soil/water) Water
Sample wt/vol: 0.01 (g/mL) ml
Level: (low/med) Low
Dilution Factor: 100
% Moisture: 100

Lab Number: D609044-07W
Client: TNRCC
Sample ID: SAMPLE #7
Lab File ID: >AT777
Date Received: 09/12/96
Date Analyzed: 9/20/96

| CAS NO. | COMPOUND | CONCENTRATION UNITS: (ug/L or ug/Kg) ug/L | Q |
|----------|----------------------------|--|-----|
| 97-63-2 | Ethyl Methacrylate | 250000. | U D |
| 87-68-3 | Hexachlorobutadiene | 250000. | U D |
| 98-82-8 | Isopropyl benzene (Cumene) | 250000. | U D |
| 99-87-6 | 4-Isopropyltoluene | 250000. | U D |
| 75-09-2 | Methylene Chloride | 250000. | U D |
| 91-20-3 | Naphthalene | 250000. | U D |
| 103-65-1 | n-Propylbenzene | 250000. | U D |
| 100-42-5 | Styrene | 250000. | U D |
| 630-20-6 | 1,1,1,2-Tetrachloroethane | 250000. | U D |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | 250000. | U D |
| 127-18-4 | Tetrachloroethene | 250000. | U D |
| 87-61-6 | 1,2,3-Trichlorobenzene | 250000. | U D |
| 120-82-1 | 1,2,4-Trichlorobenzene | 250000. | U D |
| 71-55-6 | 1,1,1-Trichloroethane | 250000. | U D |
| 79-00-5 | 1,1,2-Trichloroethane | 250000. | U D |
| 79-01-6 | Trichloroethene | 250000. | U D |
| 96-18-4 | 1,2,3-Trichloropropane | 250000. | U D |
| 95-63-6 | 1,2,4-Trimethylbenzene | 250000. | U D |
| 108-67-8 | 1,3,5-Trimethylbenzene | 250000. | U D |
| 71-43-2 | Benzene | 250000. | U D |
| 100-41-4 | Ethylbenzene | 250000. | U D |
| 108-88-3 | Toluene | 250000. | U D |
| 133-02-7 | Xylene (total) | 250000. | U D |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
D - The result is from a diluted sample.
B - The compound was found in the method blank.

VOLATILE ORGANICS ANALYSIS DATA SHEET
EPA METHOD 8260

Lab Name: Maxim Technologies, Inc.
Lab Code: 05-17 Dallas
Matrix: (soil/water) Water
Sample wt/vol: 1 (g/mL) mL
Level: (low/med) Low
Dilution Factor: 1
% Moisture: 100

Lab Number: D609044-06
Client: TNRCC
Sample ID: SAMPLE#6
Lab File ID: >AT706
Date Received: 09/12/96
Date Analyzed: 9/17/96

| CAS NO. | COMPOUND | CONCENTRATION UNITS: (ug/L or ug/Kg) ug/L | Q |
|-----------------|-----------------------------|--|---|
| 124-48-1----- | Chlorodibromomethane | 25. | U |
| 67-66-3----- | Chloroform | 25. | U |
| 95-49-8----- | 2-Chlorotoluene | 25. | U |
| 106-41-4----- | 4-Chlorotoluene | 25. | U |
| 96-12-8----- | 1,2-Dibromo-3-chloropropane | 25. | U |
| 106-93-4----- | 1,2-Dibromoethane | 25. | U |
| 74-95-3----- | Dibromomethane | 25. | U |
| 95-50-1----- | 1,2-Dichlorobenzene | 25. | U |
| 541-73-1----- | 1,3-Dichlorobenzene | 25. | U |
| 106-46-7----- | 1,4-Dichlorobenzene | 25. | U |
| 110-57-6----- | 1,4-Dichloro-2-butene | 25. | U |
| 75-34-3----- | 1,1-Dichloroethane | 25. | U |
| 107-06-2----- | 1,2-Dichloroethane | 25. | U |
| 75-35-4----- | 1,1-Dichloroethene | 25. | U |
| 78-87-5----- | 1,2-Dichloropropane | 25. | U |
| 156-59-2----- | cis-1,2-Dichloroethene | 25. | U |
| 156-60-5----- | trans-1,2-Dichloroethene | 25. | U |
| 78-87-5----- | 1,2-Dichloropropane | 25. | U |
| 142-28-9----- | 1,3-Dichloropropane | 25. | U |
| 594-20-7----- | 2,2-Dichloropropane | 25. | U |
| 563-58-6----- | 1,1-Dichloropropene | 25. | U |
| 10061-01-5----- | cis-1,3-Dichloropropene | 25. | U |
| 10061-02-6----- | trans-1,3-Dichloropropene | 25. | U |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
D - The result is from a diluted sample.
B - The compound was found in the method blank.

VOLATILE ORGANICS ANALYSIS DATA SHEET
EPA METHOD 8260

Lab Name: Maxim Technologies, Inc.
Lab Code: 05-17 Dallas
Matrix: (soil/water) Water
Sample wt/vol: 1 (g/mL) ml
Level: (low/med) Low
Dilution Factor: 1
% Moisture: 100

Lab Number: D609044-06
Client: TNRCC
Sample ID: SAMPLE#6
Lab File ID: >AT706
Date Received: 09/12/96
Date Analyzed: 9/17/96

| CAS NO. | COMPOUND | CONCENTRATION UNITS: (ug/L or ug/Kg) ug/L | Q |
|----------|----------------------------|--|---|
| 97-63-2 | Ethyl Methacrylate | 25. | U |
| 87-68-3 | Hexachlorobutadiene | 25. | U |
| 98-82-8 | Isopropyl benzene (Cumene) | 25. | U |
| 99-87-6 | 4-Isopropyltoluene | 25. | U |
| 75-09-2 | Methylene Chloride | 25. | U |
| 91-20-3 | Naphthalene | 25. | U |
| 103-65-1 | n-Propylbenzene | 25. | U |
| 100-42-5 | Styrene | 25. | U |
| 630-20-6 | 1,1,1,2-Tetrachloroethane | 25. | U |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | 25. | U |
| 127-18-4 | Tetrachloroethene | 25. | U |
| 87-61-6 | 1,2,3-Trichlorobenzene | 25. | U |
| 120-82-1 | 1,2,4-Trichlorobenzene | 25. | U |
| 71-55-6 | 1,1,1-Trichloroethane | 25. | U |
| 79-00-5 | 1,1,2-Trichloroethane | 25. | U |
| 79-01-6 | Trichloroethene | 25. | U |
| 96-18-4 | 1,2,3-Trichloropropane | 25. | U |
| 95-63-6 | 1,2,4-Trimethylbenzene | 25. | U |
| 108-67-8 | 1,3,5-Trimethylbenzene | 25. | U |
| 71-43-2 | Benzene | 25. | U |
| 100-41-4 | Ethylbenzene | 25. | U |
| 108-88-3 | Toluene | 25. | U |
| 133-02-7 | Xylene (total) | 25. | U |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
D - The result is from a diluted sample.
B - The compound was found in the method blank.

Lab Name: Maxim Technologies, Inc.
 Lab Code: 05-17 Dallas
 Matrix: (soil/water) Water
 Sample wt/vol: 0.01 (g/mL) ml
 Level: (low/med) Low
 Dilution Factor: 100
 % Moisture: 100

Lab Number: D609044-07W
 Client: TNRCC
 Sample ID: SAMPLE #7
 Lab File ID: >AT777
 Date Received: 09/12/96
 Date Analyzed: 9/20/96

| CAS NO. | COMPOUND | CONCENTRATION UNITS: (ug/L or ug/Kg) ug/L | Q |
|---------------|-----------------------------|--|-----|
| 67-64-1----- | Acetone | 5000000. | U D |
| 78-93-3----- | 2-Butanone_(MEK) | 5000000. | U D |
| 107-02-8----- | Acrolein | 2500000. | U D |
| 107-13-1----- | Acrylonitrile | 2500000. | U D |
| 591-78-6----- | 2-Hexanone | 2500000. | U D |
| 108-10-1----- | 4-Methyl-2-pentanone_(MIBK) | 2500000. | U D |
| 108-05-4----- | Vinyl Acetate | 2500000. | U D |
| 74-83-9----- | Bromomethane | 500000. | U D |
| 75-00-3----- | Chloroethane | 500000. | U D |
| 110-75-8----- | 2-Chloroethyl_Vinyl_Ether | 500000. | U D |
| 74-87-3----- | Chloromethane | 500000. | U D |
| 75-71-8----- | Dichlorodifluoromethane | 500000. | U D |
| 75-69-4----- | Trichlorofluoromethane | 500000. | U D |
| 75-01-4----- | Vinyl Chloride | 500000. | U D |
| 108-86-1----- | Bromobenzene | 250000. | U D |
| 75-97-5----- | Bromochloromethane | 250000. | U D |
| 75-27-4----- | Bromodichloromethane | 250000. | U D |
| 75-25-2----- | Bromoform | 250000. | U D |
| 104-51-8----- | n-Butylbenzene | 250000. | U D |
| 135-98-8----- | sec-Butylbenzene | 250000. | U D |
| 98-06-6----- | tert-Butylbenzene | 250000. | U D |
| 75-15-0----- | Carbon Disulfide | 5000000. | U D |
| 56-23-5----- | Carbon Tetrachloride | 250000. | U D |
| 108-90-7----- | Chlorobenzene | 250000. | U D |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
 D - The result is from a diluted sample.
 B - The compound was found in the method blank.

VOLATILE ORGANICS ANALYSIS DATA SHEET
EPA METHOD 8260

Lab Name: Maxim Technologies, Inc.
 Lab Code: 05-17 Dallas
 Matrix: (soil/water) Water
 Sample wt/vol: 0.01 (g/mL) ml
 Level: (low/med) Low
 Dilution Factor: 100
 % Moisture: 100

Lab Number: D609044-07W
 Client: TNRCC
 Sample ID: SAMPLE #7
 Lab File ID: >AT777
 Date Received: 09/12/96
 Date Analyzed: 9/20/96

| CAS NO. | COMPOUND | CONCENTRATION UNITS: | |
|-----------------|-----------------------------|----------------------|------|
| | | (ug/L or ug/Kg) | ug/L |
| 124-48-1----- | Chlorodibromomethane | 250000. | U D |
| 67-66-3----- | Chloroform | 250000. | U D |
| 95-49-8----- | 2-Chlorotoluene | 250000. | U D |
| 106-43-4----- | 4-Chlorotoluene | 250000. | U D |
| 96-12-8----- | 1,2-Dibromo-3-chloropropane | 250000. | U D |
| 106-93-4----- | 1,2-Dibromoethane | 250000. | U D |
| 74-95-3----- | Dibromomethane | 250000. | U D |
| 95-50-1----- | 1,2-Dichlorobenzene | 250000. | U D |
| 541-73-1----- | 1,3-Dichlorobenzene | 250000. | U D |
| 106-46-7----- | 1,4-Dichlorobenzene | 250000. | U D |
| 110-57-6----- | 1,4-Dichloro-2-butene | 250000. | U D |
| 75-34-3----- | 1,1-Dichloroethane | 250000. | U D |
| 107-06-2----- | 1,2-Dichloroethane | 250000. | U D |
| 75-35-4----- | 1,1-Dichloroethene | 250000. | U D |
| 78-87-5----- | 1,2-Dichloropropane | 250000. | U D |
| 156-59-2----- | cis-1,2-Dichloroethene | 250000. | U D |
| 156-60-5----- | trans-1,2-Dichloroethene | 250000. | U D |
| 78-87-5----- | 1,2-Dichloropropane | 250000. | U D |
| 142-28-9----- | 1,3-Dichloropropane | 250000. | U D |
| 594-20-7----- | 2,2-Dichloropropane | 250000. | U D |
| 563-58-6----- | 1,1-Dichloropropene | 250000. | U D |
| 10061-01-5----- | cis-1,3-Dichloropropene | 250000. | U D |
| 10061-02-6----- | trans-1,3-Dichloropropene | 250000. | U D |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
 D - The result is from a diluted sample.
 R - The compound was found in the method blank.

VOLATILE ORGANICS ANALYSIS DATA SHEET
EPA METHOD 8260

Lab Name: Maxim Technologies, Inc.
Lab Code: 05-17 Dallas
Matrix: (soil/water) Water
Sample wt/vol: 0.01 (g/mL) ml
Level: (low/med) Low
Dilution Factor: 100
% Moisture: 100

Lab Number: D609044-07W
Client: TNRCC
Sample ID: SAMPLE #7
Lab File ID: >AT777
Date Received: 09/12/96
Date Analyzed: 9/20/96

| CAS NO. | COMPOUND | CONCENTRATION UNITS: (ug/L or ug/Kg) ug/L | Q |
|---------|----------|--|---|
|---------|----------|--|---|

| | | |
|--|---------|-----|
| 97-63-2-----Ethyl Methacrylate | 250000. | U D |
| 87-68-3-----Hexachlorobutadiene | 250000. | U D |
| 98-82-8-----Isopropyl benzene (Cumene) | 250000. | U D |
| 99-87-6-----4-Isopropyltoluene | 250000. | U D |
| 75-09-2-----Methylene Chloride | 250000. | U D |
| 91-20-3-----Naphthalene | 250000. | U D |
| 103-65-1-----n-Propylbenzene | 250000. | U D |
| 100-42-5-----Styrene | 250000. | U D |
| 630-20-6-----1,1,1,2-Tetrachloroethane | 250000. | U D |
| 79-34-5-----1,1,2,2-Tetrachloroethane | 250000. | U D |
| 127-18-4-----Tetrachloroethene | 250000. | U D |
| 87-61-6-----1,2,3-Trichlorobenzene | 250000. | U D |
| 120-82-1-----1,2,4-Trichlorobenzene | 250000. | U D |
| 71-55-6-----1,1,1-Trichloroethane | 250000. | U D |
| 79-00-5-----1,1,2-Trichloroethane | 250000. | U D |
| 79-01-6-----Trichloroethene | 250000. | U D |
| 96-18-4-----1,2,3-Trichloropropane | 250000. | U D |
| 95-63-6-----1,2,4-Trimethylbenzene | 250000. | U D |
| 108-67-8-----1,3,5-Trimethylbenzene | 250000. | U D |
| 71-43-2-----Benzene | 250000. | U D |
| 100-41-4-----Ethylbenzene | 250000. | U D |
| 108-88-3-----Toluene | 250000. | U D |
| 133-02-7-----Xylene (total) | 250000. | U D |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
D - The result is from a diluted sample.
B - The compound was found in the method blank.

VOLATILE ORGANICS ANALYSIS DATA SHEET
EPA METHOD 8260

Lab Name: Maxim Technologies, Inc.
 Lab Code: 05-17 Dallas
 Matrix: (soil/water) Soil
 Sample wt/vol: 0.5 (g/mL) G
 Level: (low/med) Low
 Dilution Factor: 200
 % Moisture: 1

Lab Number: D609044-07S
 Client: TNRCC
 Sample ID: SAMPLE #7
 Lab File ID: >AT782
 Date Received: 09/12/96
 Date Analyzed: 9/20/96

| CAS NO. | COMPOUND | CONCENTRATION UNITS: | |
|---------------|-----------------------------|----------------------|-------|
| | | (ug/L or ug/Kg) | ug/Kg |
| 67-64-1----- | Acetone | 200000. | U D |
| 78-93-3----- | 2-Butanone_(MEK) | 200000. | U D |
| 107-02-8----- | Acrolein | 100000. | U D |
| 107-13-1----- | Acrylonitrile | 100000. | U D |
| 591-78-6----- | 2-Hexanone | 100000. | U D |
| 108-10-1----- | 4-Methyl-2-pentanone_(MIBK) | 100000. | U D |
| 108-05-4----- | Vinyl Acetate | 100000. | U D |
| 74-83-9----- | Bromomethane | 20000. | U D |
| 75-00-3----- | Chloroethane | 20000. | U D |
| 110-75-8----- | 2-Chloroethyl Vinyl Ether | 20000. | U D |
| 74-87-3----- | Chloromethane | 20000. | U D |
| 75-71-8----- | Dichlorodifluoromethane | 20000. | U D |
| 75-69-4----- | Trichlorofluoromethane | 20000. | U D |
| 75-01-4----- | Vinyl Chloride | 20000. | U D |
| 108-86-1----- | Bromobenzene | 10000. | U D |
| 75-97-5----- | Bromochloromethane | 10000. | U D |
| 75-27-4----- | Bromodichloromethane | 10000. | U D |
| 75-25-2----- | Bromoform | 10000. | U D |
| 104-51-8----- | n-Butylbenzene | 10000. | U D |
| 135-98-8----- | sec-Butylbenzene | 10000. | U D |
| 98-06-6----- | tert-Butylbenzene | 10000. | U D |
| 75-15-0----- | Carbon Disulfide | 200000. | U D |
| 56-23-5----- | Carbon Tetrachloride | 10000. | U D |
| 108-90-7----- | Chlorobenzene | 10000. | U D |

NOTE: U - Compound analyzed for but not detected. The reported value is the minimum attainable detection limit for the sample.
 D - The result is from a diluted sample.
 B - The compound was found in the method blank.

Reference 23

facsimile
TRANSMITTAL

to: Gary Guerra
fax #: 214-665-7449
re: Jim Miller Landfill Information
date: April 29, 1997
pages: 8, including this cover sheet.

Attached is a copy of the laboratory analysis that you had requested from Mark Duebner with the City Manager's Office on April 29, 1997.

The samples were collected by John Andrus with EmTech Environmental Services, Inc. on March 22, 1997. The samples were taken:

- upstream of the discharge point from the landfill.
- at the discharge point from the landfill (effluent).
- downstream of the discharge point from the landfill.

Armstrong Forensic Laboratory, Inc. performed the analysis.

Please let me know if you need any additional information.

SOWA contact:

From the desk of...

Mike Pichman
Distribution Division Manager
Dallas Water Utilities
4120 Scottsdale
Dallas, TX 75227

214-670-8007
Fax 214-670-8034

RONE ENGINEERS, INC.

11234 Goodnight Lane
Dallas, Texas 75229
Tel. 972/241-4517
Metro: 972/263-1555
Fax. 972/241-5174

TO: Mike Richman, Dist. Dir. Mgr.
COMPANY: City of Dallas - Dallas Water Utilities
FAX NO: (214) 670-8034
SUBJECT: Water Samples - Landfill Fire Project.
FROM: Douglas Cargy
DATE: 4-4-97
COMMENTS: Results indicate only one (1) analysis
slightly elevated. Sample #4 Benzene.
State limit is 5.0 ppb.

NUMBER OF PAGES SENT INCLUDING THIS ONE: 7

Geotechnical, Environmental, Remediation, Subsurface Investigation, Laboratory Analysis,
Project Design, Water Resources, and Building Sciences Professionals

200 398d 4215 142 712

80:01 25:7 8d0

04/03/97 THU 16:16 FAX 917 332 8015

EMTECH OPS

0172751803

Q002

P.01

Armstrong Forensic Laboratory, Inc.

330 Lock's Green Trail Arlington, Texas 76012 (817)273-2691

Andrew T. Armstrong, Ph.D.
John M. Corn, MS

April 2, 1997

EmTech Environmental Services, Inc.
303 Arthur Street
Fort Worth, TX 76107

Received: March 22, 1997
Submitted: 8 Waters
Project: F94031J

Site: Rone Engineering
City of Dallas
Dallas, TX

LABORATORY REPORT: 97EN1462

Sample No: 1
Client ID: U-01, Upstream 01
Sample Type: Water

TOTAL METALS: RCRA Series

| Test Requested | Results ppm(mg/l) | Det. Limits ppm(mg/l) | Method EPA |
|----------------|-------------------|-----------------------|------------|
| Arsenic | bdl | 0.01 | EPA 8010 |
| Barium | 0.085 | 0.001 | EPA 8010 |
| Cadmium | bdl | 0.001 | EPA 8010 |
| Chromium | 0.013 | 0.001 | EPA 8010 |
| Lead | 0.014 | 0.002 | EPA 8010 |
| Mercury | bdl | 0.0007 | EPA 7470 |
| Selenium | bdl | 0.01 | EPA 8010 |
| Silver | 0.005 | 0.002 | EPA 8010 |

bdl - below detection limit

008:3988 2115 142 712
214 241 5174 PAGE 003

04/03/97 THU 16:17 FAX 317 332 3015

EMTECH OPS

20:01 75. 7 265

0003

P. 02

Armstrong Forensic Laboratory, Inc.
Report 07EN1462
Page 2

Sample No: 2
Client ID: 11-02, Upstream 02
Sample Type: Water

RCRA VOLATILE ORGANICS: EPA Method 8015

| Organic Compound | Results ppb(ug/l) | Det. Limits ppb(ug/l) |
|----------------------|----------------------|--------------------------|
| Benzene | bdl | 0.2 |
| Carbon tetrachloride | bdl | 5.0 |
| Chlorobenzene | bdl | 0.3 |
| Chloroform | bdl | 3.0 |
| 1,4-Dichlorobenzene | bdl | 0.4 |
| 1,2-Dichloroethane | bdl | 0.8 |
| 1,1-Dichloroethylene | bdl | 1.0 |
| Methyl ethyl ketone | bdl | 3.0 |
| Tetrachloroethylene | bdl | 1.0 |
| Trichloroethylene | bdl | 1.0 |
| Vinyl chloride | bdl | 50. |

bdl - below detection limit

000-3988 0215 172 012

62:21 25. 4 8dB

04/03/97 THU 16:17 FAX 917 332 3015

EMTECH OPS

0004

P.03

Armstrong Forensic Laboratory, Inc.
Report 97EN1462
Page 3

Sample No: 3
Client ID: E-01, Effluent 01
Sample Type: Water

TOTAL METALS: RCRA Series

| Test Requested | Results ppm(mg/l) | Det. Limits ppm(mg/l) | Method EPA |
|----------------|-------------------|-----------------------|------------|
| Arsenic | bdl | 0.01 | EPA 8010 |
| Barium | 0.094 | 0.001 | EPA 8010 |
| Cadmium | bdl | 0.001 | EPA 8010 |
| Chromium | 0.005 | 0.001 | EPA 8010 |
| Lead | 0.007 | 0.002 | EPA 8010 |
| Mercury | bdl | 0.0007 | EPA 7470 |
| Selenium | bdl | 0.01 | EPA 8010 |
| Silver | 0.006 | 0.002 | EPA 8010 |

bdl - below detection limit

S20'398d 7215 172 712

62'31 25. 7 844

04/03/97 THU 15:17 FAX 817 332 8015 ENTER OPS
CO. ARMSTRONG LAB

8172751883

2005
P. 24

Armstrong Forensic Laboratory, Inc.
Report 97EN1462
Page 4

Sample No: 4
Client ID: E-02, Effluent 02
Sample Type: Water

RCRA VOLATILE ORGANICS: EPA Method 8015

| Organic Compound | Results ppb(ug/l) | Det. Limits ppb(ug/l) |
|----------------------|----------------------|--------------------------|
| Benzene * | 7.1 * | 0.2 |
| Carbon tetrachloride | bdl | 5.0 |
| Chlorobenzene | bdl | 0.3 |
| Chloroform | bdl | 3.0 |
| 1,4-Dichlorobenzene | bdl | 0.4 |
| 1,2-Dichloroethane | bdl | 0.8 |
| 1,1-Dichloroethylene | bdl | 1.0 |
| Methyl ethyl ketone | bdl | 3.0 |
| Tetrachloroethylene | bdl | 1.0 |
| Trichloroethylene | bdl | 1.0 |
| Vinyl chloride | bdl | 50 |

bdl - below detection limit

214 241 5124 PAGE 005

APR 4 '97 12:10

04/03/97 THU 16:17 FAX 817 332 8015

EMTECH OPS

ARMSTRONG LAB

0172751885

0006

P.05

Armstrong Forensic Laboratory, Inc.
Report 97EN1462
Page 5

Sample No: 5
Client ID: D-01, Downstream 01
Sample Type: Water

TOTAL METALS: RCRA Series

| Test Requested | Results ppm(mg/l) | Det. Limits ppm(mg/l) | Method EPA |
|----------------|-------------------|-----------------------|------------|
| Arsenic | bdl | 0.01 | EPA 6010 |
| Barium | 0.037 | 0.001 | EPA 6010 |
| Cadmium | bdl | 0.001 | EPA 6010 |
| Chromium | 0.002 | 0.001 | EPA 6010 |
| Lead | bdl | 0.002 | EPA 6010 |
| Mercury | bdl | 0.0007 | EPA 7470 |
| Selenium | bdl | 0.01 | EPA 6010 |
| Silver | bdl | 0.002 | EPA 6010 |

bdl - below detection limit

214 241 5174 PAGE.008

01:01 26. 7 848

04/03/97 THU 16:13 FAX 317 332 3015 SUTECH OPS

3172751283

007
P.06


Armstrong Forensic Laboratory, Inc.
Report 97EN1462
Page 6

Sample No: 6
Client ID: D-02, Downstream 02
Sample Type: Water

RCRA VOLATILE ORGANICS: EPA Method 8015

| Organic Compound | Results ppb(ug/l) | Det. Limits ppb(ug/l) |
|----------------------|----------------------|--------------------------|
| Benzene | bdl | 0.2 |
| Carbon tetrachloride | bdl | 5.0 |
| Chlorobenzene | bdl | 0.3 |
| Chloroform | bdl | 3.0 |
| 1,4-Dichlorobenzene | bdl | 0.4 |
| 1,2-Dichloroethane | bdl | 0.6 |
| 1,1-Dichloroethylene | bdl | 1.0 |
| Methyl ethyl ketone | bdl | 3.0 |
| Tetrachloroethylene | bdl | 1.0 |
| Trichloroethylene | bdl | 1.0 |
| Vinyl chloride | bdl | 50. |

bdl - below detection limit


Joe Sikes, Director, Quality Control
AIHA Accreditation No: 363
AIHA ELLAP Accredited
revised 97-1462.doc/bf

Reference 24

12/14/91 C. J. Deen

United States
Environmental Protection
Agency

Solid Waste and
Emergency Response

EPA 540-F-94-028
OSWER 9285.7-14FS
PB94-963311
November 1996



Using Qualified Data to Document an Observed Release and Observed Contamination

Office of Emergency and Remedial Response (5204G)

Quick Reference Fact Sheet

This fact sheet discusses the use of the U.S. Environmental Protection Agency's (EPA) Contract Laboratory Program (CLP) data and other sources of data qualified with a "J", "U", or "UJ" qualifier or flag. This guidance provides a management decision tool for the optional use of qualified data to document an observed release and observed contamination by chemical analysis under EPA's Hazard Ranking System (HRS). The analyte and sample matrix (i.e., soil or water) specific adjustment factors given in this fact sheet allow biased CLP and non-CLP data to be adjusted to meet the HRS criteria for documenting an observed release and observed contamination with data that are of known and documented quality. This fact sheet does not address using qualified data for identifying hazardous substances in a source.

INTRODUCTION

The EPA established the HRS to rank hazardous waste sites for National Priorities List (NPL) purposes under the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (CERCLA) as amended by the Superfund Amendments and Reauthorization Act of 1986 (SARA). This fact sheet was developed in response to a need to determine the usability of qualified data for site assessment and HRS scoring purposes. This fact sheet illustrates that qualified data are often of sufficiently known and documented quality, and may be used in establishing an observed release and observed contamination. This fact sheet explains the rationale for why some qualified data may be used for HRS purposes; presents the background information needed to use qualified data with and without adjustment factors; provides examples of qualified data use; and discusses issues raised during the development of the adjustment factor approach.

Under the HRS, chemical analytical data are often used to demonstrate an observed release and observed contamination when the release sample concentration is three times the background concentration and background levels are greater than or equal to the

appropriate detection limit; or if the release sample concentration is greater than or equal to the appropriate quantitation limit when background levels are below the appropriate detection limit. The release must also be at least partially attributable to the site under investigation (*Hazard Ranking System, Final Rule*, 40 CFR Part 300, App. A). The data used to establish the release must be of known and documented quality. (*Hazard Ranking System Guidance Manual*, Interim Final, November 1992, OSWER Directive 9345.1-07). Data that cannot be validated may not be of known and documented quality. For more information on observed release and observed contamination, refer to the fact sheets: *Establishing an Observed Release*, September 1995, PB94-963314; *Establishing Areas of Observed Contamination*, September 1995, PB94-963312; and *Establishing Background Levels*, September 1995, PB94-963313. The factor of three represents the minimum difference in sample results that demonstrate an increase in contaminant concentration above background levels, with reasonable confidence.

Although much of the analytical data used for identifying an observed release is generated under EPA's CLP, this fact sheet applies to all data regardless of the source of the data (non-CLP data). EPA procedures require that

CLP analytical data be reviewed, or validated by EPA or third party reviewers, to ensure the data are of known and documented quality and that the determination be discussed in a data validation report that accompanies the analytical results. Based on this data validation, CLP data are classified into three categories: (1) data for which all quality control (QC) requirements have passed contract-required acceptance criteria; (2) data for which at least one QC requirement has not met acceptance criteria; and (3) data for which most or all QC requirements have not met acceptance criteria. Data in the first category typically are not qualified. Data in the second category are often qualified with a "J" qualifier and, as discussed in this fact sheet, are usually usable for HRS purposes. Data in the third category are usually qualified by an "R" qualifier and are not usable for HRS purposes.

Whether data are placed into the second or third category is determined by the amount of bias associated with the analytical results. Data validation evaluates biases resulting from laboratory analytical deficiencies or sample matrices to determine whether the data are usable. Bias indicates that the reported concentration is either higher or lower than the true concentration, and the data validation report identifies the direction of the bias or if the bias is unknown.

The EPA CLP also sets minimum quantitation limits for all analytes; the Contract Required Quantitation Limit (CRQL) for organic analytes and the Contract Required Detection Limit (CRDL) for inorganic analytes. For HRS purposes and for this fact sheet, the term CRQL refers to both the contract required quantitation limit and the contract required detection limit. (40 CFR Part 300, App. A). The CRQLs are substance specific levels that a CLP laboratory must be able to routinely and reliably detect in specific sample matrices (i.e., soil, water, sediment). The CRQLs are usually set above most instrument detection limits (IDLs) and method detection limits (MDLs).

CONSIDERATIONS FOR NON-CLP DATA

Because various laboratories and analytical methods may be used to develop non-CLP data, the following list provides the general information sufficient for determining whether non-CLP data are usable for HRS purposes.

- (1) Identification of the method used for analysis. Methods include RCRA methods, SW-846, EPA methods, etc.
- (2) Quality control (QC) data. Check each method of analysis to determine if specific QC requirements are defined. If not, seek out another method.
- (3) Instrument-generated data sheets for sample results. These data sheets would be the equivalent of Form I's in CLP data.
- (4) MDLs and sample quantitation limits (SQLs). The analytical method should provide the MDL. The SQL is an adjusted MDL using sample specific measurements such as percent moisture and weight.
- (5) Data validation report.

USE OF BIASED QUALIFIED DATA

In the past, all qualified data have been inappropriately perceived by some people as data of low confidence or poor quality and have not been used for HRS evaluation. With careful assessment of the nature of the analytical biases or QC deficiencies in the data on a case-by-case basis, qualified data can represent an additional resource of data for establishing an observed release. Further, the D.C. District Court of Appeals in 1996 upheld EPA's case-by-case approach to assess data quality. In reviewing the use of qualified data to identify an observed release, the Court stated that if there are deficiencies in the data, "...the appropriate response is to review the deficiencies on a 'case-by-case basis' to determine their impact on 'usability of the data.'" The Court also stated with regards to data quality that, "...EPA does not face a standard of absolute perfection....Rather, it is statutorily required to 'assure, to the maximum extent feasible,' that it 'accurately assesses the relative degree of risk' posed by sites" [*Board of Regents of the University of Washington, et al., v. EPA*, No. 95-1324, slip op. at 8-10 (D.C. Cir. June 25, 1996).]

As discussed in this fact sheet, the application of adjustment factors to "J" qualified data can serve as a management decision tool to "adjust," or take into account, the analytical uncertainty in the data indicated by the qualifier, thereby making qualified data usable for HRS evaluation. The use of adjustment factors to account for the larger uncertainty in "J" qualified data is a conservative approach enabling a quantitative comparison of the data for use in documenting an observed release. It should be noted that the use of

adjustment factors only addresses analytical variability and does not take into account variabilities which may be introduced during field sampling. Some guidelines for using the adjustment factor approach are discussed in Exhibit 1.

CLP QA/QC PROCEDURES

CLP qualifiers are applied to analytical data based on the results of various Quality Assurance/Quality Control (QA/QC) procedures used at the laboratory. EPA analytical methods use a number of QA/QC mechanisms during sample analysis in order to assess qualitative and quantitative accuracy (*Contract Laboratory Program Statement of Work for Inorganic Analyses*, Document No. ILM02.0; *Contract Laboratory Program Statement of Work for Organic Analyses*, Document No. OLM1.8; *Quality Assurance/Quality Control Samples*, Environmental Response Team Quality Assurance Technical Information Bulletin; *Test Methods for Evaluating Solid Waste (SW-846): Physical and Chemical Methods*, Document No. SW-846). To assess data quality, the laboratory uses matrix spikes, matrix spike duplicates, laboratory control samples, surrogates, blanks, laboratory duplicates, and quarterly blind performance evaluation (PE) samples. The Agency assumes that if biases are found in the QA/QC samples, the field sample concentrations may also be biased.

Surrogates are chemically similar to the analytes of interest. They are added or "spiked" at a known concentration into the field samples before analysis. Also, selected target analytes are "spiked" into samples at a specified frequency to assess potential interferences from the sample matrix. These samples are called matrix spikes. Comparison of the known concentration of the surrogates and matrix spikes with their actual analytical results reflects the analytical accuracy. Because the surrogates are expected to behave similarly to the target analytes, they may indicate bias caused by interferences from the sample matrices. These types of interferences from the sample matrix are known as matrix effects (*CLP National Functional Guidelines for Inorganic Data Review*, Publication 9240.1-05-01; *CLP National Functional Guidelines for Organic Data Review*, Publication 9240.1-05; *Test Methods for Evaluating Solid Waste (SW-846): Physical and Chemical Methods*, Document No. SW-846).

Laboratory control samples are zero blind samples which contain known concentrations of specific analytes and are

analyzed in the same batch as field samples. Their results are used to measure laboratory accuracy. Blanks are analyzed to detect any extraneous contamination introduced either in the field or in the laboratory.

Laboratory duplicates are created when one sample undergoes two separate analyses. The duplicate results are compared to determine laboratory precision. Quarterly blind PE samples are single blind samples that evaluate the laboratory's capability of performing the specified analytical protocol.

CLP and other EPA analytical methods include specifications for acceptable analyte identification, target analytes, and minimum and maximum percent recovery of the QA/QC compounds. Data are validated according to guidelines which set performance criteria for instrument calibration, analyte identification, and identification and recovery of QA/QC compounds (*CLP Statement of Work and SW-846*). The *National Functional Guidelines for Data Review*, used in EPA validation, was designed for the assessment of data generated under the CLP organic and inorganic analytical protocols (*CLP Statement of Work; National Functional Guidelines for Data Review*). The guidelines do not preclude the validation of field and other non-CLP data. Thus, many EPA Regions have also adapted the *National Functional Guidelines for Data Review* to validate non-CLP data. Data which do not meet the guidelines' performance criteria are qualified to indicate bias or QA/QC deficiencies. The data validation report usually explains why the data were qualified and indicates the bias direction when it can be determined. Validated data that are not qualified are considered unbiased and can be used at their reported numerical value for HRS evaluation.

QUALIFIER DEFINITIONS

Most EPA validation guidelines use the data qualifiers presented in Exhibit 2 (*CLP National Functional Guidelines for Data Review*). Other qualifiers besides these may be used; the validation report should always be checked for the exact list of qualifiers and their meanings.

It should be emphasized that not meeting one or some of the contract required QA/QC acceptance criteria is often an indication that the sample was difficult to analyze, not that there is low confidence in the analysis (i.e., the

EXHIBIT 1
GUIDELINES FOR THE USE OF ADJUSTMENT FACTORS

- The use of adjustment factors identified in this fact sheet is a management tool for the optional use of "J" qualified data generated under CLP or other sources of data to document an observed release.
- Adjusted qualified data should be used with non-qualified data whenever possible.
- EPA maintains a "worst sites first" policy for placing sites on the NPL (*Additional Guidance on "Worst Sites" and "NPL Caliber Sites" to assist in SACM Implementation, OSWER Directive 9320.2-07*).
- EPA Regions should use adjustment factors with discretion on a case-by-case basis and should always carefully consider the use of qualified data in borderline cases.
- Resampling and/or reanalysis may be warranted if qualified data do not appear adequate to document an observed release.
- EPA Regions may substitute higher adjustment factors based on documented, justifiable reasons but may never use a lower adjustment factor value.
- The adjustment factors should only be applied to analytes listed in the tables. These adjustment factors should not be interpolated or extrapolated to develop factors for analytes not listed in the tables.
- The adjustment factors apply only to "J" qualified data above the CRQL.
- Detection below the CRQL is treated as non-quantifiable for HRS purposes.
- "UJ" data may be used under strict circumstances as explained in this fact sheet.
- The adjustment factors only apply to biased "J" qualified data, not to other "J" qualified data.
- The adjustment factors do not apply to "N", "NJ", or "R" qualified data. These data can not be used to document an observed release for HRS purposes.

analysis is "under control" and can be adequate for HRS decision making). Often "J", "U", and "UJ" qualified data fall into this category.

There are instances when qualified data cannot be used since the uncertainty of the results is unknown. For example, violations of laboratory instrument calibration and tuning requirements, and gross violations of holding times reflect the possibility that the results are of unknown quality (i.e., the analysis is "out of control"). Most often these data would be qualified with an "R" or an "N" (not usable for HRS purposes).

USING "U" QUALIFIED DATA

The "U" qualifier simply means that the reported concentration of the analyte was at or below the CRQL—there can be confidence that the true concentration is at or below the quantitation limit. Therefore, "U" qualified data can be used for establishing background

levels. If the release sample concentration is above this level, as specified in the HRS, an observed release can be established. The quantitation limit for that analyte could be used as a maximum background concentration if a more conservative background level seems appropriate.

USING "J" QUALIFIED DATA

As discussed previously, some "J" qualified data can be used in establishing an observed release if the uncertainty in the reported values is documented. Qualified data should always be carefully examined by the Regions to determine the reasons for qualification before use in HRS evaluation. Resampling and/or reanalysis may be warranted if qualified data only marginally document an observed release. Whenever possible, qualified data should be used in conjunction with non-qualified data.

As described in Exhibit 2, "J" qualified data indicates that bias has been detected in the sample analysis and although the analyte is definitively present, the reported concentration is an estimate. Depending on the reasons and the direction of bias, with the use of adjustment factors, "J" qualified data can represent data of known and documented quality sufficient for use in establishing an observed release and observed contamination under the HRS.

USING "UJ" QUALIFIED DATA

A combination of the "U" and "J" qualifiers indicates that the reported value may not accurately represent the concentration necessary to positively detect the analyte in the sample. Under limited conditions, "UJ" qualified data can be used to represent background concentrations for establishing an observed release. These conditions are: instances when there is confidence that the background concentration is not detectable above the CRQL, the background concentration is biased high, and the sample measurement establishing the observed release equals or exceeds the CRQL.

DIRECTION OF BIAS IN "J" QUALIFIED DATA

It is important to understand the direction of bias associated with "J" qualified data before using the data to document an observed release. Qualified data may have high, low, or unknown bias. A low bias means that the reported concentration is likely an underestimate of the true concentration. For example, data may be biased low when sample holding times for volatile organic compounds (VOCs) are moderately exceeded or when recovery of QA/QC compounds is significantly less than the amount introduced into the sample. Low surrogate recovery would also indicate a low bias. A high bias means the reported concentration is likely an overestimate of the true concentration. For example, data may be biased high when recovery of QA/QC compounds is significantly higher than the amount in the sample. A bias is unknown when it is impossible to ascertain whether the concentration is an overestimate or an underestimate. For example, an unknown bias could result when surrogate recoveries exceed method recovery criteria and matrix spike/matrix spike duplicate compounds below method recovery criteria fail the relative percent difference (RPD) criteria in the same sample.

Despite the bias, certain qualified data may be used without application of adjustment factors for determining

an observed release under certain circumstances. The following are examples of using "J" qualified data without adjustment factors:

- Low bias release samples are likely to be underestimates of true concentrations. If the reported concentration of a low bias release sample is three times above unbiased background levels, these release samples would still meet the HRS criteria. The true concentrations would still be three times above the background level.
- High bias background samples are likely to be overestimates of true concentrations. If the reported concentration of unbiased release samples are three times above the reported background concentration, they would still meet the HRS observed release criteria because they would still be three times above the true background concentration.

The above examples show that both low bias "J" qualified release samples at their reported concentrations and high bias "J" qualified background samples may be used at their reported concentrations in these situations.

High bias release samples may not be used at their reported concentrations because they are an overestimate of true concentrations in this situation; resampling and/or re-analysis of the release samples should be considered. The true difference in the background and release concentrations may be less than the HRS criteria for establishing an observed release. The reported concentration for low bias background concentrations may not be compared to release samples because it is most likely an underestimate of background level; the release sample concentration may not significantly exceed the true background concentration. However, in lieu of re-sampling and/or re-analysis, high bias release data and low bias background data may be used with adjustment factors which compensate for the probable uncertainty in the analyses.

ADJUSTMENT FACTORS FOR BIASED "J" QUALIFIED DATA

Applying adjustment factors to "J" qualified data will enable EPA to be more confident that the increase in contaminant concentrations between the background and

| EXHIBIT 2 EPA CLP DATA QUALIFIERS AND THEIR USABILITY FOR DOCUMENTING AN OBSERVED RELEASE | |
|---|---|
| Usable* | Not Usable |
| <p>"U" The substance or analyte was analyzed for, but no quantifiable concentration was found at or above the CRQL (<i>CLP National Functional Guidelines for Data Review</i>).</p> | <p>"N" The analysis indicates the presence of an analyte for which there is presumptive evidence to make a "tentative identification" (<i>CLP National Functional Guidelines for Data Review</i>).</p> |
| <p>"J" The analyte was positively identified—the associated numerical value is the approximate concentration of the analyte in the sample. The "J" qualifier indicates that one or more QA/QC requirements have not met contract required acceptance criteria, but the instrumentation was functioning properly during the analysis. For example, a "J" qualifier may indicate that the sample was difficult to analyze or that the value may lay near the low end of the linear range of the instrument. "J" data are considered biased, but provide definitive analyte identification (<i>CLP National Functional Guidelines for Data Review</i>).</p> | <p>"R" The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet QC criteria. The presence or absence of the analyte can not be verified and the result has been rejected. A sample result may be qualified with an "R" qualifier when the instrument did not remain "in control" or the stability or sensitivity of the instrument were not maintained during the analysis (<i>CLP National Functional Guidelines for Data Review</i>).</p> |
| <p>"UJ" The analyte was not quantifiable at or above the CRQL. In addition to not being quantifiable, one or more QA/QC requirements have not met contract acceptance criteria (<i>CLP National Functional Guidelines for Data Review</i>).</p> | <p>"NJ" The analysis indicates the presence of the analyte that has been "tentatively identified" and the associated numerical value represents its approximate concentration (<i>CLP National Functional Guidelines for Data Review</i>).</p> |

* Usable under certain circumstances as explained in this fact sheet.

release samples is due to a release. The adjustment factors are applied as "safety factors" to compensate for analytical uncertainty, allowing biased data to be used for determining an observed release. Dividing the high bias result by an adjustment factor deflates it from the high end of the acceptable range towards a low bias value. Multiplying a low bias concentration by an adjustment factor inflates it to the high end of the acceptable range.

Tables 1 through 4 (pages 11 - 18) present analyte and matrix-specific adjustment factors to address the analytical uncertainty when determining an observed release using high bias release samples and low bias background data. The factors are derived from percent recoveries of matrix spikes, surrogates, and laboratory control samples in the CLP Analytical Results Database

(CARD) from January 1991 to March 1996. A total of 32,447 samples were reviewed for volatile organic analytes; 32,913 samples for semivolatile organic analytes; 59,508 samples for pesticides/PCB analytes; and 5,954 samples for inorganic analytes.

The range of CARD data for each analyte includes 97 percent of all percent recoveries in the database, discarding outliers. The adjustment factors are ratios of percent recovery values at the 98.5 and 1.5 percentiles. The ratios generally show a consistent pattern.

Adjustment factors have been determined for all analytes in the CLP Target Compound List (organic analytes) and Target Analyte List (inorganic analytes). A tiered approach was used to derive the organic adjustment factors. Percent recoveries for surrogates were

examined first, followed by matrix spike recoveries. When both matrix spike and surrogate data were available for the same analyte, the larger adjustment factor (representing more extreme high and low percent recoveries) was used. Laboratory control samples were used to calculate the inorganic adjustment factors. Quarterly blind sample data were not used to determine adjustment factors because of the small data set available. A default adjustment factor of 10 was used for analytes when percent recovery data were unavailable.

Adjustment factors do not correct the biased sample concentration to its true value, as such "correction" is not possible. CARD data do not differentiate and quantify individual sources of variation. Instead, the ratio of percentile used to develop adjustment factors represents a "worst-case" scenario. Adjustment factors either inflate background values to the high end of the range or deflate release data to the low end. Therefore, adjustment factors compensate or adjust for the apparent analytical variability when comparing a high bias value to a low bias value (see Exhibit 3).

USING THE ADJUSTMENT FACTORS

This section of the fact sheet demonstrates how adjustment factors can be used with "J" qualified data for HRS scoring purposes, including documentation and detection limit issues.

Documentation Requirements for Using Qualified Data

In using "J" qualified data to determine an observed release, include a discussion of "J" qualifiers from the data validation report and cite it as a reference in the site assessment report or HRS documentation record. If adjustment factors are applied to "J" qualified data, reference and cite this fact sheet. These steps will ensure that the direction of bias is documented and will demonstrate how biases have been adjusted.

Detection Limit Restrictions

Adjustment factors may only be applied to "J" qualified data with concentrations above the CLP CRQL for organics or CRDL for inorganics. "J" qualified data with concentrations below the CRQL can not be used to document an observed release except as specified in the previous section entitled "Using 'UJ' Qualified Data."

Application of Factors

Exhibit 3 shows how to apply the factors to "J" qualified data. Multiply low bias background sample results by

the analyte-specific adjustment factor or the default factor of 10 when an analyte-specific adjustment factor is not available. The resulting new background value effectively becomes a high bias value that may be used to determine an observed release. Divide high bias release sample data by the analyte-specific adjustment factor or the default factor of 10 when an analyte-specific adjustment factor is not available. The resulting new release sample value effectively becomes a low bias value that may be used to determine an observed release.

Note: High bias background data, low bias release data, and unbiased data may be used at their reported concentrations.

Note: Adjusted release and background values must still meet HRS criteria (e.g., release concentration must be at least three times above background level) to determine an observed release.

Examples Using Trichloroethene in Soil and Water

1. *Release water sample is unbiased, background water sample is unbiased but all data are qualified with a "J" due to an contractual laboratory error not analytical error.*

Background sample value: 12 $\mu\text{g/L}$ (J) no bias

Release sample value: 40 $\mu\text{g/L}$ (J) no bias

The CRQL for trichloroethene is 10 $\mu\text{g/Kg}$ for soil and 10 $\mu\text{g/L}$ for water.

In this example, the qualification of the data is not related to bias in the reported concentrations. Thus, using adjustment factors is not needed and an observed release is established if all other criteria are met.

2. *Release soil sample data is biased low, background soil sample data is biased high.*

Background sample value: 12 $\mu\text{g/Kg}$ (J) high bias

Release sample value: 40 $\mu\text{g/Kg}$ (J) low bias

In this example, the direction of bias indicates that the true release value may be higher and the true background value may be lower than reported values. The release sample concentration still exceeds background by more than three times, so an observed release is established, provided all other HRS criteria are met. Using adjustment factors is not needed.

EXHIBIT 3
USE OF ADJUSTMENT FACTORS FOR "J" QUALIFIED DATA

| Type of Sample | Type of Bias | Action Required |
|--------------------------|--------------|--|
| Background Sample | No Bias | None: Use concentration without factor |
| | Low Bias | Multiply concentration by factor |
| | High Bias | None: Use concentration without factor |
| | Unknown Bias | Multiply concentration by factor |
| Release Sample | No Bias | None: Use concentration without factor |
| | Low Bias | None: Use concentration without factor |
| | High Bias | Divide concentration by factor |
| | Unknown Bias | Divide concentration by factor |

3. *Release soil sample data is unbiased, background soil sample is biased low.*

Background sample value: 12 µg/Kg (J) *low bias*
Release sample value: 30 µg/Kg *no bias*

In this example, the true background value is assumed to be less than the reported value; however, an observed release may still be possible. To use the data to establish an observed release, multiply the background sample data value by the adjustment factor given for trichloroethene in soil (2.11). No adjustment factor is needed for the release sample.

New background sample value:
 $(12 \text{ µg/Kg}) \times (2.11) = 25.32 \text{ µg/Kg (J) high bias}$

The release sample concentration does not meet or exceed the new background level by three times, so an observed release is not established.

4. *Release water sample data is biased high, background water sample data is unbiased.*

Background sample value: 15 µg/L *no bias*
Release sample value: 70 µg/L (J) *high bias*

In this example, the true release value may be lower than the reported value; however, an observed release may still be possible. To use the data to establish an observed release, divide the release sample by the adjustment factor for trichloroethene in water (1.66).

No adjustment factor is needed for the background sample.

New release sample value:
 $(70 \text{ µg/L}) \div (1.66) = 42.17 \text{ µg/L (J) low bias}$

The new release sample concentration does not meet or exceed the background level by three times, so an observed release is not established.

5. *Release soil sample data has unknown bias; background soil sample data has unknown bias.*

The following example is the most conservative approach to using adjustment factors with qualified data.

Background sample value: 20 µg/Kg (J) *unknown bias*
Release sample value: 325 µg/Kg (J) *unknown bias*

In this example, it is not possible to determine from the reported values if an observed release is possible. To use the data to establish an observed release, divide the release sample value and multiply the background sample value by the adjustment factor given for trichloroethene in soil (2.11).

New release sample value:
 $(325 \text{ µg/Kg}) \div (2.11) = 154.03 \text{ µg/Kg (J) low bias}$

New background sample value:
 $(20 \text{ µg/Kg}) \times (2.11) = 42.2 \text{ µg/Kg (J) high bias}$

The new release sample is at least three times the new background concentration, so an observed release is established, provided all other HRS criteria are met.

ISSUES WITH USING ADJUSTMENT FACTOR APPROACH

Some issues were raised regarding the application of adjustment factors to qualified data during the Agency's internal review process.

One issue is that "J" qualifiers are added to analytical results for many reasons that may or may not affect the accuracy and precision of the analytical result. The application of an adjustment factor to "J" qualified data in which bias is not affected could be considered overly conservative.

All qualified data should be carefully evaluated to determine if the data are biased. Based on the reasons for bias, the use of an adjustment factor should only be considered as a management tool that provides a quick screening of the data for site assessment, not a means for correcting the biased value to a true value. Application of adjustment factors are intended for use with qualified data reported at or above the CRQL and may not be applicable to data which are qualified but technically sound. As stated previously, qualified data should always be carefully reviewed on a case-by-case basis prior to use in HRS evaluation.

Another issue is the validity of "10" as a default adjustment factor. A default adjustment factor of 10 was a policy decision based on the range of adjustment factors and an industry approach. The default was chosen in order to account for the maximum variability regardless of the direction of the bias. Therefore, the default value of 10 is generally considered to be a conservative adjustment factor. EPA reviewed the use of the default value of 10 and determined that this value was conservative.

Even if using adjustment factors is sometimes overly conservative, this approach is preferable to not using the data at all. EPA maintains a "worst sites first" policy that only the sites considered most harmful to human health and/or the environment should be listed. EPA considers the use of adjustment factors appropriate as a management decision tool. However, discretion is needed when applying adjustment factors. The use of adjustment factors may not be appropriate in all cases.

USE OF OTHER ADJUSTMENT FACTORS

EPA Regions may substitute higher, but never lower, adjustment factor values for the ones listed in this fact sheet on a case-by-case basis when technically justified. For example, other adjustment factors may be applied to conform with site-specific Data Quality Objectives (DQOs) or with Regional Standard Operating Procedures (SOPs) (*Data Quality Objectives Process for Superfund*, Publication 9355.9-01).

SUMMARY

For site assessment purposes, EPA Regions should not automatically discard "J" qualified data. However, site-specific data usability determinations may result in the data's not being used.

Data qualified under the EPA's CLP or from other sources of validated data may be used to demonstrate an observed release if certain measures are taken to ensure that the bias of the data qualifier is adjusted using the factor approach specified in this fact sheet. (This fact sheet provides a management decision tool for making qualified data usable for documenting an observed release.) The analyte and matrix-specific adjustment factors provided in Tables 1 through 4 of this fact sheet present these adjustment factors.

The scope of this fact sheet is limited to the situations described in Exhibit 1. The use of qualified analytical data without the adjustment factors presented in this fact sheet is limited. Higher adjustment factors may be substituted by EPA Regions on a case-by-case basis when technically justified by site-specific DQOs or SOPs.

REFERENCES

1. U.S. Government Printing Office, *Federal Register*, Part II, Environmental Protection Agency, 40 CFR Part 300, Hazard Ranking System, Final Rule, December 14, 1990.
2. U.S. Environmental Protection Agency, *Hazard Ranking System Guidance Manual*, Office of Solid Waste and Emergency Response, PB92-963377, November 1992.
3. U.S. Environmental Protection Agency, 1995. *Establishing an Observed Release*. Office of Emergency and Remedial Response. PB94-963314.
4. U.S. Environmental Protection Agency, 1995. *Establishing Areas of Observed Contamination*. Office of Emergency and Remedial Response. PB94-963312.
5. U.S. Environmental Protection Agency, 1995. *Establishing Background Levels*. Office of Emergency and Remedial Response. PB94-963313.
6. U.S. Environmental Protection Agency, 1994. *CLP National Functional Guidelines for Inorganic Data Review*. Office of Solid Waste and Emergency Response. Publication 9240.1-05-01.
7. U.S. Environmental Protection Agency, 1993. *CLP National Functional Guidelines for Organic Data Review*. Office of Solid Waste and Emergency Response. Publication 9240.1-05.
8. U.S. Environmental Protection Agency, 1991. *Contract Laboratory Program Statement of Work for Inorganic Analysis*. Document No. ILM02.0.
9. U.S. Environmental Protection Agency, 1991. *Contract Laboratory Program Statement of Work for Organic Analysis*. Document No. OLM1.8.
10. U.S. Environmental Protection Agency, 1993. *Additional Guidance on "Worst Sites" and "NPL Caliber Sites" to Assist in SACM Implementation*. Office of Emergency and Remedial Response. PB94-963206.
11. *Board of Regents of the University of Washington, et al., v. EPA*, No. 95-1324, slip op. at 10 (D.C. Cir. June 25, 1996).10.
12. U.S. Environmental Protection Agency, 1991. *Guidance for Performing Preliminary Assessments Under CERCLA*. Office of Solid Waste and Emergency Response. Publication 9345.0-01-A.
13. U.S. Environmental Protection Agency, 1992. *Guidance for Performing Site Inspections Under CERCLA*. Office of Solid Waste and Emergency Response. PB92-963375.
14. U.S. Environmental Protection Agency, 1992. *Quality Assurance/Quality Control Samples*. Environmental Response Team Quality Assurance Technical Information Bulletin.
15. U.S. Environmental Protection Agency, 1986. *Test Methods for Evaluating Solid Waste (SW-846): Physical and Chemical Methods*. Office of Solid Waste and Emergency Response. Document No. SW-846.
16. U.S. Environmental Protection Agency, 1993. *Data Quality Objectives Process for Superfund*. Office of Emergency and Remedial Response. Publication 9355.9-01.

TABLE 1
FACTORS FOR VOLATILE ORGANIC ANALYTES

| VOLATILE ORGANIC ANALYTES | SOIL MATRIX | | WATER MATRIX | |
|---------------------------------|--|--------|---------------------------------------|--------|
| | Number of CARD Samples Reviewed | Factor | Number of CARD Samples Reviewed | Factor |
| 1,1,1-TRICHLOROETHANE | — | 10.0 | — | 10.0 |
| 1,1,2,2-TETRACHLOROETHANE | — | 10.0 | — | 10.0 |
| 1,1,2-TRICHLOROETHANE | — | 10.0 | — | 10.0 |
| 1,1-DICHLOROETHANE | — | 10.0 | — | 10.0 |
| 1,1-DICHLOROETHENE | 7,031 | 2.71 | 5,015 | 2.35 |
| 1,2-DICHLOROETHANE-D4 | 32,446 | 1.52 | 25,516 | 1.38 |
| 1,2-DICHLOROETHENE (TOTAL) | — | 10.0 | — | 10.0 |
| 1,2-DICHLOROPROPANE | — | 10.0 | — | 10.0 |
| 2-BUTANONE | — | 10.0 | — | 10.0 |
| 2-HEXANONE | — | 10.0 | — | 10.0 |
| 4-METHYL-2-PENTANONE | — | 10.0 | — | 10.0 |
| ACETONE | — | 10.0 | — | 10.0 |
| BENZENE | 7,024 | 1.97 | 5,001 | 1.64 |
| BROMODICHLOROMETHANE | — | 10.0 | — | 10.0 |
| BROMOFORM | — | 10.0 | — | 10.0 |
| BROMOFLUOROBENZENE | 32,444 | 1.7 | 25,518 | 1.26 |
| BROMOMETHANE | — | 10.0 | — | 10.0 |
| CARBON DISULFIDE | — | 10.0 | — | 10.0 |

TABLE 1
FACTORS FOR VOLATILE ORGANIC ANALYTES

| VOLATILE ORGANIC ANALYTES | SOIL MATRIX | | WATER MATRIX | |
|---------------------------------|--|--------|---------------------------------------|--------|
| | Number of CARD Samples Reviewed | Factor | Number of CARD Samples Reviewed | Factor |
| CARBON TETRACHLORIDE | — | 10.0 | — | 10.0 |
| CHLOROBENZENE | 7,018 | 2.0 | 5,015 | 1.54 |
| CHLOROETHANE | — | 10.0 | — | 10.0 |
| CHLOROFORM | — | 10.0 | — | 10.0 |
| CHLOROMETHANE | — | 10.0 | — | 10.0 |
| CIS-1,3-DICHLOROPROPENE | — | 10.0 | — | 10.0 |
| DIBROMOCHLOROMETHANE | — | 10.0 | — | 10.0 |
| ETHYLBENZENE | — | 10.0 | — | 10.0 |
| METHYLENE CHLORIDE | — | 10.0 | — | 10.0 |
| STYRENE | — | 10.0 | — | 10.0 |
| TETRACHLOROETHENE | — | 10.0 | — | 10.0 |
| TOLUENE-D8 | 32,447 | 1.63 | 25,526 | 1.21 |
| TRANS-1,3-DICHLOROPROPENE | — | 10.0 | — | 10.0 |
| TRICHLOROETHENE | 6,988 | 2.11 | 4,938 | 1.66 |
| VINYL CHLORIDE | — | 10.0 | — | 10.0 |
| XYLENE (TOTAL) | — | 10.0 | — | 10.0 |

TABLE 2
FACTORS FOR SEMIVOLATILE ORGANIC ANALYTES

| SEMIVOLATILE ORGANIC ANALYTES | SOIL MATRIX | | WATER MATRIX | |
|-------------------------------------|------------------------------------|--------|---------------------------------------|--------|
| | Number of CARD Samples Reviewed | Factor | Number of CARD Samples Reviewed | Factor |
| 1,2,4-TRICHLOROBENZENE | 6,792 | 4.83 | 4,605 | 3.71 |
| 1,2-DICHLOROBENZENE-D4 | 32,848 | 4.22 | 21,506 | 3.0 |
| 1,3-DICHLOROBENZENE | — | 10.0 | — | 10.0 |
| 1,4-DICHLOROBENZENE | 6,796 | 6.0 | 4,599 | 3.85 |
| 2,2'-OXYBIS(1-CHLOROPROPANE) | — | 10.0 | — | 10.0 |
| 2,4,6-TRIBROMOPHENOL | 32,605 | 9.38 | 21,509 | 3.57 |
| 2,4,5-TRICHLOROPHENOL | — | 10.0 | — | 10.0 |
| 2,4,6-TRICHLOROPHENOL | — | 10.0 | — | 10.0 |
| 2,4-DICHLOROPHENOL | — | 10.0 | — | 10.0 |
| 2,4-DIMETHYLPHENOL | — | 10.0 | — | 10.0 |
| 2,4-DINITROPHENOL | — | 10.0 | — | 10.0 |
| 2,4-DINITROTOLUENE | 6,798 | 4.88 | 4,623 | 3.52 |
| 2,6-DINITROTOLUENE | — | 10.0 | — | 10.0 |
| 2-CHLORONAPHTHALENE | — | 10.0 | — | 10.0 |
| 2-CHLOROPHENOL-D4 | 32,798 | 4.08 | 21,506 | 2.92 |
| 2-FLUOROBIPHENYL | 32,913 | 3.38 | 21,532 | 2.84 |
| 2-FLUORPHENOL | 32,781 | 5.05 | 21,511 | 3.34 |
| 2-METHYLNAPHTHALENE | — | 10.0 | — | 10.0 |
| 2-METHYLPHENOL | — | 10.0 | — | 10.0 |
| 2-NITROANILINE | — | 10.0 | — | 10.0 |
| 2-NITROPHENOL | — | 10.0 | — | 10.0 |
| 3,3'-DICHLOROBENZIDINE | — | 10.0 | — | 10.0 |
| 3-NITROANILINE | — | 10.0 | — | 10.0 |
| 4,6-DINITRO-2-METHYLPHENOL | — | 10.0 | — | 10.0 |
| 4-BROMOPHENYL-PHENYLETHER | — | 10.0 | — | 10.0 |

TABLE 2
FACTORS FOR SEMIVOLATILE ORGANIC ANALYTES

| SEMIVOLATILE ORGANIC ANALYTES | SOIL MATRIX | | WATER MATRIX | |
|-------------------------------------|------------------------------------|--------|---------------------------------------|--------|
| | Number of CARD Samples Reviewed | Factor | Number of CARD Samples Reviewed | Factor |
| 4-CHLORO-3-METHYLPHENOL | 6,715 | 6.26 | 4,609 | 4.46 |
| 4-CHLOROANILINE | — | 10.0 | — | 10.0 |
| 4-CHLOROPHENYL-PHENYLETHER | — | 10.0 | — | 10.0 |
| 4-METHYLPHENOL | — | 10.0 | — | 10.0 |
| 4-NITROANILINE | — | 10.0 | — | 10.0 |
| 4-NITROPHENOL | 6,627 | 9.33 | 4,586 | 5.96 |
| ACENAPHTHENE | 6,773 | 4.68 | 4,600 | 3.63 |
| ACENAPHTHYLENE | — | 10.0 | — | 10.0 |
| ANTHRACENE | — | 10.0 | — | 10.0 |
| BENZO(A)ANTHRACENE | — | 10.0 | — | 10.0 |
| BENZO(A)PYRENE | — | 10.0 | — | 10.0 |
| BENZO(B)FLUORANTHENE | — | 10.0 | — | 10.0 |
| BENZO(G,H,I)PERYLENE | — | 10.0 | — | 10.0 |
| BENZO(K)FLUORANTHENE | — | 10.0 | — | 10.0 |
| BIS(2-CHLOROETHOXY)METHANE | — | 10.0 | — | 10.0 |
| BIS(2-CHLOROETHYL)ETHER | — | 10.0 | — | 10.0 |
| BIS(2-ETHYLHEXYL)PHTHALATE | — | 10.0 | — | 10.0 |
| BUTYLBENZYLPHTHALATE | — | 10.0 | — | 10.0 |
| CARBAZOLE | — | 10.0 | — | 10.0 |
| CHRYSENE | — | 10.0 | — | 10.0 |
| DI-N-BUTYLPHTHALATE | — | 10.0 | — | 10.0 |
| DI-N-OCTYLPHTHALATE | — | 10.0 | — | 10.0 |
| DIBENZ(A,H)ANTHRACENE | — | 10.0 | — | 10.0 |
| DIBENZOFURAN | — | 10.0 | — | 10.0 |
| DIETHYLPHTHALATE | — | 10.0 | — | 10.0 |

TABLE 2
FACTORS FOR SEMIVOLATILE ORGANIC ANALYTES

| SEMIVOLATILE ORGANIC ANALYTES | SOIL MATRIX | | WATER MATRIX | |
|-------------------------------------|------------------------------------|--------|---------------------------------------|--------|
| | Number of CARD Samples Reviewed | Factor | Number of CARD Samples Reviewed | Factor |
| DIMETHYLPHTHALATE | — | 10.0 | — | 10.0 |
| FLUORANTHENE | — | 10.0 | — | 10.0 |
| FLUORENE | — | 10.0 | — | 10.0 |
| HEXACHLOROBENZENE | — | 10.0 | — | 10.0 |
| HEXACHLOROBUTADIENE | — | 10.0 | — | 10.0 |
| HEXACHLOROCYCLOPENTADIENE | — | 10.0 | — | 10.0 |
| HEXACHLOROETHANE | — | 10.0 | — | 10.0 |
| INDENO(1,2,3-CD)PYRENE | — | 10.0 | — | 10.0 |
| ISOPHORONE | — | 10.0 | — | 10.0 |
| N-NITROSO-DI-N-PROPYLAMINE | 6,725 | 4.92 | 4,513 | 4.0 |
| N-NITROSODIPHENYLAMINE(1) | — | 10.0 | — | 10.0 |
| NAPHTHALENE | — | 10.0 | — | 10.0 |
| NITROBENZENE-D5 | 32,867 | 3.96 | 21,533 | 2.73 |
| PENTACHLOROPHENOL | 6,597 | 72.5 | 4,550 | 10.12 |
| PHENANTHRENE | — | 10.0 | — | 10.0 |
| PHENOL-D5 | 32,855 | 3.85 | 21,489 | 3.53 |
| PYRENE | 6,543 | 11.86 | 4,612 | 5.67 |
| TERPHENYL-D14 | 32,899 | 4.35 | 21,541 | 6.32 |

**TABLE 3
FACTORS FOR PESTICIDES/PCB ANALYTES**

| VOLATILE ORGANIC ANALYTES | SOIL MATRIX | | WATER MATRIX | |
|---------------------------------|--|--------|---------------------------------------|--------|
| | Number of CARD Samples Reviewed | Factor | Number of CARD Samples Reviewed | Factor |
| 4,4'-DDD | — | 10.0 | — | 10.0 |
| 4,4'-DDE | — | 10.0 | — | 10.0 |
| 4,4'-DDT | 5,343 | 12.82 | 3,850 | 7.14 |
| ALDRIN | 5,526 | 14.26 | 3,829 | 6.63 |
| ALPHA-BHC | — | 10.0 | — | 10.0 |
| ALPHA-CHLORDANE | — | 10.0 | — | 10.0 |
| AROCLOR-1016 | — | 10.0 | — | 10.0 |
| AROCLOR-1221 | — | 10.0 | — | 10.0 |
| AROCLOR-1232 | — | 10.0 | — | 10.0 |
| AROCLOR-1242 | — | 10.0 | — | 10.0 |
| AROCLOR-1248 | — | 10.0 | — | 10.0 |
| AROCLOR-1254 | — | 10.0 | — | 10.0 |
| AROCLOR-1260 | — | 10.0 | — | 10.0 |
| BETA-BHC | — | 10.0 | — | 10.0 |
| DECACHLOROBIPHENYL | 57,315 | 17.79 | 33,592 | 10.0 |
| DELTA-BHC | — | 10.0 | — | 10.0 |
| DIELDRIN | 5,539 | 11.93 | 3,861 | 4.87 |

| TABLE 3 FACTORS FOR PESTICIDES/PCB ANALYTES | | | | |
|--|--|--------|---------------------------------------|--------|
| VOLATILE ORGANIC ANALYTES | SOIL MATRIX | | WATER MATRIX | |
| | Number of CARD Samples Reviewed | Factor | Number of CARD Samples Reviewed | Factor |
| ENDOSULFAN I | — | 10.0 | — | 10.0 |
| ENDOSULFAN II | — | 10.0 | — | 10.0 |
| ENDOSULFAN SULFATE | — | 10.0 | — | 10.0 |
| ENDRIN | 5,521 | 14.13 | 3,850 | 5.33 |
| ENDRIN ALDEHYDE | — | 10.0 | — | 10.0 |
| ENDRIN KETONE | — | 10.0 | — | 10.0 |
| GAMMA-BHC (LINDANE) | 5,545 | 11.79 | 3,832 | 10.0 |
| GAMMA-CHLORDANE | — | 10.0 | — | 10.0 |
| HEPTACHLOR | 5,548 | 7.88 | 3,836 | 5.26 |
| HEPTACHLOR EPOXIDE | — | 10.0 | — | 10.0 |
| METHOXYCHLOR | — | 10.0 | — | 10.0 |
| TETRACHLORO-M-XYLENE | 59,508 | 8.5 | 33,787 | 5.29 |
| TOXAPHENE | — | 10.0 | — | 10.0 |

TABLE 4
FACTORS FOR INORGANIC ANALYTES

| INORGANIC ANALYTES | SOIL MATRIX | | WATER MATRIX | |
|--------------------|---------------------------------|--------|---------------------------------|--------|
| | Number of CARD Samples Reviewed | Factor | Number of CARD Samples Reviewed | Factor |
| ALUMINUM | 5387 | 1.66 | 6208 | 1.30 |
| ANTIMONY | 5392 | 1.98 | 6170 | 1.27 |
| ARSENIC | 5675 | 1.74 | 6303 | 1.35 |
| BARIUM | 5360 | 3.99 | 6201 | 1.25 |
| BERYLLIUM | 5399 | 1.28 | 6208 | 1.25 |
| CADMIUM | 5385 | 1.41 | 6166 | 1.29 |
| CALCIUM | 5383 | 1.28 | 6201 | 1.24 |
| CHROMIUM | 5389 | 1.29 | 6210 | 1.30 |
| COBALT | 5392 | 1.25 | 6212 | 1.27 |
| COPPER | 5394 | 1.22 | 6205 | 1.25 |
| CYANIDE | 3281 | 1.55 | 225 | 1.36 |
| IRON | 5391 | 1.34 | 6216 | 1.27 |
| LEAD | 5982 | 1.44 | 6384 | 1.31 |
| MAGNESIUM | 5397 | 1.23 | 6210 | 1.24 |
| MANGANESE | 5395 | 1.24 | 6214 | 1.28 |
| MERCURY | 5954 | 1.83 | 256 | 1.50 |
| NICKEL | 5400 | 1.35 | 6210 | 1.29 |
| POTASSIUM | 3874 | 17.49 | 6175 | 1.24 |
| SELENIUM | 5620 | 2.38 | 6278 | 1.41 |
| SILVER | 5392 | 1.74 | 6215 | 1.42 |
| SODIUM | 5024 | 25.43 | 6195 | 1.26 |
| THALLIUM | 5621 | 1.86 | 6253 | 1.37 |
| VANADIUM | 5393 | 1.34 | 6212 | 1.25 |
| ZINC | 5404 | 1.50 | 6224 | 1.29 |

Reference 25

**STATEMENT OF WORK
FOR
SAMPLE ANALYSIS (ORGANIC AND INORGANIC)**

**MULTI-MEDIA
MULTI-CONCENTRATION**

June 1995

Prepared by:

**Ecology and Environment, Inc.
Technical Assistance Team
EPA Region 6**

TABLE 1
VOLATILE TARGET COMPOUND LIST AND REQUIRED QUANTITATION LIMITS

| Analyte | CAS# | QUANTITATION LIMIT | | |
|--------------------------------|------------|--------------------|----------------------|---------------------------------|
| | | Water ug/L | Low Soil ug/Kg | Med/High Soil/Waste ug/Kg |
| 1. Chloromethane | 74-87-3 | 10 | 10 | 1200 |
| 2. Bromomethane | 74-83-9 | 10 | 10 | 1200 |
| 3. Vinyl Chloride | 75-01-4 | 10 | 10 | 1200 |
| 4. Chloroethane | 75-00-3 | 10 | 10 | 1200 |
| 5. Methylene chloride | 75-09-2 | 10 | 10 | 1200 |
| 6. Acetone | 67-64-1 | 10 | 10 | 1200 |
| 7. Carbon disulfide | 75-15-0 | 10 | 10 | 1200 |
| 8. 1,1-Dichloroethene | 75-35-4 | 10 | 10 | 1200 |
| 9. 1,1-Dichloroethane | 75-34-3 | 10 | 10 | 1200 |
| 10. 1,2-Dichloroethene (total) | 540-59-0 | 10 | 10 | 1200 |
| 11. Chloroform | 67-66-3 | 10 | 10 | 1200 |
| 12. 1,2-Dichloroethane | 107-06-2 | 10 | 10 | 1200 |
| 13. 2-Butanone | 78-93-3 | 10 | 10 | 1200 |
| 14. 1,1,1-Trichloroethane | 71-55-6 | 10 | 10 | 1200 |
| 15. Carbon tetrachloride | 56-23-5 | 10 | 10 | 1200 |
| 16. Bromodichloromethane | 75-27-4 | 10 | 10 | 1200 |
| 17. 1,2-Dichloropropane | 78-87-5 | 10 | 10 | 1200 |
| 18. cis-1,3-Dichloropropene | 10061-01-5 | 10 | 10 | 1200 |
| 19. Trichloroethene | 79-01-6 | 10 | 10 | 1200 |
| 20. Dibromochloromethane | 124-48-1 | 10 | 10 | 1200 |
| 21. 1,1,2-Trichloroethane | 79-00-5 | 10 | 10 | 1200 |
| 22. Benzene | 71-43-2 | 10 | 10 | 1200 |
| 23. trans-1,3-Dichloropropene | 10061-02-6 | 10 | 10 | 1200 |
| 24. Bromoform | 75-25-2 | 10 | 10 | 1200 |
| 25. 4-Methyl-2-pentanone | 108-10-1 | 10 | 10 | 1200 |
| 26. 2-Hexanone | 591-78-6 | 10 | 10 | 1200 |
| 27. Tetrachloroethene | 127-18-4 | 10 | 10 | 1200 |
| 28. Toluene | 108-88-3 | 10 | 10 | 1200 |
| 29. 1,1,2,2-Tetrachloroethane | 79-34-5 | 10 | 10 | 1200 |
| 30. Chlorobenzene | 108-90-7 | 10 | 10 | 1200 |
| 31. Ethyl benzene | 100-41-4 | 10 | 10 | 1200 |
| 32. Styrene | 100-42-5 | 10 | 10 | 1200 |
| 33. Xylenes (total) | 1330-20-7 | 10 | 10 | 1200 |

TABLE 4
SEMI-VOLATILE TARGET COMPOUND LIST
AND REQUIRED QUANTITATION LIMITS

| Analyte | CAS# | QUANTITATION LIMIT | | |
|---------------------------------|----------|--------------------|----------------------|---------------------------------|
| | | Water ug/L | Low Soil ug/Kg | Med/High Soil/Waste ug/Kg |
| 1. Phenol | 108-95-2 | 10 | 330 | 10000 |
| 2. bis(2-Chloroethyl) ether | 111-44-4 | 10 | 330 | 10000 |
| 3. 2-Chlorophenol | 95-57-8 | 10 | 330 | 10000 |
| 4. 1,3-Dichlorobenzene | 541-73-1 | 10 | 330 | 10000 |
| 5. 1,4-Dichlorobenzene | 106-46-7 | 10 | 330 | 10000 |
| 6. 1,2-Dichlorobenzene | 95-50-1 | 10 | 330 | 10000 |
| 7. 2-Methylphenol | 95-48-7 | 10 | 330 | 10000 |
| 8. 2,2'-oxybis(1-Chloropropane) | 108-60-1 | 10 | 330 | 10000 |
| 9. 4-Methylphenol | 106-44-5 | 10 | 330 | 10000 |
| 10. N-Nitroso-di-n-propylamine | 621-64-7 | 10 | 330 | 10000 |
| 11. Hexachloroethane | 67-72-1 | 10 | 330 | 10000 |
| 12. Nitrobenzene | 98-95-3 | 10 | 330 | 10000 |
| 13. Isophorone | 78-59-1 | 10 | 330 | 10000 |
| 14. 2-Nitrophenol | 88-75-5 | 10 | 330 | 10000 |
| 15. 2,4-Dimethylphenol | 105-67-9 | 10 | 330 | 10000 |
| 16. bis(2-Chloroethoxy)methane | 111-91-1 | 10 | 330 | 10000 |
| 17. 2,4-Dichlorophenol | 120-83-2 | 10 | 330 | 10000 |
| 18. 1,2,4-Trichlorobenzene | 120-82-1 | 10 | 330 | 10000 |
| 19. Naphthalene | 91-20-3 | 10 | 330 | 10000 |
| 20. 4-Chloroaniline | 106-47-8 | 10 | 330 | 10000 |
| 21. Hexachlorobutadiene | 87-68-3 | 10 | 330 | 10000 |
| 22. 4-Chloro-3-methylphenol | 59-50-7 | 10 | 330 | 10000 |
| 23. 2-Methylnaphthalene | 91-57-6 | 10 | 330 | 10000 |
| 24. Hexachlorocyclopentadiene | 77-47-4 | 10 | 330 | 10000 |
| 25. 2,4,6-Trichlorophenol | 88-06-2 | 10 | 330 | 10000 |
| 26. 2,4,5-Trichlorophenol | 95-95-4 | 25 | 800 | 25000 |
| 27. 2-Chloronaphthalene | 91-58-7 | 10 | 330 | 10000 |
| 28. 2-Nitroaniline | 88-74-4 | 25 | 800 | 25000 |
| 29. Dimethylphthalate | 131-11-3 | 10 | 330 | 10000 |
| 30. Acenaphthylene | 208-96-8 | 10 | 330 | 10000 |
| 31. 2,6-Dinitrotoluene | 606-20-2 | 10 | 330 | 10000 |
| 32. 3-Nitroaniline | 99-09-2 | 25 | 800 | 25000 |
| 33. Acenaphthene | 83-32-9 | 10 | 330 | 10000 |
| 34. 2,4-Dinitrophenol | 51-28-5 | 25 | 800 | 25000 |
| 35. 4-Nitrophenol | 100-02-7 | 25 | 800 | 25000 |

TABLE 4 (cont)

| | | | | |
|--------------------------------|-----------|----|-----|-------|
| 36. Dibenzofuran | 132-64-9 | 10 | 330 | 10000 |
| 37. 2,4-Dinitrotoluene | 121-14-2 | 10 | 330 | 10000 |
| 38. Diethylphthalate | 84-66-2 | 10 | 330 | 10000 |
| 39. 4-Chlorophenyl-phenylether | 7005-72-3 | 10 | 330 | 10000 |
| 40. Fluorene | 86-73-7 | 10 | 330 | 10000 |
| 41. 4-Nitroaniline | 100-01-6 | 25 | 800 | 25000 |
| 42. 4,6-Dinitro-2-methylphenol | 534-52-1 | 25 | 800 | 25000 |
| 43. N-Nitrosodiphenylamine | 86-30-6 | 10 | 330 | 10000 |
| 44. 4-Bromophenyl-phenylether | 101-55-3 | 10 | 330 | 10000 |
| 45. Hexachlorobenzene | 118-74-1 | 10 | 330 | 10000 |
| 46. Pentachlorophenol | 87-86-5 | 25 | 800 | 25000 |
| 47. Phenanthrene | 85-01-8 | 10 | 330 | 10000 |
| 48. Anthracene | 120-12-7 | 10 | 330 | 10000 |
| 49. Carbazole | 86-74-8 | 10 | 330 | 10000 |
| 50. Di-n-butylphthalate | 84-74-2 | 10 | 330 | 10000 |
| 51. Fluoranthene | 206-44-0 | 10 | 330 | 10000 |
| 52. Pyrene | 129-00-0 | 10 | 330 | 10000 |
| 53. Butylbenzylphthalate | 85-68-7 | 10 | 330 | 10000 |
| 54. 3,3'-Dichlorobenzidine | 91-94-1 | 10 | 330 | 10000 |
| 55. Benzo(a)anthracene | 56-55-3 | 10 | 330 | 10000 |
| 56. Chrysene | 218-01-9 | 10 | 330 | 10000 |
| 57. bis(2-Ethylhexyl)phthalate | 117-81-7 | 10 | 330 | 10000 |
| 58. Di-n-octylphthalate | 117-84-0 | 10 | 330 | 10000 |
| 59. Benzo(b)fluoranthene | 205-99-2 | 10 | 330 | 10000 |
| 60. Benzo(k)fluoranthene | 207-08-9 | 10 | 330 | 10000 |
| 61. Benzo(a)pyrene | 50-32-8 | 10 | 330 | 10000 |
| 62. Indeno(1,2,3-cd)pyrene | 193-39-5 | 10 | 330 | 10000 |
| 63. Dibenz(a,h)anthracene | 53-70-3 | 10 | 330 | 10000 |
| 64. Benzo(g,h,i)perylene | 191-24-2 | 10 | 330 | 10000 |

TABLE 7
PESTICIDE/PCB TARGET COMPOUND LIST
AND REQUIRED QUANTITATION LIMITS

| Analyte | CAS# | QUANTITATION LIMIT | | |
|------------------------|------------|--------------------|---------------|----------------|
| | | Water ug/L | Soil ug/Kg | Waste ug/Kg |
| 1. alpha-BHC | 319-84-6 | 0.05 | 1.7 | 50 |
| 2. beta-BHC | 319-85-7 | 0.05 | 1.7 | 50 |
| 3. delta-BHC | 319-86-8 | 0.05 | 1.7 | 50 |
| 4. gamma-BHC (Lindane) | 58-89-9 | 0.05 | 1.7 | 50 |
| 5. Heptachlor | 76-44-8 | 0.05 | 1.7 | 50 |
| 6. Aldrin | 309-00-2 | 0.05 | 1.7 | 50 |
| 7. Heptachlor epoxide | 1024-57-3 | 0.05 | 1.7 | 50 |
| 8. Endosulfan I | 959-98-8 | 0.05 | 1.7 | 50 |
| 9. Dieldrin | 60-57-1 | 0.10 | 3.3 | 100 |
| 10. 4,4'-DDE | 72-55-9 | 0.10 | 3.3 | 100 |
| 11. Endrin | 72-20-8 | 0.10 | 3.3 | 100 |
| 12. Endosulfan II | 33213-65-9 | 0.10 | 3.3 | 100 |
| 13. 4,4'-DDD | 72-54-8 | 0.10 | 3.3 | 100 |
| 14. Endosulfan sulfate | 1031-07-8 | 0.10 | 3.3 | 100 |
| 15. 4,4'-DDT | 50-29-3 | 0.10 | 3.3 | 100 |
| 16. Methoxychlor | 72-43-5 | 0.50 | 17.0 | 500 |
| 17. Endrin ketone | 53494-70-5 | 0.10 | 3.3 | 100 |
| 18. Endrin aldehyde | 7421-36-3 | 0.10 | 3.3 | 100 |
| 19. alpha-Chlordane | 5103-71-9 | 0.05 | 1.7 | 50 |
| 20. gamma-Chlordane | 5103-74-2 | 0.05 | 1.7 | 50 |
| 21. Toxaphene | 8001-35-2 | 5.0 | 170.0 | 5000 |
| 22. Aroclor-1016 | 12674-11-2 | 1.0 | 33.0 | 1000 |
| 23. Aroclor-1221 | 11104-28-2 | 2.0 | 67.0 | 2000 |
| 24. Aroclor-1232 | 11141-16-5 | 1.0 | 33.0 | 1000 |
| 25. Aroclor-1242 | 53469-21-9 | 1.0 | 33.0 | 1000 |
| 26. Aroclor-1248 | 12672-29-6 | 1.0 | 33.0 | 1000 |
| 27. Aroclor-1254 | 11097-69-1 | 1.0 | 33.0 | 1000 |
| 28. Aroclor-1260 | 11096-82-5 | 1.0 | 33.0 | 1000 |

TABLE 10

INORGANIC TARGET ANALYTE LIST AND REQUIRED DETECTION LIMITS

| ANALYTE | CAS | WATER ug/L | SOIL/WASTE mg/Kg |
|-----------|-----------|---------------|---------------------|
| Aluminum | 7429-90-5 | 200 | 40 |
| Antimony | 7440-36-0 | 60 | 12 |
| Arsenic | 7440-38-2 | 10 | 2 |
| Barium | 7440-39-3 | 200 | 40 |
| Beryllium | 7440-41-7 | 5 | 1 |
| Cadmium | 7440-43-9 | 5 | 1 |
| Calcium | 7440-70-2 | 5000 | 1000 |
| Chromium | 7440-47-3 | 10 | 2 |
| Cobalt | 7440-48-4 | 50 | 10 |
| Copper | 7440-50-8 | 25 | 5 |
| Iron | 7439-89-6 | 100 | 20 |
| Lead | 7429-92-1 | 3 | 0.6 |
| Magnesium | 7439-95-4 | 5000 | 1000 |
| Manganese | 7439-96-5 | 15 | 3 |
| Mercury | 7439-97-6 | 0.2 | 0.1 |
| Nickel | 7440-02-0 | 40 | 8 |
| Potassium | 7440-09-7 | 5000 | 1000 |
| Selenium | 7782-49-2 | 5 | 1 |
| Silver | 7440-22-4 | 10 | 2 |
| Sodium | 7440-23-5 | 5000 | 1000 |
| Thallium | 7440-28-0 | 10 | 2 |
| Vanadium | 7440-62-2 | 50 | 10 |
| Zinc | 7440-66-6 | 20 | 4 |
| Cyanide | | 10 | 0.5 |

Reference 26

Report 269

**OCCURRENCE, AVAILABILITY, AND
CHEMICAL QUALITY OF GROUND
WATER IN THE CRETACEOUS
AQUIFERS OF NORTH-CENTRAL
TEXAS**

Volume 1



DEPARTMENT OF WATER RESOURCES

Table 1.—Stratigraphic Units and Their Water-bearing Properties
Yield, in gallons per minute (gal/min): small, less than 100 gal/min; moderate, 100–1,000 gal/min; large, more than 1,000 gal/min.


| Era | System | Series | Group | Stratigraphic units | Approximate maximum thickness (feet) | Character of rocks | Water-bearing characteristics |
|-----------|------------|-------------|----------------|---|--------------------------------------|---|---|
| Cenozoic | Quaternary | Recent | | Alluvium | 75 | Sand, silt, clay and gravel. | Yields small to large amounts of water to wells along the Red River |
| | | Pleistocene | | Fluviatile terrace deposits | | | |
| | Tertiary | Eocene | Wilcox | | 100 | Fine to medium sand with silt and clay | Yields small quantities of water to wells in the eastern part of the area. |
| | | Paleocene | Midway | | 150 | Gray, calcareous clay, in part silty to sandy | Do. |
| Mesozoic | Cretaceous | Gulf | Navarro | Kemp Clay Corsicana Marl | 300 | Fossiliferous clay and hard limy marl | Not known to yield water to wells in the area. |
| | | | | Nacatoch Sand | 500 | Fine sand and marl, fossiliferous | Yields small to moderate quantities of water near the outcrop. |
| | | | Taylor | Marlbrook Marl Pecan Gap Chalk Wolfe City - Ozan Formations | 1,500 | Clay, marl, mudstone, and chalk | Yields small quantities of water to shallow wells. |
| | | | Austin | Gober Chalk Brownstown Marl Blossom Sand Bonham Formation | 700 | Chalk, limestone, and marl; fine to medium sand, fossiliferous | Yields small to moderate quantities of water to wells in the northeastern part of the area; very limited as an aquifer. |
| | | | Eagle Ford | | 650 | Shale with thin beds of sandstone and limestone | Yields small quantities of water to shallow wells. |
| | | | Woodbine | | 700 | Medium to coarse iron sand, sandstone, clay and some lignite | Yields moderate to large quantities of water to municipal, industrial and irrigation wells. |
| | | Comanche | Washita | Grayson Marl - Mainstreet Limestone Pawpaw Formation - Weno Limestone - Denton Clay Fort Worth - Duck Creek Kiamichi Formation | 1,000 | Fossiliferous limestone, marl, and clay; some sand near top | Yields small quantities of water to shallow wells. |
| | | | Fredericksburg | Edwards Limestone Comanche Peak Formation | 250 | Limestone, clay, marl, shale, and shell agglomerates | Do. |
| | | | | Walnut Formation | | | |
| | | | Trinity | Paluxy Formation | 400 | Fine sand, sandy shale, and shale | Yields small to moderate quantities of water to wells. |
| | | | | Antlers Formation | 900 | Limestone, marl, shale, and anhydrite | Yields small quantities of water in localized areas. |
| | | | | Glen Rose Formation | | | |
| | | | | Twin Mountains Formation | 1,000 | Fine to coarse sand, shale, clay, and basal gravel and conglomerate | Yields moderate to large quantities of water to wells. |
| Paleozoic | | | | Paleozoic rocks undifferentiated | | Sandstone, limestone, shale and conglomerate | Yields small quantities of water in the western part of the area. |

Reference 27

Report 269

*OCCURRENCE, AVAILABILITY, AND
CHEMICAL QUALITY OF GROUND
WATER IN THE CRETACEOUS
AQUIFERS OF NORTH-CENTRAL TEXAS*


Volume 2



TEXAS DEPARTMENT OF WATER RESOURCES

July 1982

119



KAUFMAN COUNTY

32.33


Reference 28



Water Resources Data Texas

Water Year 1990

Volume 1. Arkansas River Basin, Red River Basin, Sabine River Basin, Neches River Basin, Trinity River Basin and Intervening Coastal Basins



U.S. GEOLOGICAL SURVEY WATER-DATA REPORT TX-90-1
Prepared in cooperation with the State of Texas
and with other agencies

08057410 TRINITY RIVER BELOW DALLAS, TX

LOCATION.--Lat 32°42'26", long 96°44'08", Dallas County, Hydrologic Unit 12030105, on right bank at downstream side of bridge on South Loop Highway 12, 1.0 mi downstream from White Rock Creek, 1.5 mi upstream from Fivemile Creek, 6.4 mi southeast of Dallas County Courthouse in Dallas, and at mile 491.8.

DRAINAGE AREA.--6,278 mi².

WATER-DISCHARGE RECORDS

PERIOD OF RECORD.--November 1956 to September 1961 (monthly records only), October 1961 to current year.

GAGE.--Water-stage recorder. Datum of gage is 365.89 ft above National Geodetic Vertical Datum of 1929.

REMARKS.--Records good, except those for estimated daily discharges, which are fair. Flow is affected at times by eight upstream reservoirs with a combined capacity of 1,714,400 acre-ft, of which 846,200 acre-ft is for flood control. Several cities within the Dallas-Fort Worth metroplex divert water for municipal use and return it to the river as sewage effluents above this station. Low flows are sustained by sewage effluents.

AVERAGE DISCHARGE.--33 years (water years 1958-90), 2,017 ft³/s (1,461,000 acre-ft/yr).

EXTREMES FOR PERIOD OF RECORD.--Maximum discharge, 87,000 ft³/s May 4, 1990 (gage height, 34.79 ft); minimum daily, 131 ft³/s Dec. 9, 1956.

EXTREMES OUTSIDE PERIOD OF RECORD.--Flood of May 25, 1908, reached a stage of 41.1 ft, from information by U.S. Army Corps of Engineers, and is the highest since that date. Floods in 1866 and 1908 reached about the same stage at Dallas.

EXTREMES FOR CURRENT YEAR.--Maximum discharge, 87,000 ft³/s May 4 at 0200 hours (gage height, 34.79 ft); minimum daily, 524 ft³/s Oct. 29.

DISCHARGE, CUBIC FEET PER SECOND, WATER YEAR OCTOBER 1989 TO SEPTEMBER 1990
MEAN VALUES

| DAY | OCT | NOV | DEC | JAN | FEB | MAR | APR | MAY | JUN | JUL | AUG | SEP |
|-------|-------|-------|-------|-------|--------|--------|--------|---------|--------|--------|--------|-------|
| 1 | 584 | 1130 | 587 | 887 | 6510 | 1770 | 4460 | 19800 | 13700 | 6090 | 4600 | 604 |
| 2 | 583 | 781 | 579 | 725 | 16900 | 1080 | 4790 | 32600 | 17300 | 5850 | 4710 | 579 |
| 3 | 571 | 684 | 585 | 720 | 11200 | 816 | 5530 | 67600 | 14300 | 5750 | 5330 | 567 |
| 4 | 574 | 635 | 592 | 1060 | 4530 | 756 | 5840 | 79200 | 12300 | 5720 | 6400 | 593 |
| 5 | 580 | 607 | 598 | 928 | 1470 | 731 | 5630 | 65000 | 12200 | 5720 | 8270 | 607 |
| 6 | 569 | 631 | 588 | 744 | 1120 | 726 | 6590 | 61700 | 12800 | 5770 | 10300 | 599 |
| 7 | 606 | 634 | 576 | 702 | 1020 | 1850 | 8390 | 57700 | 13300 | 5860 | 9050 | 600 |
| 8 | 558 | 672 | 585 | 681 | 1410 | 3560 | 7540 | 52300 | 13400 | 5670 | 6500 | 684 |
| 9 | 552 | 734 | 598 | 659 | 1000 | 1740 | 6380 | 46900 | 13500 | 3430 | 5250 | 726 |
| 10 | 552 | 663 | 590 | 656 | 1640 | 1180 | 6880 | 41800 | 13500 | 1040 | 4810 | 842 |
| 11 | 542 | 594 | 592 | 645 | 1390 | 2710 | 7220 | 37300 | 13300 | 924 | 4580 | 1030 |
| 12 | 548 | 609 | 612 | 659 | 1080 | 9850 | 6530 | 35000 | 12900 | 970 | 4160 | 890 |
| 13 | 563 | 596 | 598 | 642 | 972 | 14500 | 6180 | 32700 | 12400 | 1210 | 3510 | 787 |
| 14 | 544 | 594 | 600 | 618 | 851 | 12100 | 8910 | 30000 | 11700 | 1050 | 3220 | 755 |
| 15 | 537 | 576 | 602 | 632 | 974 | 14400 | 15700 | 27500 | 10800 | 957 | 3090 | 681 |
| 16 | 542 | 594 | 627 | 674 | 1060 | 10300 | 16200 | 25000 | 9780 | 967 | 2730 | 630 |
| 17 | 542 | 588 | 621 | 750 | 1000 | 6130 | 10700 | 22300 | 9210 | 1430 | 2470 | 625 |
| 18 | 610 | 571 | 630 | 2050 | 748 | 4540 | 6070 | 19500 | 8960 | 3030 | 2100 | 765 |
| 19 | 617 | 576 | 615 | 7110 | 760 | 4490 | 3910 | 16800 | 8810 | 4220 | 2020 | 758 |
| 20 | 569 | 587 | 630 | 9640 | 745 | 5270 | 4340 | 14700 | 8420 | 4720 | 1970 | 684 |
| 21 | 546 | 604 | 621 | 4770 | 881 | 6090 | 6900 | 13400 | 7860 | 4820 | e1880 | 759 |
| 22 | 525 | 890 | 654 | 1510 | 2410 | 6670 | 8800 | 12700 | 7530 | 4840 | e1600 | 732 |
| 23 | 525 | 998 | 660 | 978 | 1910 | 7170 | 8440 | 12900 | 7070 | 5300 | e1350 | 680 |
| 24 | 540 | 715 | 695 | 844 | 1020 | 7290 | 9130 | 13200 | 6970 | 5650 | e1000 | 631 |
| 25 | 528 | 648 | 760 | 776 | 833 | 6880 | 9730 | 13500 | 7030 | 5920 | e900 | 616 |
| 26 | 535 | 643 | 811 | 764 | 777 | 8180 | 14000 | 13300 | 7080 | 5490 | e860 | 596 |
| 27 | 530 | 625 | 832 | 758 | 764 | 7560 | 26000 | 13200 | 7060 | 4990 | e750 | 579 |
| 28 | 528 | 628 | 752 | 780 | 1200 | 8070 | 25600 | 13000 | 6910 | 4770 | 675 | 570 |
| 29 | 524 | 627 | 726 | 802 | --- | 10500 | 23000 | 12800 | 6780 | 4650 | 655 | 555 |
| 30 | 2210 | 599 | 719 | 739 | --- | 9570 | 21000 | 13100 | 6510 | 4590 | 711 | 543 |
| 31 | 2610 | --- | 937 | 931 | --- | 6060 | --- | 13000 | --- | 4600 | 675 | --- |
| TOTAL | 20944 | 20033 | 20172 | 44834 | 66175 | 182539 | 300390 | 929500 | 313380 | 125998 | 106126 | 20267 |
| MEAN | 676 | 668 | 651 | 1446 | 2363 | 5888 | 10010 | 29980 | 10450 | 4064 | 3423 | 676 |
| MAX | 2610 | 1130 | 937 | 9640 | 16900 | 14500 | 26000 | 79200 | 17300 | 6090 | 10300 | 1030 |
| MIN | 524 | 571 | 576 | 618 | 745 | 726 | 3910 | 12700 | 6510 | 924 | 655 | 543 |
| AC-FT | 41540 | 39740 | 40010 | 88930 | 131300 | 362100 | 595800 | 1844000 | 621600 | 249900 | 210500 | 40200 |

CAL YR 1989 TOTAL 1658817 MEAN 4545 MAX 61500 MIN 524 AC-FT 3290000
WTR YR 1990 TOTAL 2150358 MEAN 5891 MAX 79200 MIN 524 AC-FT 4265000

e Estimated

Reference 29



FISHING



Water Body Records (T)

[A | B | C | D | E | F | G | H | I | J | K | L | M | N | O | P | Q | R | S | T | U | V | W | X | Y | Z]

ALL TACKLE CATEGORY

Updated 3/12/99

| WATER BODY | SPECIES | | WEIGHT (LBS) | LENGTH (IN) | DATE | ANGLER | METHOD |
|-----------------|----------|----------------|--------------|-------------|----------|----------------------|------------|
| Tawakoni | Bass | Hybrid Striped | 15.25 | 28.00 | 5/16/88 | Franklin H Smith | Rod & Reel |
| Tawakoni | Bass | Hybrid Yellow | 3.50 | 18.00 | 7/15/89 | Lucky Turner | Rod & Reel |
| Tawakoni | Bass | Largemouth | 10.75 | 24.50 | 3/8/93 | Davey Turner | Rod & Reel |
| Tawakoni | Bass | Striped | 22.25 | 36.50 | 7/1/91 | Gloria Sahaydak Quam | Rod & Reel |
| Tawakoni | Bass | White | 3.64 | 15.25 | 4/17/91 | Britt Henson | Rod & Reel |
| Tawakoni | Buffalo | Smallmouth | 52.75 | 41.00 | 5/6/95 | Gotcher Wilson | Trotline |
| Tawakoni | Catfish | Blue | 40.25 | 41.00 | 2/27/97 | David Hanson | Rod & Reel |
| Tawakoni | Catfish | Channel | 16.25 | 32.50 | 2/21/97 | David Hanson | Rod & Reel |
| Tawakoni | Catfish | Flathead | 110.50 | 60.50 | 6/5/98 | Bryan Eubanks | Trotline |
| Tawakoni | Crappie | White | 3.33 | 17.75 | 4/6/98 | Bobbie Griffin | Rod & Reel |
| Tawakoni | Goldfish | | 3.19 | 16.00 | 4/19/94 | Jerry Brooks | Rod & Reel |
| Tehuacana Creek | Bass | Largemouth | 5.78 | 22.00 | 1/27/94 | Rick Rivard | Rod & Reel |
| Tehuacana Creek | Catfish | Channel | 8.06 | 26.50 | 1/27/94 | Rick Rivard | Rod & Reel |
| Tehuacana Creek | Sunfish | Green | 1.22 | 9.29 | 4/21/95 | Rickie Rivard | Rod & Reel |
| Texas & Pacific | Crappie | White | 1.94 | 14.50 | 5/3/98 | Kenneth Allen | Rod & Reel |
| Texoma | Bass | Hybrid Striped | 14.88 | 31.00 | 3/22/92 | Bruce Maybrier | Rod & Reel |
| Texoma | Bass | Largemouth | 11.06 | 24.00 | 12/21/92 | Alvin Bouge | Rod & Reel |
| Texoma | Bass | Smallmouth | 6.91 | 24.00 | 1/22/96 | Yarri Schreibvogel | Rod & Reel |
| Texoma | Bass | Spotted | 4.38 | 20.50 | 11/25/88 | Chuck Bishop | Rod & Reel |
| Texoma | Bass | Striped | 35.12 | 39.00 | 4/25/84 | Terry Harber | Rod & Reel |
| Texoma | Bass | White | 3.41 | 18.00 | 2/8/94 | Robert Blair | Rod & Reel |
| Texoma | Bluegill | | 0.56 | 8.66 | 10/23/94 | Gina Schreibvogel | Rod & Reel |
| Texoma | Buffalo | Bigmouth | 41.50 | 37.00 | 6/30/90 | Walter M. Cole | Rod & Reel |
| Texoma | Buffalo | Smallmouth | 28.50 | 35.00 | 4/27/91 | Sandra Wiseman | Rod & Reel |

| | | | | | | | |
|-----------------------|----------|----------------|--------|-------|---------|-------------------------|-------------|
| Texoma | Carp | Common | 9.25 | 26.00 | 5/2/98 | Adam James | Rod & Reel |
| Texoma | Carp | Grass | 31.50 | 39.50 | 3/24/96 | Harold McAlester | Rod & Reel |
| Texoma | Catfish | Blue | 116.00 | 59.00 | 4/21/85 | C D Martindale | TROTLINE |
| Texoma | Catfish | Channel | 10.07 | 27.50 | 9/6/95 | Randy Jameson | Rod & Reel |
| Texoma | Catfish | Flathead | 45.65 | 42.50 | 4/6/97 | Ed Wolfe | Rod & Reel |
| Texoma | Crappie | Black | 2.00 | 14.88 | 4/12/96 | Yarri Schreibvogel | Rod & Reel |
| Texoma | Crappie | White | 3.23 | 15.50 | 3/9/95 | William Van Der Giessen | Rod & Reel |
| Texoma | Drum | Freshwater | 34.70 | 32.25 | 3/30/95 | Billy Walker | Rod & Reel |
| Texoma | Gar | Alligator | 77.50 | 73.00 | 6/13/95 | Joe Robertson | Rod & Reel |
| Texoma | Gar | Longnose | 22.72 | 55.00 | 8/30/91 | Mark Wright | Rod & Reel |
| Texoma | Gar | Spotted | 4.15 | 30.38 | 7/30/93 | John Hardin | Rod & Reel |
| Texoma | Goldeye | | 2.31 | 17.50 | 5/28/96 | Mandy Richmond | Rod & Reel |
| Texoma | Sunfish | Green | 0.75 | 9.38 | 1/24/94 | Wendy Schreibvogel | Rod & Reel |
| Texoma | Sunfish | Hybrid Green | 0.68 | 9.50 | 1/5/94 | Wendy Schrievvogel | Rod & Reel |
| Texoma | Sunfish | Longear | 0.18 | 5.75 | 9/14/92 | John Hardin | Rod & Reel |
| Timber Creek | Bass | White | 1.53 | 15.63 | 4/29/93 | John Hardin | Rod & Reel |
| Timber Creek | Bluegill | | 0.06 | 4.63 | 4/29/93 | John Hardin | Rod & Reel |
| Timber Creek | Buffalo | Smallmouth | 7.30 | 22.50 | 4/27/93 | Justin Hardin | Rod & Reel |
| Timber Creek | Bullhead | Black | 0.98 | 12.75 | 4/29/93 | John Hardin | Rod & Reel |
| Timber Creek | Bullhead | Yellow | 0.17 | 6.88 | 4/30/93 | John Hardin | Rod & Reel |
| Timber Creek | Carp | | 6.00 | 21.88 | 4/30/93 | Justin Hardin | Rod & Reel |
| Timber Creek | Catfish | Channel | 0.69 | 12.88 | 4/30/93 | John Hardin | Rod & Reel |
| Timber Creek | Drum | Freshwater | 0.79 | 12.25 | 4/27/93 | John Hardin | Rod & Reel |
| Timber Creek | Gar | Spotted | 5.80 | 32.38 | 4/30/93 | John Hardin | Rod & Reel |
| Timber Creek | Sunfish | Longear | 0.15 | 5.69 | 4/27/93 | Ryan Collins | Rod & Reel |
| Toledo Bend Reservoir | Bass | Hybrid Striped | 15.81 | 32.50 | 5/25/87 | Johnny Pritchett | Rod & Reel |
| Toledo Bend Reservoir | Bass | Largemouth | 14.69 | 24.00 | 3/4/98 | Kraig Welborn | Rod & Reel |
| Toledo Bend Reservoir | Bass | Striped | 33.22 | 41.00 | 2/8/80 | James E Kent Jr | Rod & Reel |
| Toledo Bend Reservoir | Bass | White | 4.25 | 15.63 | 9/17/83 | Danny L. Statler | Rod & Reel |
| Toledo Bend Reservoir | Bowfin | | 19.00 | 32.50 | 1/3/75 | George E Lord | TROTLINE |
| Toledo Bend Reservoir | Buffalo | Bigmouth | 75.00 | 42.00 | 8/7/85 | Joe R Walker | TROTLINE |
| Toledo Bend Reservoir | Buffalo | Smallmouth | 78.00 | 46.00 | 6/23/92 | Travis Thornton | Rod & Reel |
| Toledo Bend Reservoir | Carp | Grass | 51.25 | 43.25 | 7/12/97 | Darrell Curry | Bow & Arrow |
| Toledo Bend Reservoir | Catfish | Blue | 67.54 | 46.00 | 4/12/95 | Doug Skinner | Stump Hook |
| Toledo Bend Reservoir | Catfish | Flathead | 97.50 | 48.00 | 5/24/91 | Otis L. Pleasant | Trotline |

| | | | | | | | |
|------------------------------|----------|----------------|-------|-------|----------|---------------------|-------------|
| Toledo Bend Reservoir | Crappie | Black | 3.69 | 17.75 | 1/17/85 | Fritz Gowan | Rod & Reel |
| Toledo Bend Reservoir | Crappie | White | 2.88 | 17.25 | 3/13/98 | Geneva Daniels | Rod & Reel |
| Toledo Bend Reservoir | Drum | Freshwater | 31.50 | 30.00 | 3/3/95 | Freddie Keel | Rod & Reel |
| Toledo Bend Reservoir | Warmouth | | 1.09 | 11.00 | 4/14/95 | William Tawney | Rod & Reel |
| Towle Park | Bass | White | 5.06 | 20.00 | 4/26/92 | Charles Parlin | Rod & Reel |
| Town Lake | Bass | Guadalupe | 3.01 | 18.00 | 8/23/92 | Terry Hall | Rod & Reel |
| Town Lake | Bass | Hybrid Striped | 17.78 | 34.00 | 1/18/93 | Morris Boyd | Rod & Reel |
| Town Lake | Bass | Largemouth | 10.42 | 25.50 | 1/31/95 | James Garcia | Rod & Reel |
| Town Lake | Bass | Smallmouth | 5.75 | 22.75 | 3/16/80 | Grant C Hartman | Rod & Reel |
| Town Lake | Bass | Striped | 45.50 | 44.25 | 3/2/93 | Morris Boyd | Rod & Reel |
| Town Lake | Bass | White | 3.36 | 19.00 | 4/2/97 | J. Darryl Freeman | Rod & Reel |
| Town Lake | Bluegill | | 0.19 | 5.50 | 8/2/97 | J. Darryl Freeman | Rod & Reel |
| Town Lake | Buffalo | Smallmouth | 59.00 | 40.50 | 10/28/97 | Gibbs Milliken | Fly Rod |
| Town Lake | Carp | | 46.50 | 40.50 | 4/2/96 | Robert Smith | Bow & Arrow |
| Town Lake | Catfish | Blue | 41.00 | 42.50 | 5/12/83 | Pete Pattisor | Rod & Reel |
| Town Lake | Catfish | Flathead | 2.64 | 18.50 | 7/28/97 | Mickey Gardener | Rod & Reel |
| Town Lake | Drum | Freshwater | 9.63 | 25.00 | 7/31/96 | J. Darryl Freeman | Rod & Reel |
| Town Lake | Pike | Northern | 18.28 | 41.00 | 8/29/81 | Mike Sharpe | Rod & Reel |
| Town Lake | Redhorse | Gray | 5.46 | 22.00 | 4/8/96 | Robert Smith | Bow & Arrow |
| Town Lake | Shad | Gizzard | 2.67 | 18.00 | 4/12/97 | J. Darryl Freeman | Rod & Reel |
| Town Lake | Sunfish | Hybrid | 0.23 | 6.00 | 8/5/97 | J. Darryl Freeman | Rod & Reel |
| Town Lake | Sunfish | Longear | 0.31 | 5.50 | 8/5/97 | J. Darryl Freeman | Rod & Reel |
| Town Lake | Sunfish | Redbreast | 0.58 | 9.00 | 7/9/93 | Steve Lightfoot | Rod & Reel |
| Town Lake | Sunfish | Redear | 2.99 | 14.00 | 4/1/97 | John Runnels | Rod & Reel |
| Town Lake | Warmouth | | 1.30 | 10.50 | 7/19/91 | Ralph E. Manns, Jr. | Rod & Reel |
| Town Resaca | Carp | | 6.48 | 23.00 | 5/16/93 | Noe Flores | Rod & Reel |
| Town Resaca | Catfish | Channel | 7.00 | 26.00 | 5/16/93 | Brandon Christ | Rod & Reel |
| Town Resaca | Cichlid | Rio Grande | 0.69 | 10.00 | 5/16/93 | Jennifer Rubinstine | Rod & Reel |
| Town Resaca | Sleeper | Bigmouth | 0.64 | 12.00 | 5/16/93 | Regan Messenger | Rod & Reel |
| Town Resaca | Tilapia | Blue | 0.83 | 11.00 | 5/16/93 | Mateo Leal | Rod & Reel |
| Tradinghouse Creek Reservoir | Bass | Largemouth | 10.60 | 26.00 | 1/17/98 | David Foster | Rod & Reel |
| Tradinghouse Creek Reservoir | Bass | White | 2.00 | 15.80 | 2/25/94 | Dan Walling | Rod & Reel |
| Tradinghouse Creek Reservoir | Bluegill | | 0.22 | 6.85 | 7/1/93 | Rick Rivard | Rod & Reel |

| | | | | | | | |
|------------------------------|-------------|----------------|-------|-------|----------|------------------------|-------------|
| Tradinghouse Creek Reservoir | Buffalo | Bigmouth | 39.00 | 33.00 | 2/18/95 | Billy York | Rod & Reel |
| Tradinghouse Creek Reservoir | Buffalo | Smallmouth | 42.30 | 39.00 | 4/9/97 | Donnie Rice | Rod & Reel |
| Tradinghouse Creek Reservoir | Catfish | Blue | 32.00 | 36.00 | 4/3/93 | Rick Rivard | Trotline |
| Tradinghouse Creek Reservoir | Catfish | Channel | 6.92 | 24.00 | 3/5/94 | Rick Rivard | Rod & Reel |
| Tradinghouse Creek Reservoir | Catfish | Flathead | 62.00 | 46.00 | 7/8/97 | Rick Rivard | Trotline |
| Tradinghouse Creek Reservoir | Crappie | White | 1.94 | 14.75 | 2/11/94 | Rickie Rivard | Rod & Reel |
| Tradinghouse Creek Reservoir | Drum | Red | 29.50 | 40.00 | 4/3/91 | Brenda Kay Nichols | Rod & Reel |
| Tradinghouse Creek Reservoir | Gar | Spotted | 4.19 | 29.53 | 4/11/93 | Rick Rivard | Trotline |
| Tradinghouse Creek Reservoir | Mullet | Striped | 9.94 | 29.37 | 5/18/94 | Bryan Hanus | Bow & Arrow |
| Tradinghouse Creek Reservoir | Sunfish | Redear | 0.34 | 7.56 | 7/1/93 | Rick Rivard | Rod & Reel |
| Tradinghouse Creek Reservoir | Tilapia | Blue | 3.88 | 17.00 | 2/11/94 | Rickie Rivard | Rod & Reel |
| Trammell | Bass | Largemouth | 13.50 | 26.25 | 2/10/97 | Michael Brasvel | Rod & Reel |
| Trammell | Bass | White | 4.38 | 16.75 | 5/1/93 | Larry Harding | Rod & Reel |
| Travis | Bass | Guadalupe | 3.69 | 18.25 | 9/25/83 | Allen M Christenson Jr | Rod & Reel |
| Travis | Bass | Hybrid Striped | 13.75 | 32.25 | 6/17/89 | John Kohler | Rod & Reel |
| Travis | Bass | Largemouth | 14.21 | 28.00 | 1/25/93 | James Penny | Rod & Reel |
| Travis | Bass | Smallmouth | 4.50 | 22.00 | 3/31/92 | Robert Hough | Rod & Reel |
| Travis | Bass | Striped | 30.50 | 42.00 | 6/7/90 | Rudolph Cardenas, Jr. | Rod & Reel |
| Travis | Bass | White | 2.88 | 18.25 | 3/21/89 | John Gilbert | Rod & Reel |
| Travis | Bluegill | | 0.88 | 10.50 | 4/14/95 | Matt Jeske | Rod & Reel |
| Travis | Buffalo | Smallmouth | 15.00 | 28.00 | 12/26/94 | Leland Roberts | Rod & Reel |
| Travis | Catfish | Blue | 40.94 | 42.00 | 12/13/97 | William Hoes | Trotline |
| Travis | Catfish | Flathead | 7.20 | 25.50 | 4/20/97 | Lance McMullan | Trotline |
| Travis | Crappie | White | 1.43 | 14.00 | 4/4/94 | Carl Reuter | Rod & Reel |
| Travis | Drum | Freshwater | 3.42 | 20.25 | 5/20/95 | Peter Jeske | Rod & Reel |
| Travis | Sunfish | Redbreast | 0.24 | 7.63 | 5/16/93 | Artie Hebert | Rod & Reel |
| Travis | Sunfish | Redear | 0.38 | 8.25 | 5/16/93 | Artie Hebert | Rod & Reel |
| Travis | Trout | Rainbow | 1.51 | 16.50 | 4/19/97 | James Harris | Rod & Reel |
| Trinidad | Bass | White | 4.25 | 18.00 | 3/7/83 | Winston Thornburg | Rod & Reel |
| Trinity River | Bass | Hybrid Striped | 14.10 | 29.02 | 6/26/95 | Howard Hall | Rod & Reel |
| Trinity River | Bass | Largemouth | 7.13 | 24.50 | 3/15/78 | Micky Bean | Rod & Reel |
| Trinity River | Bass | White | 3.72 | 18.00 | 2/24/95 | Gilbert Celaya | Rod & Reel |
| Trinity River | Bluegill | | 0.14 | 5.88 | 4/7/94 | Justin Hardin | Rod & Reel |
| Trinity River | Carp | | 4.44 | 23.50 | 6/7/94 | Rick Rivard | Rod & Reel |
| Trinity River | Carp | Grass | 12.50 | 31.00 | 6/16/91 | PaPa Earl | Rod & Reel |
| Trinity River | Carp sucker | River | 2.10 | 16.25 | 6/18/96 | Del Sowders | Rod & Reel |

| | | | | | | | |
|-----------------------|----------|-------------|--------|-------|----------|-------------------|-------------|
| Trinity River | Catfish | Blue | 76.00 | 45.00 | 4/14/91 | Richard C. Jordan | Rod & Reel |
| Trinity River | Catfish | Channel | 1.75 | 16.50 | 6/15/94 | Del Sowders | Rod & Reel |
| Trinity River | Catfish | Flathead | 58.00 | 53.00 | 7/21/77 | Dean Brown | Rod & Reel |
| Trinity River | Crappie | White | 2.50 | 15.40 | 2/8/95 | Rick Rivard | Rod & Reel |
| Trinity River | Drum | Freshwater | 1.25 | 13.58 | 6/7/94 | Rick Rivard | Rod & Reel |
| Trinity River | Gar | Alligator | 162.50 | 84.00 | 9/15/91 | Bobby J. Fly | Rod & Reel |
| Trinity River | Gar | Longnose | 82.00 | 77.00 | 5/13/90 | Rance E. Allen | Bow & Arrow |
| Trinity River | Gar | Spotted | 1.98 | 23.25 | 6/2/93 | John Hardin | Rod & Reel |
| Trinity River | Sunfish | Green | 0.20 | 7.00 | 4/17/95 | Justin Hardin | Rod & Reel |
| Trinity River | Sunfish | Longear | 0.14 | 5.94 | 4/7/94 | John Hardin | Rod & Reel |
| Trinity River | Warmouth | | 0.50 | 7.50 | 2/8/95 | Rick Rivard | Rod & Reel |
| Tule Creek | Bass | White | 3.25 | 18.25 | 4/18/92 | S. J. Stormes | Rod & Reel |
| Twin Buttes Reservoir | Bass | Largemouth | 14.25 | 26.00 | 8/24/91 | Greg H. Benson | Rod & Reel |
| Twin Buttes Reservoir | Bass | Smallmouth | 5.31 | 22.00 | 5/26/90 | Barry Bennett | Rod & Reel |
| Twin Buttes Reservoir | Bass | Striped | 4.39 | 22.50 | 2/13/98 | John Dennis | Rod & Reel |
| Twin Buttes Reservoir | Catfish | Blue | 50.37 | 43.50 | 3/29/92 | Courtney Woehl | Trotline |
| Twin Buttes Reservoir | Catfish | Flathead | 63.50 | 47.00 | 3/24/91 | Wayne Peck | Rod & Reel |
| Twin Buttes Reservoir | Walleye | | 8.25 | 29.50 | 9/4/82 | Kim H. Holmes | Rod & Reel |
| Tyler | Bass | Largemouth | 12.56 | 25.30 | 2/13/87 | Argus Cathey | Rod & Reel |
| Tyler | Bluegill | | 0.61 | 9.00 | 4/27/98 | Ana Bonner | Rod & Reel |
| Tyler | Catfish | Blue | 26.10 | 37.00 | 11/9/95 | Joe Smith | Floatline |
| Tyler | Catfish | Channel | 20.44 | 34.38 | 3/18/89 | Fred Garrett | trotline |
| Tyler | Catfish | Flathead | 74.00 | 50.50 | 10/12/93 | John Carter | Rod & Reel |
| Tyler | Crappie | Black | 1.36 | 13.00 | 10/3/94 | Jeff Adams | Rod & Reel |
| Tyler | Crappie | White | 2.33 | 16.25 | 11/23/96 | Richard Brands | Rod & Reel |
| Tyler | Drum | Freshwater | 17.38 | 29.75 | 6/5/94 | Michael Baker | Rod & Reel |
| Tyler | Pacu | Red-bellied | 3.09 | 15.50 | 7/19/95 | Jason Daniels | Rod & Reel |
| Tyler | Pickrel | Chain | 2.48 | 22.00 | 1/27/97 | Billy McFarland | Rod & Reel |
| Tyler | Sunfish | Redear | 0.76 | 9.50 | 6/23/97 | Craig Bonner | Rod & Reel |
| Tyler State Park | Sunfish | Redbreast | 0.56 | 7.87 | 12/2/95 | Del Sowders | Rod & Reel |
| Tyler State Park | Sunfish | Spotted | 0.07 | 4.00 | 8/26/92 | John Hardin | Rod & Reel |
| Tyler State Park | Warmouth | | 0.46 | 8.50 | 4/7/95 | Del Sowders | Rod & Reel |

A | B | C | D | E | F | G | H | I | J | K | L | M | N | O | P | Q | R | S | T | U | V | W | X | Y | Z]

For more information contact Angler Recognition Awards Program Coordinator:

Email: mailto:jknight@tyler.net

Telephone: (903) 566-1615

Mail: 11810 FM 848, Tyler, Texas 75707.

Please send comments, suggestions, or questions to:

TEXAS PARKS & WILDLIFE

4200 SMITH SCHOOL RD. AUSTIN, TX 78744

Last Revision Date: March 03, 1999

Last Revision: April 15, 1999



98 Stocking Report

[Filter](#)

Current Filter: [Waterbody Name] = 'TRINITY RIVER'

Where "Waterbody Name" is highlighted, indicates a link to more detailed descriptions including a lake map, access points, what to fish for, nearby state parks, and more!

Where "Fish Name" is highlighted, also indicates a link to more detailed descriptions including biology, distribution, description, and an image of the fish.

Press the "Filter" button to submit another fish stocking search. DO NOT use the Back button.

| Waterbody Name | Fish Name | Stocking Date | Number Stocked | Stage |
|----------------|----------------------------|---------------|----------------|------------|
| TRINITY RIVER | Paddlefish | 5/26/98 | 3890 | Fingerling |
| TRINITY RIVER | Paddlefish | 5/27/98 | 3544 | Fingerling |
| TRINITY RIVER | Paddlefish | 5/28/98 | 3215 | Fingerling |
| TRINITY RIVER | Paddlefish | 6/15/98 | 4999 | Fingerling |
| TRINITY RIVER | Paddlefish | 6/15/98 | 5000 | Fingerling |
| TRINITY RIVER | Paddlefish | 6/16/98 | 4998 | Fingerling |
| TRINITY RIVER | Paddlefish | 6/16/98 | 4996 | Fingerling |

Please send comments, suggestions, or questions to:

TEXAS PARKS & WILDLIFE

4200 SMITH SCHOOL RD. AUSTIN, TX 78744

or click on the address to send an E-mail message.

[Home](#) | [Nature](#) | [Hunting](#) | [Fishing](#) | [Boating](#) | [Parks & Historic Sites](#) | [Nature](#) | [Education](#) | [Kids'](#)
[Page](#) | [Adventure](#) | [Newsstand](#) | [Gift Shop](#) | [Jobs](#) | [All About TPW](#) | [Related Sites](#) | [Search](#)

Reference 30

THE UNIVERSITY OF TEXAS AT AUSTIN
BUREAU OF ECONOMIC GEOLOGY

TO ACCOMPANY MAP—DALLAS SHEET—
GEOLOGIC ATLAS OF TEXAS

GEOLOGIC ATLAS OF TEXAS DALLAS SHEET

GAYLE SCOTT MEMORIAL EDITION

VIRGIL E. BARNES, Project Director



**1972
Revised 1988**

Ko

Ozan Formation ("lower Taylor marl")

Clay, calcareous, silt and sand content increases upward, montmorillonitic, blocky, conchoidal fracture, medium gray; some glauconite, phosphate pellets, hematite nodules, and pyrite nodules; some very thin limestone lenses locally in lower part; weathers light brownish gray with poor fissility, grades upward to Wolfe City Formation; marine megafossils; thickness 500± feet

Kau

Austin Chalk

Upper and lower parts, chalk, mostly microgranular calcite, massive, some interbeds and partings of calcareous clay, thin bentonitic beds locally in lower part, lower part forms westward-facing scarp; light gray. Middle part, mostly thin-bedded marl with interbeds of massive chalk, locally burrowed, marcasite-pyrite nodules common, light gray. Weathers white, marine megafossils scarce, thickness 300-500 feet, thins southward

Kef

Eagle Ford Group undivided

North of Hill County, shale, sandstone, and limestone; shale, bituminous, selenitic, with calcareous concretions and large septaria; sandstone and sandy limestone in upper and middle parts, platy, burrowed, medium to dark gray; in lower part bentonitic; hard limestone bed marks base in Ellis and Johnson Counties; locally forms low cuesta; thickness 200-300 feet

Kwb

Woodbine Formation

Sandstone, some clay and shale. Upper part, mostly sandstone, fine grained, well sorted, in part tuffaceous, ripple marked, large scale cross-bedding, reddish brown; near top some sandstone with large discoid concretions, medium to coarse grained, friable; some shale, jarositic, gray, fissile; some marine megafossils, oyster reefs locally. Middle part, mostly sandstone, fine grained, cross-bedded; some interbeds of clay, carbonaceous, in part sandy, gray to brown. Lower part, interbedded sandstone and clay; sandstone, fine grained, very thinly bedded to massive, some beds of ironstone and ironstone conglomerate, white, red, brown; clay, sandy, gray to brown; channeled locally. Thickness 175-250 feet, thickens northward

Kgm

Grayson Marl and Main Street Limestone undivided

Mostly Grayson Marl, mostly calcareous clay and marl, blocky, yellowish gray and medium gray; some 0.25-1.0-foot limestone beds in upper one-third, very fine grained, fossiliferous; weathers yellowish brown, forms gentle slope; thickness 60-100 feet, thins northward
Main Street Limestone, medium grained, chalky, some 6-8-foot units of calcareous shale, thin bedded to massive, distinctly bedded to wavy bedded and nodular, yellowish gray; weathers light gray to white; thickness 20-35 feet, thins northward

Upper Cretaceous

Lower Cretaceous

CRETACEOUS

Reference 31

United States
Environmental Protection
Agency

Office of Emergency and
Remedial Response
Washington DC 20460

EPA/540-R-92-021
PB92 - 963375
September 1992


Superfund

9345.1-05



Guidance for Performing Site Inspections Under CERCLA

Interim Final



Reference 32

Michelle Brown
Print Originator's Name
Ecology and Environment, Inc.

RECORD OF COMMUNICATION

| | |
|--|--|
| Conversation with: TPWD | Date: 08/03/99 (Mo) (Day) (Year) |
| Name: Ken Kosalski (spelling?) | Time: 2:30:00 AM/PM |
| Address: | <input checked="" type="checkbox"/> Originator Placed Call |
| Phone: 1-512-389-4505 | <input type="checkbox"/> Originator Received Call |
| Subject: fishing in the Trinity | |
| Discussion: Asked if he could give me an estimate of the pounds of fish caught from the Trinity, south of Dallas, each year. He said that TPWD does not keep any records of the amount of fish caught in rivers, only lakes (reservoirs). Suggested I call Clell Guest, a local Dallas official. 817-732-0761. | |
| Clell confirmed Ken's ^{2nd} response. No records available. | |
| Follow-Up-Action: | |
| Originator's Signature: Michelle Brown | |

Reference 33

Frederick Douglass Elementary School



Sorry, no photo
available yet...

226 N. Jim Miller Rd., 75217

| | |
|---------------------------|----------------------|
| Principal | Ellen Perry |
| Phone | 309-7180 |
| Parent Contact | Pat Rhoden |
| Phone | 391-9314 |
| Counselors | |
| Grades | PreK-3 |
| Enrollment | 570 |
| Average Class Size | 18 |
| School Colors | Red and black |
| Mascot | Dolphins |

School Sequence

Grades 4-6:

Burleson

Middle Schools:

Comstock

High Schools:

Spruce

Outstanding Features & Programs

- Bilingual
- Reading Is FUNdamental (RIF)
- Chapter I
- Special Education Resource Room
- Team Teaching
- Physical Education
- ESL
- Laureate
- Accelerated Learning Curriculum
- School-Centered Education
- Computer Program
- Texas Successful Schools Awards

Extracurricular Offerings

- Scouting program
- Field trips
- Jump for Heart


Special Incentives

- Award for good citizenship
- Field Day
- Award for perfect attendance

Faculty Information

- Outstanding teachers
- Many with advanced degrees
- Computer literate

W. A. Blair Elementary School



7720 Gayglen Drive, 75217

| | |
|---------------------------|---------------------------|
| Principal | Glenda Baylor |
| Phone | 309-7100 |
| Parent Contact | Wanda McBeth |
| Phone | 391-1376 |
| Grades | PreK-6 |
| Enrollment | 680 |
| Average Class Size | [K-4] 22, [5-6] 26 |
| School Colors | Black and gold |
| Mascot | Panther |

School Sequence

Middle Schools:

Comstock

High Schools:

Spruce

Outstanding Features & Programs

- Pre-kindergarten
- Special education
- Basics program
- Laureate Program
- Self-contained program
- Physical education (4-6)
- Math program
- Physical education (K-3)
- ESL class

Extracurricular Offerings

- Resource speakers
- Field trips
- Programs featuring pupils
- Junior Red Cross

Special Incentives

- Attendance Ribbons (six weeks)
- Field Day
- After School Recreation Program
- Spelling Bee Contest
- Awards assembly
- Honor Roll Awards

Faculty Information

- 47% advanced degrees

Reference 34

ST-96-20R Estimates of Housing Units, Households, Households by Age of
Householder, and Persons per Household: July 1, 1996

The documentation is located at the end of the data file.

These data supersede those released to the public with Press Release CB97-112, July 7, 1997
and data released with Product Announcement CB96-166.

Due to new information these estimates were revised. The revisions included small changes to the estimates of housing units and
the population per household. The household estimates were not affected.

Source: Population Estimates Program, Population Division, U.S. Bureau of the Census.

Contact: Statistical Information Staff, Population Division, U.S. Bureau of the Census.

Internet release date: July 7, 1997

Revised release date: August 21, 1997

(In thousands.)

| U.S., region, division, and state | Total housing units | Total house- holds | Households by age of householder | | | | | | Persons per household |
|--------------------------------------|---------------------------|--------------------------|----------------------------------|-------------------|-------------------|-------------------|-------------------|----------------------|-----------------------------|
| | | | 15 to 24 years | 25 to 34 years | 35 to 44 years | 45 to 54 years | 55 to 64 years | 65 years and over | |
| United States..... | 109,800 | 98,751 | 5,220 | 18,441 | 23,046 | 18,337 | 12,326 | 21,381 | 2.62 |
| Northeast..... | 21,530 | 19,298 | 719 | 3,433 | 4,454 | 3,651 | 2,475 | 4,567 | 2.60 |
| New England..... | 5,789 | 5,078 | 203 | 964 | 1,197 | 954 | 602 | 1,158 | 2.54 |
| Middle Atlantic..... | 15,742 | 14,219 | 516 | 2,469 | 3,256 | 2,697 | 1,873 | 3,409 | 2.61 |
| Midwest..... | 26,014 | 23,390 | 1,264 | 4,308 | 5,447 | 4,260 | 2,927 | 5,184 | 2.59 |
| East North Central..... | 18,047 | 16,339 | 843 | 3,021 | 3,825 | 3,023 | 2,061 | 3,567 | 2.60 |
| West North Central..... | 7,968 | 7,051 | 422 | 1,287 | 1,622 | 1,237 | 866 | 1,617 | 2.54 |
| South..... | 39,416 | 34,949 | 2,003 | 6,553 | 7,968 | 6,430 | 4,460 | 7,535 | 2.60 |
| South Atlantic..... | 20,774 | 18,146 | 935 | 3,391 | 4,102 | 3,331 | 2,286 | 4,102 | 2.56 |
| East South Central..... | 6,776 | 6,122 | 352 | 1,108 | 1,358 | 1,134 | 828 | 1,342 | 2.58 |
| West South Central..... | 11,866 | 10,681 | 716 | 2,054 | 2,508 | 1,965 | 1,347 | 2,091 | 2.67 |
| West..... | 22,840 | 21,113 | 1,233 | 4,147 | 5,177 | 3,997 | 2,463 | 4,096 | 2.71 |
| Mountain..... | 6,691 | 6,022 | 417 | 1,124 | 1,442 | 1,137 | 744 | 1,157 | 2.62 |
| Pacific..... | 16,149 | 15,092 | 816 | 3,023 | 3,735 | 2,861 | 1,719 | 2,939 | 2.75 |
| New England: | | | | | | | | | |
| Connecticut..... | 1,365 | 1,231 | 43 | 222 | 289 | 237 | 152 | 287 | 2.59 |
| Maine..... | 630 | 483 | 25 | 84 | 115 | 91 | 59 | 109 | 2.50 |
| Massachusetts..... | 2,547 | 2,322 | 88 | 457 | 536 | 432 | 273 | 536 | 2.53 |
| New Hampshire..... | 531 | 439 | 19 | 89 | 115 | 83 | 48 | 85 | 2.58 |
| Rhode Island..... | 427 | 378 | 16 | 70 | 86 | 67 | 43 | 96 | 2.53 |
| Vermont..... | 289 | 227 | 12 | 42 | 56 | 45 | 26 | 45 | 2.50 |
| Middle Atlantic: | | | | | | | | | |
| New Jersey..... | 3,186 | 2,889 | 84 | 492 | 689 | 569 | 380 | 674 | 2.71 |

| | | | | | | | | | |
|-------------------------|-------|-------|-----|-------|-------|-------|-----|-------|------|
| New York..... | 7,392 | 6,737 | 251 | 1,223 | 1,546 | 1,296 | 896 | 1,524 | 2.62 |
| Pennsylvania..... | 5,163 | 4,594 | 180 | 753 | 1,021 | 832 | 597 | 1,211 | 2.55 |
| East North Central: | | | | | | | | | |
| Illinois..... | 4,724 | 4,352 | 207 | 824 | 1,025 | 807 | 549 | 942 | 2.66 |
| Indiana..... | 2,444 | 2,209 | 123 | 414 | 510 | 408 | 283 | 472 | 2.57 |
| Michigan..... | 4,067 | 3,576 | 183 | 657 | 852 | 676 | 443 | 765 | 2.62 |
| Ohio..... | 4,594 | 4,260 | 225 | 769 | 978 | 782 | 550 | 956 | 2.56 |
| Wisconsin..... | 2,218 | 1,943 | 105 | 357 | 460 | 350 | 238 | 432 | 2.58 |
| West North Central: | | | | | | | | | |
| Iowa..... | 1,197 | 1,103 | 66 | 190 | 241 | 190 | 141 | 275 | 2.50 |
| Kansas..... | 1,109 | 982 | 65 | 180 | 226 | 171 | 116 | 224 | 2.54 |
| Minnesota..... | 1,981 | 1,763 | 98 | 341 | 434 | 318 | 206 | 366 | 2.58 |
| Missouri..... | 2,374 | 2,052 | 113 | 373 | 461 | 364 | 264 | 478 | 2.54 |
| Nebraska..... | 699 | 631 | 43 | 113 | 143 | 109 | 76 | 147 | 2.54 |
| North Dakota..... | 291 | 247 | 18 | 44 | 55 | 40 | 30 | 60 | 2.51 |
| South Dakota..... | 316 | 273 | 19 | 46 | 62 | 45 | 33 | 68 | 2.59 |
| South Atlantic: | | | | | | | | | |
| Delaware..... | 318 | 276 | 13 | 56 | 65 | 50 | 34 | 58 | 2.56 |
| District of Columbia... | 268 | 231 | 10 | 50 | 50 | 42 | 29 | 50 | 2.17 |
| Florida..... | 6,771 | 5,648 | 274 | 920 | 1,161 | 940 | 714 | 1,640 | 2.50 |
| Georgia..... | 3,021 | 2,723 | 164 | 575 | 665 | 526 | 327 | 465 | 2.64 |
| Maryland..... | 2,049 | 1,871 | 74 | 370 | 471 | 373 | 228 | 356 | 2.65 |
| North Carolina..... | 3,197 | 2,796 | 157 | 547 | 628 | 514 | 362 | 589 | 2.54 |
| South Carolina..... | 1,604 | 1,376 | 75 | 258 | 311 | 262 | 182 | 289 | 2.62 |
| Virginia..... | 2,752 | 2,511 | 131 | 511 | 603 | 489 | 308 | 469 | 2.56 |
| West Virginia..... | 793 | 714 | 38 | 104 | 148 | 135 | 103 | 187 | 2.50 |
| East South Central: | | | | | | | | | |
| Alabama..... | 1,814 | 1,624 | 96 | 290 | 354 | 296 | 221 | 367 | 2.58 |
| Kentucky..... | 1,638 | 1,478 | 85 | 265 | 330 | 275 | 201 | 322 | 2.56 |
| Mississippi..... | 1,083 | 979 | 57 | 176 | 216 | 175 | 133 | 222 | 2.70 |
| Tennessee..... | 2,240 | 2,041 | 114 | 377 | 459 | 388 | 273 | 431 | 2.54 |
| West South Central: | | | | | | | | | |
| Arkansas..... | 1,077 | 951 | 59 | 162 | 195 | 169 | 130 | 236 | 2.58 |
| Louisiana..... | 1,780 | 1,572 | 96 | 283 | 364 | 294 | 211 | 324 | 2.69 |
| Oklahoma..... | 1,453 | 1,265 | 88 | 218 | 272 | 226 | 170 | 291 | 2.54 |
| Texas..... | 7,556 | 6,894 | 473 | 1,391 | 1,677 | 1,276 | 836 | 1,240 | 2.71 |
| Mountain: | | | | | | | | | |
| Arizona..... | 1,890 | 1,687 | 114 | 323 | 381 | 299 | 204 | 366 | 2.57 |
| Colorado..... | 1,640 | 1,502 | 96 | 282 | 391 | 306 | 182 | 246 | 2.49 |
| Idaho..... | 481 | 430 | 35 | 73 | 100 | 81 | 54 | 86 | 2.72 |
| Montana..... | 377 | 341 | 23 | 50 | 80 | 67 | 46 | 75 | 2.51 |
| Nevada..... | 691 | 619 | 36 | 122 | 145 | 119 | 83 | 115 | 2.54 |
| New Mexico..... | 711 | 619 | 39 | 108 | 151 | 118 | 81 | 122 | 2.72 |
| Utah..... | 692 | 639 | 60 | 138 | 149 | 110 | 71 | 112 | 3.08 |
| Wyoming..... | 209 | 184 | 15 | 28 | 46 | 36 | 24 | 35 | 2.56 |

| | | | | | | | | | |
|-----------------|--------|--------|-----|-------|-------|-------|-------|-------|------|
| Pacific: | | | | | | | | | |
| Alaska..... | 242 | 214 | 17 | 41 | 64 | 49 | 24 | 20 | 2.75 |
| California..... | 11,827 | 11,101 | 574 | 2,306 | 2,747 | 2,067 | 1,253 | 2,153 | 2.81 |
| Hawaii..... | 433 | 389 | 16 | 61 | 96 | 79 | 49 | 87 | 2.96 |
| Oregon..... | 1,343 | 1,249 | 76 | 209 | 294 | 248 | 150 | 273 | 2.51 |
| Washington..... | 2,304 | 2,139 | 133 | 407 | 532 | 417 | 242 | 406 | 2.53 |

Note: Consistent with April 1, 1990 census counts, which include count question resolution corrections processed through December 199.

Documentation notes:

Age - The age of individuals is in terms of age at their last birthday.

Census Regions and Divisions - The Census Bureau delineates two sets of sub-national regions that are formed of states. This two-tiered system of regions consists of 9 census divisions nested in 4 census regions. The Northeast region includes the New England division: Connecticut, Maine, Massachusetts, New Hampshire, Rhode Island, and Vermont; and the Middle Atlantic division: New Jersey, New York, and Pennsylvania. The Midwest region includes the East North Central division: Illinois, Indiana, Michigan, Ohio, and Wisconsin; and the West North Central division: Iowa, Kansas, Minnesota, Missouri, Nebraska, North Dakota, and South Dakota. The South region includes the South Atlantic division: Delaware, District of Columbia, Florida, Georgia, Maryland, North Carolina, South Carolina, Virginia, West Virginia; the East South Central division: Alabama, Kentucky, Mississippi, and Tennessee; and the West South Central division: Arkansas, Louisiana, Oklahoma, and Texas. The West region includes the Mountain division: Arizona, Colorado, Idaho, Montana, Nevada, New Mexico, Utah, and Wyoming; and the Pacific division: Alaska, California, Hawaii, Oregon, and Washington.

Household - A household includes all persons who occupy a housing unit. A household consists of a single family, one person living alone, two or more families living together, or any other group of related or unrelated persons who share living arrangements.

Householder - One person in each household is designated as the householder. In most cases, this is the person, or one of the persons, in whose name the home is owned, being bought, or rented. If there is no such person in the household, any adult household member 15 years old and over could be designated as the householder.

Housing Unit (Census) - A housing unit is a house, an apartment, a mobile home, a group of rooms, or a single room that is occupied (or if vacant, is intended for occupancy) as separate living quarters. Separate living quarters are those in which the occupants live and eat separately from any other persons in the building and which have direct access from the outside of the

building or through a common hall. The April 1, 1990 census count of housing units is the number of housing units in an area as reported in the 1990 Census of Housing, or as subsequently revised. Revisions to an area's 1990 census count of housing units may occur as the result of (1) post-1990 census corrections of political boundaries, geographic misallocations, or documented underenumerations or overenumerations, and (2) geographic boundary updates made subsequent to the 1990 census, which include annexations, new incorporations, mergers, etc. The closing date for these two forms of revisions applied to this set of estimates was December, 1994.

Housing Unit (Estimate) - Estimates of the number of housing units are calculated by updating the number of housing units from the 1990 census with data on subsequent gains and losses to the housing inventory. The main data sources for estimating these gains and losses are construction and demolition permits. For areas where permit data are not available, alternative methods are used to estimate the construction and demolition of units. Additional information on the methodology used to produce these housing unit estimates is contained at our Internet site with a URL of <<http://www.census.gov/population/www/methodep.html>>.

Persons per Household - The number of persons per household is obtained by dividing the number of persons in households by the number of households (or householders).

Population (Census) - The April 1, 1990 census population is a count of the number of persons residing in an area (resident population) as reported in the 1990 Census of Population, or as subsequently revised. Revisions to an area's 1990 census population count may occur as the result of (1) post-1990 census corrections of political boundaries, geographic misallocations, or documented underenumerations or overenumerations, and (2) geographic boundary updates made subsequent to the 1990 census, which include annexations, new incorporations, mergers, etc. The closing date for these two forms of revisions applied to this set of estimates was December, 1994.

Population (Estimate) - The estimated population is the computed number of persons living in an area (resident population) as of July 1. The estimated population is calculated from a demographic components of change model that incorporates information on natural change (births and deaths) and net migration (net domestic migration and net movement from abroad) that has occurred in the area since the reference date, such as April 1, 1990, the date of the 1990 census. Additional information on the methodology used to produce these population estimates is contained in Current Population Reports P25-1127 and at our Internet site with a URL of <<http://www.census.gov/population/www/methodep.html>>.